



NOTES:

1. EXISTING STONE WALL IS APPROX. 208 FEET LONG AND HAS A TYPICAL WIDTH OF APPROX. 1.5 FEET WIDE AT THE TOP BY 2 FEET WIDE AT THE BOTTOM, WITH A TYPICAL HEIGHT OF APPROX. 4 FEET ABOVE GRADE.
2. APPROX. 50% OF THE WALL (FRONT & BACK) NEEDS REPAIR WHICH INCLUDES BUT IS NOT LIMITED TO TUCKPOINTING LOOSE AND/OR CRACKED MORTAR JOINTS, RESETTING OR REPLACING LOOSE OR MISSING/BROKEN STONES, REALIGNING/RESETTING LOOSE LIMESTONE CAPS AND RESEALING THEIR JOINTS.
3. CLEAN AND REUSE EXISTING STONES AS MUCH AS POSSIBLE. PROVIDE NEW MATCHING STONES AS NEEDED TO FULLY COMPLETE THE WALL REPAIR WORK BACK TO ORIGINAL CONDITION MATCHING ADJACENT UNDISTURBED AREA.
4. ALL NEW MORTAR FOR THIS WALL PROJECT SHALL HAVE THE COLOR MATCH WITH THE EXISTING AGED MORTAR AS CLOSELY AS POSSIBLE.
5. COMPLETE AN INITIAL TEST SECTION OF WALL TUCKPOINTING AND OBTAIN COR APPROVAL FOR COLOR AND WORKMANSHIP PRIOR TO PROCEEDING WITH THE ENTIRE PROJECT.
6. SURFACE FINISH TOOLING PATTERN OF ALL RETUCK POINTED JOINTS TO MATCH EXISTING SURFACE FINISH TOOLING PATTERN OF THE ADJACENT EXISTING AREAS OF THE MONUMENT STONE WALL. COMPLETED WORK TO VISUALLY MATCH AND BLEND WITH SURROUNDING MONUMENT STONE WALL IN COLOR AND TEXTURE AND PATTERN.



PROJECT AREA – FLAG POLE MONUMENT WALL



EXAMPLE OF LIMESTONE CAP REQUIRE RESETTING AND JOINT RESEALING (REMOVE OLD SEALANT)



EXAMPLE OF BROKEN STONE TO BE REPLACED, LIMESTONE CAP TO BE RESET AND JOINT TO BE RESEALED (REMOVE OLD SEALANT)



EXAMPLES OF CRACKED MORTAR JOINT REQUIRE TUCK POINTING AND LIMESTONE CAP REQUIRE JOINT RESEALING (REMOVE OLD SEALANT)



EXAMPLES OF LOOSE STONES REQUIRE RESETTING

**FINAL FOR CONSTRUCTION**  
**JUNE 16, 2015**

				<div>one inch = one hundred feet</div> <div></div>		<div></div> <div>NATIONAL CEMETERY ADMINISTRATION</div>		<div>Project Title</div> <div>SITE PLAN - FLAG POLE STONE WALL</div>		<div>Project Title</div> <div>REPAIR PAVEMENT, STONE WALLS &amp; WALKWAY</div>		<div>Date</div> <div>6/16/2015</div>					
								<div>Approved: Division Chief</div>		<div>Building Number</div> <div>*****</div>		<div>Checked</div>		<div>Drawn</div> <div>RNE</div>		<div>Project No.</div> <div>774CM3915-002</div>	
								<div>Approved: Service Director</div>		<div>Location</div> <div>FORT CUSTER NATIONAL CEMETERY</div>		<div>DRAWING NO.</div> <div>L-2</div>		<div>Dwg. 3 Of 5</div>			
Revisions		Date															