

January 14, 2016

Mr. Patrick Wee
Contracting Officer Representative
Project & Construction Management
VA Central CA Health Care System
2615 E. Clinton Ave., Fresno CA 93703



ARCHITECTURE
P L A N N I N G
INTERIOR DESIGN

235 PINE STREET
17TH FLOOR
SAN FRANCISCO
CALIFORNIA 94104

TEL 415.397.3117
FAX 415.397.1517
WWW.POLYTECHAE.COM

RE: **Expand Community Living Center Building 31 – Phase 1**
Project No: 570-218
Addendum No. 2 01-14-2016

Addendum No. 2 - Narrative of Changes:

Below are document changes to the 100% Construction Document Submission dated January 14, 2016.

DRAWINGS		
Document #	Revisions	Description
AS201C	Delta 1	<ul style="list-style-type: none">• Add missing fixture type to light fixture.• Change fixture type T for fixture type Z under wall cabinet in Kitchen/Servery 1D03A and 1E12A.• Clarify single window shade at Nurse break room 1D15 and 1E04.
AS401	Delta 1	<ul style="list-style-type: none">• Add dimensions for drapery panel and add bracket for drapery rod on elevation 3.
AS601A	Delta 1	<ul style="list-style-type: none">• Add missing fixture type to light fixture.• Change fixture type T for fixture type Z under wall cabinet Kitchen/Servery 1D03A.• Clarify single window shade at Nurse break room 1D15
AS601B	Delta 1	<ul style="list-style-type: none">• Add missing fixture type to light fixture• Change fixture type T for fixture type Z under wall cabinet Kitchen/Servery 1D03A and 1E12A.• Clarify single window shade at Nurse break room 1D15 and 1E04.• Add missing dual window shade at Resident Bedroom.
AS720	Delta 1	<ul style="list-style-type: none">• Revise detail 3 to add drapery bracket and wood pole.• Add detail 4 Rolling Single Shade at Window Head.
AF201	Delta 1	<ul style="list-style-type: none">• Coordinate Room Material and Finish Schedule with Finish Plan.
PP202	Delta 1	<ul style="list-style-type: none">• Relocated 3" CW entrance into building & meter location.• Added shut off valve and resized 2-1/2" main to 3".
ES001	Delta 1	<ul style="list-style-type: none">• Added Fixture Type Z to the Luminaire Schedule.• Revised voltage for fixture type A.• Revised Voltage for fixture type T.

EL201	Delta 1	<ul style="list-style-type: none"> Added Fixture Type Z and switch control to the plan Added Fixture Type D1 and switch control to the plan. Added Fixture Type D and switch control to the plan. Added switch controls for corridor fixtures type A. Added PC sensor for Dining Area 1D03.
EL202	Delta 1	<ul style="list-style-type: none"> Added Fixture Type Z and switch control to the plan Added switch control for fixtures type D, D1 to the plan Added switch controls for corridor fixtures type A. Added homerun 1NH1-7.
ES501	Delta 1	<ul style="list-style-type: none"> Added Fixture Type D1 low voltage control switches to the Lighting Relay Panel Schedule. Updated Lighting Control Relay Panel Schedule.
SPECIFICATIONS		
01 81 12		<ul style="list-style-type: none"> Revise 01 81 12 3.1D to read "Measurement and verification period shall cover at least two years of postconstruction occupancy by Owner".
12 24 00		<ul style="list-style-type: none"> Revise 12 24 00 window coverings for shade type used.

Please let me know if you have any questions.

Sincerely,



Don Williams, AIA
 Architect/Associate
 POLYTECH ASSOCIATES INC.
 235 Pine Street, 17th Floor
 San Francisco, CA 94104
 Direct: (415) 926-6718
 e-mail: dwilliams@polytechae.com