

5 INTERIOR PHOTOGRAPH
A-110 NOT TO SCALE

1 FLOOR PLAN
A-110 1/4" = 1'-0"



08-04	REPLACE EXIT DEVICES WITH EXIT-ONLY SVR EXIT DEVICES ON INACTIVE LEAF
08-05	REPAIR EXISTING HOLLOW METAL DOOR JAMB, INSTALL NEW DOOR, PAINT DOOR TO MATCH EXISTING
08-13	AT ACTIVE LEAF, ADD MORTISE EXIT DEVICE WITH STAND ALONE KEYPAD TRIM
08-16	(2) HINGE - PEMKO - CFMXXHD (VERIFY HEIGHT) (2) PUSH BAR - CORBIN RUSSWIN - ED5470 N85S M5S 630 (2) CLOSER - CORBIN RUSSWIN - DC6210 A12 689 (2) CYLINDERS - CORBIN RUSSWIN (2) KICKPLATE - ROCKWOOD - 1050 10"X2" LDW US32D (1) THRESHOLD - PEMKO - 171A (1) WEATHERSTRIP - PEMKO - 303AS (1) SWEEP - PEMKO - 315CN



