

**FIXTURE NOTES:**

- CONTRACTOR SHALL PROVIDE SUITABLE TRIM AND APPURTENANCES TO MOUNT FIXTURES IN TYPE OF CEILING OR WALL AS SPECIFIED IN ARCHITECTURAL FINISH SCHEDULES REGARDLESS OF CATALOG NUMBER GIVEN. CONTRACTOR SHALL VERIFY TYPE OF CEILING OR WALL BY REVIEWING ARCH. FINISH SCHEDULES AND ORDER NECESSARY KIT IF SO NEEDED.
- FIXTURES SHALL MEET LUMINAIRE DISCONNECT REQUIREMENTS AS SPECIFIED IN NEC 410.130(G).
- FIXTURES SHALL BE SUPPORTED FROM THE STRUCTURE OR AS APPROVED BY THE COR.
- NOT USED.
- COMPLETE REQUIREMENTS FOR LIGHT FIXTURES ARE NOT BASED ON CATALOG NUMBERS ALONE BUT ALSO SHALL INCLUDE THE DESCRIPTION, NOTES AND DEMONSTRATED USE ON THE DRAWINGS. ANY CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- ALL LED LIGHT FIXTURES SHALL BE EQUIPPED FOR BOTH 0-10V DIMMING AS WELL AS LINE-VOLTAGE SWITCHING OPERATION, UNLESS OTHERWISE NOTED. WHERE DIMMING SWITCH IS SHOWN CONTROLLING LED LIGHT FIXTURES, PROVIDE COMPATIBLE SWITCH AND 0-10V WIRING.

TYPE	MANUFACTURERS	CATALOG INFORMATION	LAMP DATA		BALLAST DATA		INPUT WATTS	VOLTAGE	MOUNTING	FIXTURE DESCRIPTION	REMARKS
			NO.	TYPE	NO.	TYPE					
A02	COLUMBIA H.E. WILLIAMS LITHONIA OR APPROVED EQUAL	LLT24 SERIES 50 SERIES TL SERIES		LED-35K			52		RECESSED	2'X4' RECESSED LED STATIC TROFFER, STEEL HOUSING, FLUSH STEEL DOOR, 0.125" A-12 ACRYLIC PRISMATIC LENS, PAF 4700 LUMEN, 3500K, SPRING LOADED LATCHES.	RECESSED IN GRID OR GYPSUM CEILING. REFER TO ARCHITECTURAL RCP PLANS. 4" MINIMUM DEPTH. CAT. NO. LLT24-35MLG-FSA12F-XU-PAF
A03	COLUMBIA H.E. WILLIAMS LITHONIA OR APPROVED EQUAL	LLT24 SERIES 50 SERIES TL SERIES		LED-35K			36		RECESSED	2'X2' RECESSED LED STATIC TROFFER, STEEL HOUSING, FLUSH STEEL DOOR, 0.125" A125 ACRYLIC PRISMATIC LENS, PAF 3300 LUMEN, 3500K, SPRING LOADED LATCHES.	RECESSED IN GRID OR GYPSUM CEILING. REFER TO ARCHITECTURAL RCP PLANS. 4" MINIMUM DEPTH. CAT. NO. LLT24-35MLG-FSA12F-XU-PAF
A05	COLUMBIA H.E. WILLIAMS LITHONIA METALUX CZ SERIES	L5ER24 SERIES HETL SERIES ALL SERIES		LED-35K			52		RECESSED	2'X4' RECESSED LED ARCHITECTURAL TROFFER STEEL HOUSING, CONTOUR LENSED DIFFUSER 3500K, 6100 LUMENS, WHITE FINISH, PAINT AFTER FABRICATION.	RECESSED IN GRID OR GYPSUM CEILING. REFER TO ARCHITECTURAL RCP PLANS. 4" MINIMUM DEPTH. CAT. NO. L5ER24-35HLG-C-XU-PAF
A07	COLUMBIA H.E. WILLIAMS LITHONIA METALUX CZ SERIES	L5ER22 SERIES HETL SERIES ALL SERIES		LED-35K			41		RECESSED	2'X4' RECESSED LED ARCHITECTURAL TROFFER STEEL HOUSING, CONTOUR LENSED DIFFUSER 3500K, 3600 LUMENS, WHITE FINISH, PAINT AFTER FABRICATION.	RECESSED IN GRID OR GYPSUM CEILING. REFER TO ARCHITECTURAL RCP PLANS. 4" MINIMUM DEPTH. CAT. NO. L5ER22-35HLG-C-XU-PAF
A09	COLUMBIA H.E. WILLIAMS LITHONIA METALUX CZ SERIES	L5ER24 SERIES HETL SERIES ALL SERIES		LED-35K			41		RECESSED	2'X4' RECESSED LED ARCHITECTURAL TROFFER STEEL HOUSING, CONTOUR LENSED DIFFUSER 3500K, 4200 LUMENS, WHITE FINISH, PAINT AFTER FABRICATION.	RECESSED IN GRID OR GYPSUM CEILING. REFER TO ARCHITECTURAL RCP PLANS. 4" MINIMUM DEPTH. CAT. NO. L5ER24-35LWG-C-XU-PAF
B01	PRUDENTIAL OR APPROVED EQUAL	P8920 SERIES		LED-35K			54		RECESSED	24" ROUND, RECESSED LED SKYLIGHT FIXTURE, DIE-FORMED STEEL HOUSING, FROSTED ACRYLIC LENS, 0-10V DIMMING, 3150 LUMENS, 3500K, PAF.	RECESSED IN GRID OR GYPBOARD CEILING. SEE ARCH. FINISH SCHEDULE FOR CEILING TYPE. CAT. NO. P8920-LED35MO-CWA-TMW-SC-UNV-X
E01	H.E. WILLIAMS CHLORIDE DUAL-LITE LIGHTOLIER	EXIT/CA SERIES CAD SERIES SC SERIES LDS SERIES		LED-35K			4		AS NOTED	LED EXIT SIGN, WHITE CAST ALUMINUM HOUSING, RED LETTERS, UNIVERSAL MOUNTING DIR. ARROWS & FACES AS INDICATED.	NFPA 101 CHEVRONS, WIRED AHEAD OF LOCAL SWITCH, DUAL INPUT VOLTAGE. AC ONLY - NO BATTERY. CAT. NO. EXIT/CA-**-R-WF-WHT-AC
F14	H.E. WILLIAMS EQ. LIGHTOLIER EQ. GOTHAM EQ. PRESQUITE	ICLEDPSL60		LED-35K			18		RECESSED	6" DIA. LED SHOWER LIGHT, 1300 LUMENS 3500K, WHITE ALUM. REFLECTOR, UL WET LOCATION, BAR HANGERS, DROP OPAL POLYCARBONATE LENS.	
F25	OR APPROVED EQUAL	8VLF5 SERIES		LED-35K			38		RECESSED	6" DIA. OPEN LED DOWNLIGHT, MIN. 2000 LUMENS, 3500K, LOW IRIDESCENT SILVER HAZE REFLECTOR, BAR HANGERS PRE-WIRED J-BOX, OPAL ACRYLIC.	PROVIDE WITH 10% DIMMING CAPABILITY CAT. NO. 8VLF5-2000-35K-M-HAZ
G14	BETA-CALCO ARVO OR APPROVED EQUAL	30 G121-PM		LED-35K			8	120	WALL	LED WALL SCONCE, WHITE BRUSHED ALUMINUM SHADE FINISH	CAT. NO. D1140-LED6-120-MG-MG
G15	BROWNLEE OR APPROVED EQUAL	5542		LED-35K			17		WALL	26" DECORATIVE LED WALL BRACKET, SATIN NICKEL FINISH, FROSTED GLASS DIFFUSER	MOUNT OVER VANITY MIRROR. REFER TO ARCHITECTURAL ELEVATIONS FOR MOUNTING HEIGHT
G16	KIRLUN OR APPROVED EQUAL	RNO0869		LED-35K			3		WALL	LED PATIENT ROOM NIGHT LIGHT LOW PROFILE, CLEAR ACRYLIC PRISMATIC LENS, ALUMINUM FRAME.	3" DEPTH HOUSING, GASKETED BETWEEN DOOR AND FRAME, TAMPER RESISTANT, WHITE FINISH, MOUNT AT 18" AFF.

REVISION NO.	REVISION DESCRIPTION	By	Date
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

**Department of Veterans Affairs**  
**Create a Pulmonary Area with Sleep Labs**  
 2300 Ramsey St.  
 Fayetteville, NC. 28301



Architect/Engineer Address

**HARRELL**  
 DESIGN GROUP, P.C.

8016 TOWER POINT DRIVE  
 CHARLOTTE, NC 28227

P 704.814.1320  
 F 704.321.0833

WWW.HARRELLDG.COM

COPYRIGHT © 2015 HARRELL DESIGN GROUP, PC  
 HEG PROJECT # 13008

Recommended Approvals:	
1. MEDICAL DIRECTOR	6. OPERATIONS SERVICE LINE MANAGER
2. ASSOCIATE DIRECTOR	7. INFECTION CONTROL MANAGER
3. CHIEF OF STAFF	8. SAFETY MANAGER
4. ASSOC. DIRECTOR	9. GENERAL ENGINEER
5. SERVICE LINE MGRS.	10. COR

Drawing Title  
**LIGHTING FIXTURE SCHEDULE**

FINAL SUBMISSION

Project Title  
**CREATE A PULMONARY AREA WITH SLEEP LABS**

Drawn: [Signature]  
 Building Number: 1  
 AutoCAD File Name: [Blank]  
 Checked: [Signature]  
 Reviewed: [Signature]  
 Const. Contract No.: [Blank]

Date: 11/13/2015  
 Project Number: 565-13-111  
 Drawing No.: **E002**

