

QUESTIONS 1-4 AND ANSWERS

- 1. Drawing A-302 detail 1 & 8 show a cut thru of counter. There is no spec. for the countertop nor do we see where on drawings it calls for a new counter. **Answer:** Yes the counter is part of the project. New 14'-6"X2'-1" solid surface countertop with solid-surface base.
·
2. Drawing A-101 shows the counter by a dotted line, but there is no notes telling us to install this counter. (Is counter part of this contract?) **Answer:** Yes the counter is part of the project, the drawings will be corrected. The details for the counter is 8/A-302.
3. Drawing AD-101 & 3AD-101 there is a demo note T located in corridor outside rooms 3A-121 & 125. There is no note T in the list of demo notes. What is note T for? **Answer:** It is for the removal of existing handrails. A new general demolition note (12) sketch will be added to sheets AD-101 and 3 AD-101 which will read: "All existing handrails located in corridors with new work shall be removed and stored at the direction of the Contracting Officer Representative." In addition a new finish note (15) will be added to the sketch for A-101 and Pr A-101 Noting: "New handrails meeting current Philadelphia VAMC interior requirements shall be mounted to match current handrail locations and heights."
4. Question - will this be done by owner? (There are no details) **Answer:** This will be sent to the A/E for clarification today. **CO Answer:** Assume this will be provided by contractor unless another amendment is posted to say otherwise.