

SECTION 26 25 11
BUSWAYS

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, connection, and testing of busways for use in electrical systems rated 600 V and below.

1.2 RELATED WORK

- A. Section 07 84 00, FIRESTOPPING: Sealing around busway penetrations to maintain the integrity of fire-resistant rated construction.
- B. Section 07 92 00, JOINT SEALANTS: Sealing around busway penetrations through the building envelope to prevent moisture migration into the building.
- C. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- D. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path to ground for possible ground fault currents.
- E. Section 26 24 16, PANELBOARDS: Circuit breakers for use in plug-in busway.
- F. Section 26 29 21, ENCLOSED SWITCHES AND CIRCUIT BREAKERS: Switches and fuses for use in plug-in busway.

1.3 QUALITY ASSURANCE

- A. Refer to Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES), in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

1.4 SUBMITTALS

- A. Submit six copies of the following in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

1. Shop Drawings:

- a. Submit sufficient information to demonstrate compliance with drawings and specifications.
- b. Submit the following data for approval:
 - 1) Electrical ratings, dimensions, mounting details and position, mounting method, vertical supports, materials, fire stops, and weatherproofing.
 - 2) Detailed coordinated connections to equipment terminations such as switchgear, switchboards, and transformers.
 - 3) Coordination Drawings: Submit floor plans and sections, drawn to scale. Include bus assembly layouts and relationships between components and adjacent structural, mechanical, and electrical elements. Indicate vertical and horizontal

enclosed busway runs, offsets, transitions, and clearances for access above and to the side of enclosed busways. Indicate vertical elevation of busway above the floor or bottom of structure. Indicate support locations, type of support, and weight on each support.

- c. Certification from the manufacturer that representative busway has been seismically tested to International Building Code requirements. Certification shall be based upon simulated seismic forces on a shake table or by analytical methods, but not by experience data or other methods.

2. Manuals:

- a. Submit complete maintenance and operating manuals including technical data sheets, and information for ordering replacement parts.

- 1) Include information for testing, repair, troubleshooting, assembly, and disassembly.

- b. If changes have been made to the maintenance and operating manuals originally submitted, submit updated maintenance and operating manuals two weeks prior to the final inspection.

3. Certifications: Two weeks prior to final inspection, submit the following.

- a. Certification by the manufacturer that the busway conforms to the requirements of the drawings and specifications.
- b. Certification by the Contractor that the busway has been properly installed, adjusted, and tested.

1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplement and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.

B. International Code Council (ICC):

IBC-12.....International Building Code

C. National Electrical Manufacturers Association (NEMA):

BU 1-02.....Busways

BU 1.1-10.....General Instructions for Handling,
Installation, Operation and Maintenance of
Busway Rated 600 Volts or Less

BU 1.2-08.....Application Information for Busway Rated 600
Volts or Less

D. National Fire Protection Association (NFPA):

70-11.....National Electrical Code (NEC)

E. Underwriters Laboratories Inc. (UL):

857-09.....Busways

PART 2 - PRODUCTS

2.1 MATERIAL

A. Busway shall be in accordance with NEMA and UL.

B. Busway shall be rated as shown on the drawings.

C. Busway shall have the following features:

1. For indoor locations; feeder type, totally enclosed and moisture resistant.
2. Short circuit current rating shall not be less than 10,000 (120-208 volt systems) and 14,000 (277-480 volt systems).
3. 3-phase, 4-wire, with full rated neutral conductor.
4. Internal 50%-rated ground bus bar. Busway housing is not allowed to serve as the equipment grounding conductor.
5. All bus bars, phase, neutral, and ground, for each busway shall be within a single housing.
6. Bus Bars:
 - a. Shall be full round edge rectangular copper of sufficient cross-section to provide full current rating without exceeding a temperature rise of 55° C above a 40° C ambient.
 - b. Interconnection joints shall be tin or silver plated, with steel bolts, nuts, and Belleville washers.
 - c. Shall be completely insulated with flame-retardant, track-resistant, self-extinguishing insulation.
7. Housings:
 - a. Shall be steel or aluminum, with continuous mounting rails.
 - b. Shall be thoroughly cleaned and painted at the factory with primer and the manufacturer's standard finish.
 - c. Shall have rustproof metal hardware.
 - d. Provide external flanges and weatherproofing at busway entrances to buildings.
 - e. For busways that pass through fire-resistant rated construction, incorporate listed fire stops within the busway housings and external flanges.

- f. Install expansion fittings in the busway runs in compliance with the manufacturer's standard recommendations.
 - g. The temperature rise at any point on the housing shall not exceed 30° C above an ambient temperature of 40° C.
- 8. Busway shall not be reduced in size at any point.
- 9. Provide manufacturer's fittings and accessories, including but not limited to elbows, tees, tap boxes, transformer taps, end boxes, expansion fittings, offsets, adapters, hangers, and mounting hardware.
- D. Dimensions and Configuration:
 - 1. Configure within the space designated for busway installation.
 - 2. Coordinate busway routing with equipment installation by other trades to avoid conflicts.
 - 3. Make final field measurements and check them with the busway coordination drawings prior to authorization of fabrication of the busways.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install busways as required by the NEC and the manufacturer's requirements.
- B. Support busways as required by the NEC and as required by manufacturer's shop drawings.
- C. Coordinate all of the busway terminations to equipment to ensure proper phasing.
- D. Tighten bolted connections with a torque wrench to values as required by the manufacturer.
- E. Install expansion fittings at locations where busways cross building expansion joints. Install at other locations so distance between expansion fittings does not exceed manufacturer's recommended distance between fittings.
- F. Install fire-stop assemblies per Section 07 84 00, FIRESTOPPING where busways penetrate fire-resistant construction.
- G. Install weatherproofing fittings and flanges where busways penetrate exterior elements such as walls or roofs. Seal around openings to make weathertight according to Section 07 92 00, JOINT SEALANTS.

3.2 ACCEPTANCE CHECKS AND TESTS

- A. Perform manufacturer's required field tests in accordance with the manufacturer's recommendations. In addition, include the following:
 - 1. Visual Inspection and Tests:

- a. Compare equipment nameplate data with specifications and approved shop drawings.
- b. Inspect physical, electrical, and mechanical condition.
- c. Verify appropriate anchorage, required area clearances, and correct alignment.
- d. Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey after energization.
- e. Verify appropriate equipment grounding.
- f. Examine outdoor busways for removal of weep-hole plugs, if applicable, and the correct installation of joint shield.

2. Electrical Tests:

- a. After installation, test busway phase-to-phase and phase-to-ground resistance with an insulation resistance tester.

Resulting values shall not be less than one megohm.

3.3 FOLLOW-UP VERIFICATION

- A. Upon completion of acceptance checks and tests, the Contractor shall show by demonstration in service that the busway is in good operating condition and properly performing the intended function.
- B. After the busways have been energized for not less than 30 days, repeat the torque wrench tightening of all bolt connections.

---END---