



- GENERAL NOTES:**
SEE SHEET M1001 FOR GENERAL NOTES
- KEY NOTES:**
- 1 20/12 TRANSFER DUCT.
 - 2 RECESSED CABINET FAN COIL WITH CEILING PLATE, ELECTRIC HEAT, TRIM FLANGE MOUNT AND BOTTOM RETURN.
 - 3 EXISTING AIR DEVICE.
 - 4 ROUND SUPPLY UP TO BELL MOUTH AT AC-49.
 - 5 CONTINUOUS SLOT DIFFUSER.
 - 6 ECCENTRIC TRANSITION.
 - 7 EXHAUST AIR UP.
 - 8 RETURN AIR UP.
 - 9 VERIFY EXACT LENGTH PROVIDE FLAT BLANK, BLANK-OFF OVER UNUSED PORTIONS OF SLOT DIFFUSER.
 - 10 EMERGENCY 100% EXHAUST SWITCH.
 - 11 COOLING ONLY VAV BOX.
 - 12 VISUAL ONLY BALL-IN-WALL INDICATOR (NEGATIVE ROOM APPLICATION) EQUALTO AIRFLOW DIRECTION INC. MODEL ADI-69-V-N.
 - 13 VAV EXHAUST TERMINAL.
 - 14 CAV EXHAUST TERMINAL.
 - 15 EXHAUST DUCT ABOVE (SHOWN DASHED FOR CLARITY).
 - 16 SIZE DUCTWORK TO MATCH FULL VAV DISCHARGE SIZE.

1 ENLARGED FIRST FLOOR HVAC PLAN
1/4" = 1'-0"

