7/29/09

Solicitation No.VA-\_

Imaging Center Project No.: 589-999 Department of Veterans Affairs Harry S. Truman Memorial Veterans Hospital Columbia, Missouri

# SECTION 09 65 13 RESILIENT BASE AND ACCESSORIES

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies the installation of vinyl or rubber base and resilient stair treads with sheet rubber flooring on landings.

### 1.2 RELATED WORK

- A. Color and texture: as indicated on the finish schedule.
- B. Integral base with sheet flooring: Section 09 65 16, RESILIENT SHEET FLOORING.

#### 1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Description of each product.
  - 2. Base material manufacturer's recommendations for adhesives.
  - 3. Application and installation instructions.
- C. Samples:
  - 1. Base: 150 mm (6 inches) long, each type and color.
  - 2. Sheet Rubber Flooring: 300 mm (12 inches) square.
  - 3. Adhesive: Literature indicating each type.

### 1.4 DELIVERY

- A. Deliver materials to the site in original sealed packages or containers, clearly marked with the manufacturer's name or brand, type and color, production run number and date of manufacture.
- B. Materials from containers which have been distorted, damaged or opened prior to installation will be rejected.

### 1.5 STORAGE

- A. Store materials in weather tight and dry storage facility.
- B. Protect material from damage by handling and construction operations before, during, and after installation.

### **1.6 APPLICABLE PUBLICATIONS**

- A. The publication listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society for Testing and Materials (ASTM): F1344-04.....Rubber Floor Tile

Imaging Center Project No.: 589-999 Solicitation No.VA-\_ Department of Veterans Affairs Harry S. Truman Memorial Veterans Hospital Columbia, Missouri

F1859-04.....Rubber Sheet Floor Covering without Backing
F1860-04....Rubber Sheet Floor Covering with Backing
F1861-02....Resilient Wall Base

C. Federal Specifications (Fed. Spec.): RR-T-650E.....Treads, Metallic and Non-Metallic, Nonskid

### PART 2 - PRODUCTS

### 2.1 GENERAL

A. Use only products by the same manufacturer and from the same production run.

# 2.2 RESILIENT BASE

- A. ASTM F1861, 3 mm (1/8 inch) thick, 100 mm (4 inches) high, Type TP Rubber, Thermoplastics, Group 2-layered with molded top. Style B-cove.
- B. Where carpet occurs, use Style A-straight.
- C. Use only one type of base throughout.
- D. Provide pre-molded inside and outside corners. Job-formed corners are not acceptable.

## 2.3 RESILIENT TREADS

- A. Fed. Spec. RR-T-650, Composition A, Type 2, 5 mm (3/16 inch) thick on wear surface tapering to 3 mm (1/8 inch) thick at riser end.
- B. Nosing shape to conform to sub-tread nosing shape.

## 2.4 SHEET RUBBER FLOORING

- A. ASTM F1344, F1859 or F1860, 900 mm (36 inches) wide, 3 mm (1/8 inch) thick, smooth face, material by the same manufacturer as the rubber treads, color and pattern to match treads.
- B. Use for stair landings.
- C. Use rubber flooring made with a minimum of 90% consumer rubber where possible.

#### 2.5 PRIMER (FOR CONCRETE FLOORS)

A. As recommended by the adhesive and tile manufacturer.

### 2.6 LEVELING COMPOUND (FOR CONCRETE FLOORS)

A. Provide products with latex or polyvinyl acetate resins in the mix.

## 2.7 ADHESIVES

- A. Use products recommended by the material manufacturer for the conditions of use.
- B. Use low-VOC adhesive during installation. Water based adhesive with low VOC is preferred over solvent based adhesive.

7/29/09

7/29/09 Solicitation No.VA-

Imaging Center Project No.: 589-999 Department of Veterans Affairs Harry S. Truman Memorial Veterans Hospital Columbia, Missouri

#### PART 3 - EXECUTION

#### 3.1 PROJECT CONDITIONS

- A. Maintain temperature of materials above 21° C (70  $^{\circ}F)\,,$  for 48 hours before installation.
- B. Maintain temperature of rooms where work occurs, between  $21^{\circ}$  C and  $27^{\circ}$  C  $(70^{\circ}F$  and  $80^{\circ}F)$  for at least 48 hours, before, during, and after installation.
- C. Do not install materials until building is permanently enclosed and wet construction is complete, dry, and cured.

#### 3.2 INSTALLATION REQUIREMENTS

- A. The respective manufacturer's instructions for application and installation will be considered for use when approved by the COTR.
- B. Submit proposed installation deviation from this specification to the COTR indicating the differences in the method of installation.
- C. The COTR reserves the right to have test portions of material installation removed to check for non-uniform adhesion and spotty adhesive coverage.

# 3.3 PREPARATION

- A. Examine surfaces on which material is to be installed.
- B. Fill cracks, pits, and dents with leveling compound.
- C. Level to 3 mm (1/8 inch) maximum variations.
- D. Do not use adhesive for leveling or filling.
- E. Grind, sand, or cut away protrusions; grind high spots.
- F. Clean substrate area of oil, grease, dust, paint, and deleterious substances.
- G. Substrate area dry and cured. Perform manufacturer's recommended bond and moisture test.
- H. Preparation of existing installation:
  - 1. Remove existing base and stair treads including adhesive.
  - 2. Do not use solvents to remove adhesives.
  - 3. Prepare substrate as specified.

### 3.4 BASE INSTALLATION

- A. Location:
  - Unless otherwise specified or shown, where base is scheduled, install base over toe space of base of casework, lockers, laboratory, pharmacy furniture island cabinets and where other equipment occurs.
  - Extend base scheduled for room into adjacent closet, alcoves, and around columns.

Solicitation No.VA-\_

Imaging Center Project No.: 589-999 Department of Veterans Affairs Harry S. Truman Memorial Veterans Hospital Columbia, Missouri

- B. Application:
  - 1. Apply adhesive uniformly with no bare spots.
  - 2. Set base with joints aligned and butted to touch for entire height.
  - Before starting installation, layout base material to provide the minimum number of joints with no strip less than 600 mm (24 inches) length.
    - a. Short pieces to save material will not be permitted.
    - b. Locate joints as remote from corners as the material lengths or the wall configuration will permit.
- C. Form corners and end stops as follows:
  - 1. Score back of outside corner.
  - 2. Score face of inside corner and notch cove.
- D. Roll base for complete adhesion.

### 3.6 SHEET RUBBER INSTALLATION.

- A. Prepare surfaces to receive sheet rubber in accordance with applicable portions of paragraph, preparation.
- B. Layout of Sheet Rubber:
  - 1. Use minimum number of joints compatible with material direction and symmetrical joint location.
  - Where sheet rubber intersect vertical stair members, other sheets, stair treads, and other resilient materials at the floor landings, material shall touch for the entire length within 5 mils (0.005 inch).
  - Install sheet rubber on floors and intermediate landings where resilient stair treads are installed; center joint with other flooring material under doors.
- C. Application:
  - 1. Apply adhesive uniformly with no bare spots.
  - 2. Roll sheet rubber to assure adhesion.

## 3.7 CLEANING AND PROTECTION

- A. Clean all exposed surfaces of base and adjoining areas of adhesive spatter before it sets.
- B. Keep traffic off resilient material for at least 72 hours after installation.
- C. Clean and polish materials in the following order:
  - After two weeks, scrub resilient base, sheet rubber and treads materials with a minimum amount of water and a mild detergent. Leave

Solicitation No.VA-\_\_\_

Imaging Center Project No.: 589-999 Department of Veterans Affairs Harry S. Truman Memorial Veterans Hospital Columbia, Missouri

surfaces clean and free of detergent residue. Polish resilient base to a gloss finish.

2. Do not polish tread and sheet rubber materials.

- D. When construction traffic is anticipated, cover tread materials with reinforced kraft paper and plywood or hardboard properly secured and maintained until removal is directed by the COTR.
- E. Where protective materials are removed and immediately prior to acceptance, replace damaged materials and re-clean resilient materials. Damaged materials are defined as having cuts, gouges, scrapes or tears and not fully adhered.

- - - E N D - - -