

VA Spokane Addendum 005 drawing changes

GI002

- Add drawing sheet AE622 WINDOW TYPES to drawing index

GI003 (sheet not issued)

- Add note 34; "When working in buildings other than the existing Building 40 such as modifying steam lines in Building 27 ALL infection control measures still apply as identified in the construction documents. Every effort is to be taken to control dust and debris from affecting others and the operations of equipment. Clean owner equipment in the surrounding area if it is not protected. Maintain plastic coverage on exposed dirt areas when work is completed in crawl spaces."
- Add note 35; General Contractor to provide a 10lb ABC fire extinguisher at every new fire extinguisher cabinet.

AE102 (sheet not issued)

- Add door and assembly B1160A, 3'-6" x 7'-0" located on west wall of room B1160, see AE620 for specifics

AE104 (sheet not issued)

- Delete ceilings and grids in Corridors B1130 & B1131, add painting underside of exposed deck
- Delete ceilings and grids in Storage B1137 & B1138, add painting underside of exposed deck

AE131: (issued sheet)

- Added keynotes and detail references
- Revised walk-off matt layout

AE311: (issued sheet)

- Added detail references

AE511: (issued sheet)

- Revise reveal dimensions
- Added notes

AE512: (issued sheet)

- Added details
- Revised dimensions
- Revised details and flashing
- Revised precast profiles at louvers

AE513: (issued sheet)

- Add ladder details for roof

AE521: (sheet not issued)

- Delete detail 6 it is a duplicate
- Detail 10 add verbiage identifying the basis of design is for KOROGARD H100 color from manufacturer's standard color pallet.
- Details 4,11, and 14 all pipe sizes to be 1 ½" O.D., delete reference to schedule 40.

VA Spokane Addendum 005 drawing changes

AE522: (issued sheet)

- Added details

AE531: (issued sheet)

- Added details

AE541: (issued sheet)

- Added ceiling information and details

AE620: (issued sheet)

- Updated frame materials in schedules and finishes as well as adding in three re-lights, defined tempered units and glass types at re-lights

AE622: (issued sheet)

- New sheet

AF101 (sheet not issued)

- Delete CPT in Corridors B1130 & B1131 and replace with RT to match existing, see finish schedule
- Delete CPT in Storage B1137 & B1138 and replace with RT to match existing, see finish schedule
- Add 100 sq. ft. of RT to match existing in link corridor of basement level of existing Building 40, next to room S40-2, see finish schedule

Architectural Specs:

Revised 09 60 00

Revised 11 52 13

Division 23 Spec Changes:

Section Number - Section Title

1. Revise section 210511, Revised paragraph 3.1-G
2. Revise section 220511, Revised paragraph 3.1-N-2
3. Revise section 230511, Revised paragraph 3.1-N-2
4. Revise section 260511, Revised paragraph 1.10-C-2
5. Revise section 270511, Revised paragraph 1.8-B-2
6. Revise section 275116, Revised paragraph 2.0-C
7. Revise section 275116, Revised paragraph 2.1-E
8. Revise section 275116, Revised paragraph 2.1-S
9. Revise section 275116, Revised paragraph 2.4-A
10. Revise section 280500, Revised paragraph 3.1-G-2

Mechanical Drawing Changes:

MH100 - BASEMENT LEVEL HVAC PLAN

- Between gridlines EF.4 and M and 1 and 2 delete the flex duct to the supply diffuser. The ceiling in this area is being deleted. Extend the sheet metal ductwork as required and attach the diffuser directly to the rigid sheet metal.

MS101 - SITE PLAN MECHANICAL

VA Spokane Addendum 005 drawing changes

- At the pier blocks and roller pipe supports add the following note:
"PROVIDE 12GA SHEET METAL SHIELD BETWEEN CONDUIT PIPE AND ROLLER.
SHIELD TO BE MINIMUM OF 18" LONG AND SECURED TO THE CONDUIT PIPE".

Electrical Drawing Changes:

ES101 - ELECTRICAL SITE PLAN

- Deleted Deductive Alternate Bid #7 Construction Notes.
- Revise Sheet Note #6 to include protection of existing transformers and feeders.
- Add Sheet Note to include (6) additional strip lights, Type 'F5' in basement of Building 26. Location to be coordinated in field with VA.

EL100 - BASEMENT PLAN - LIGHTING

- Revise light fixtures in Corridors B1130 and B1131 from 2x4 troffers in lay-in ceiling grid to chain-hung strip fixtures, Type 'F5'.
- EP101 - LEVEL 1 PLAN - POWER
- Added Pushbutton to open Door Operator in Corridor B L1106 with note stating "PROVIDE RACEWAY AND WIRING BETWEEN ACTUATOR AND OPERATOR AND CONNECT COMPLETE."

EP401 - ENLARGED POWER PLANS

- Change UPS circuit located in IT L1107 of ENLARGED PLAN - IT L1107 to Panel P40A1-64.66.
- Change receptacle circuits located in IT L1107 of ENLARGED PLAN - IT L1107 to Panel P40A1-60.62.

EP610 - PANEL SCHEDULES - ELECTRICAL

- Added 30 A 2 P circuit breaker to Panel 'MB40AB' for CU-1 (MB40AB-2,4.).
- Added 20 A 2 P circuit breaker to Panel 'MB40AB' for FCU-1 (MB40AB-6,8.).
- Added 20 A 1 P circuit breaker to Panel 'MB40AB' for CRU-1 (MB40AB-10.).
- Added 20 A 1 P circuit breaker to Panel 'P40A1' Sect 2 for Receptacle (P40A1-60.).
- Added 20 A 1 P circuit breaker to Panel 'P40A1' Sect 2 for Receptacle (P40A1-62.).
- Added 20 A 2 P circuit breaker to Panel 'P40A1' Sect 2 for UPS Unit (P40A1-64,66.).

EP611 - PANEL SCHEDULES - ELECTRICAL

- Deleted Note 1 from Mechanical Equipment Connection Schedule.
- Changed circuit for Equipment Item CU-1 to MB40AB-2,4.
- Changed circuit for Equipment Item FCU-1 to MB40AB-6,8.
- Changed circuit for Equipment Item CRU-1 to MB40AB-10.
- Changed circuit for Equipment Item HWUH-1 to MB40AB-37.
- Changed circuit for Equipment Item HWUH-2 to MB40AB-39.

ET100 - BASEMENT LEVEL PLAN - TECHNOLOGY

VA Spokane Addendum 005 drawing changes

- Deleted Sheet Keynotes 5, 7, 8, and 9. These notes will not be used.
- Deleted Deductive Alternate 4 and its boundary lines.
- Sheet Keynote located at entry to Mechanical B1140 changed to 12.

ET101 - LEVEL 1 PLAN - TECHNOLOGY

- Added Deductive Alternate 2 and its boundaries.