

Item No. 1 - Section 084113 Aluminum-Framed Entrances and Storefronts

A. Page 3, Para. 2.5: Stile and Rail Doors: Add the following:

"A. Muntin Bars: Horizontal tubular rail member for each door; 4 1/4 inch nominal width."

B. Page 4, Para. 2.5: Add the following:

“E. Locking: Equip door unit with manufacturer’s electrified locking.

1. Electric Solenoid Lock (Fail Secure)
2. Access Control Locking capability with surface or recessed panic hardware for latch release and breakout egress during power failure or emergency.”
3. Automatic motor controls to interface with Card Reader activation. Card Reader provided by Security Contractor.”

F. Door position monitoring: Equip door with position and/or latch status contacts, with remote monitoring capability of panel status.”

Item No. 2 – Door Hardware 087100

A. 087100 - 3, Art. 1.9, Para. C; Add the following to abbreviations

"SDC Security Door Controls Camarillo, CA"

B. 087100 - 15, Hardware Set #1 – Main Entry; Revise as follows”

1	Auto Operator	Horizontal Sliding door with electrified locking, access control and door position monitoring. Refer to Section 087113. Balance of hardware by door manufacturer
1	Cylinder as required.	

1	Card Reader	FIPS-201	HID
---	-------------	----------	-----

During normal operating hours, sensor activates automatic entrance. Electrified Latching is retracted. After hours, electrified latch is released to locked position. Access control deactivates sensor on exterior side. Presenting authorized credentials at card reader, retracts latch, activates sensor and/or automatic door for a specified interval. Free egress at all times."

C. 087100 -15, Add the following - Revise Conference F100 exterior door from hardware group #2 to hardware group #2.1:

(Coordination Note: Refer to Technology Drawings. Rough-in only for future electrified devices at opening CSS 1-14, with Hardware Set 2.1 applied to opening CSS 1-20)

Hardware Set #2.1 - Exterior entry at Police Area (Conference Room F100)

3 Hinges	A5112 (CB1960R)	626	ST
1 Elec. Exit Device	E03 (EL LX-RX-33A-NL-OP X 388)	US32D	VO
	J401 pull by alum door mfr.		
1 Power Transfer	EPT-12C	626	BE
1 Rim Cylinder	12E-72 STD	626	BE
1 Door Closer	C02021 (QDC115M)	689	SH
1 Floor Stop	L02181 (1214CK x 1268CK)	626	TR
	Core drilled with anchor. Cast in place		
1 Threshold	896 S 36"	AL	NA
1 Card Reader	FIPS-201		HID
1 Door Position Switch	By Security Contractor		

NOTE: Weatherstripping by alum. door and frame mfr. Operation: Presenting authorized credentials at card reader releases latch for temporary entry for prescribed interval. Free egress at all times. Door wire chase and wiring included. Card reader, monitoring, power supply and relay by Security Contractor.

D. 087100 - 16, Hardware Set #6 – Secure Storage; Revise as follows:

(Coordination Note: Refer to Technology Drawings. Rough-in only for future electrified devices at opening CSS 1-4 & CSS 1-6)

1. Delete Deadlock.
2. Change cylindrical lockset to mortise lock as follows:

"1 Mortise Lockset F07 (45H-7D15H) S1 630 BE

Note: Prepare door and frame with wiring routes to future electrified mortise lockset."

E. 087100 - 16, Add Hardware Set: Revise Evidence F111 from hardware set #6 to hardware set #6.1

"Hardware Set #6.1 - Evidence Room F111

1 Continuous Hinge	661CE UL 84"	AL	ST
1 Electro-Mech Lock	DEU (45HW-7DEU15J RQE LS) S1	626	BE
1 Door Closer	C02021 (QDC115M)	689	SH
	NOTE: Mount on pull side.		
2 Kick Plate	J102 (KO050)	619	TR
1 Floor Stop	L02141 (1211)	619	TR
1 Card Reader	FIPS-201		HID
1 Door Position Switch	By Security Contractor		

NOTE: Presenting authorized credentials sends power to activate lever for temporary entry for prescribed interval. Free egress at all times. Door wire

chase and wiring included. Card reader, power supply, monitoring and relay by Security Contractor."

F. 087100 -17, Hardware Set #11 – Operations; Revise as follows:

"1 Continuous Hinge	661CE UL 84	AL	ST
1 Electro-Mech Lock	DEU (45HW-7DEU15J RQE LS) S1	626	BE"

Add the following:

"1 Door Position Switch By Security Contractor"

G. 087100 -18, Hardware Set #14 – Armory; Revise as follows:

"1 Electro-Mech Lockset	DEU (45HW-7DEU15J RQE LS)	626	BE
1 Door Closer	C02012 (QDC115M) Hinge side	689	SH"

Add the following:

"1 Magnetic Lock	1511 (Fail Safe)x EZ-D10	SDC
1 Door Position Switch	By Security Contractor	

NOTE: Presenting authorized credentials activates lever and releases magnetic lock for temporary entry for prescribed interval. Lockset RQE wired to release magnetic lock and override alarm. Free egress at all times. Door wire chase and wiring included. Card reader, power supply, monitoring and relay by Security Contractor."

H. 087100 -18, Hardware Set #18 –Telecom/IT; Add and Revise as follows:

1 Concealed OH Stop	C01541 (1023) Push side	630	AB
1 Magnetic Lock	1511 (Fail Safe) x EZ-D10	626	BE
1 Request to Exit Switch	423MU	Red	SDC
1 Card Reader	FIPS-201		HID
1 Door Position Switch	By Security Contractor		

NOTE: Presenting authorized credentials releases magnetic lock for temporary entry for prescribed interval. Magnetic locks wired to fire alarm control system. Free egress at all times with RQE. Door wire chase and wiring included. Card reader, power supply and relay by Security Contractor."