

# PART III

## SCHEDULE B -- SPECIAL REQUIREMENTS

**PART III: SCHEDULE B--SPECIAL REQUIREMENTS**

**SECTION 1: INSTRUCTIONS FOR PRICING THIS SCHEDULE .....3**

**SECTION 2: GENERAL INFORMATION AND INSTRUCTIONS FOR USERS .....4**

**SECTION 3: SPECIAL ITEMS FOR THE ENTIRE CLINIC .....5**

3.1 PUBLIC ADDRESS SYSTEM .....5

3.2 AUDIO VISUAL, NURSE CALL, AND CODE ONE (BLUE) SYSTEM .....5

3.3 MASTER ANTENNA TELEVISION (BROADBAND) SYSTEM .....5

3.4 SECURITY MANAGEMENT AND CONTROL, AND CENTRALIZED POLICE SECURITY MANAGEMENT SYSTEMS .....5

3.5 PATIENT (ALSO STAFF) ANNUNCIATOR/LOCATOR SYSTEM .....5

3.6 MOTION INTRUSION DETECTOR (MID) .....5

3.7 RADIO ENTERTAINMENT DISTRIBUTION (RED) .....5

3.8 DURESS ALARM AND EMERGENCY NOTIFICATION SYSTEM .....6

3.9 RADIO PAGING SYSTEM .....6

3.10 TWO-WAY RADIO SYSTEM .....6

3.11 SECURITY SURVEILLANCE TELEVISION (SSTV) .....6

3.12 INTERCOMMUNICATION SYSTEM .....6

3.13 VIDEO TELECONFERENCING SYSTEM (VTEL) .....6

3.14 VA SATELLITE TV SYSTEM .....6

3.15 ELECTRONIC ACCESS AND DOOR CONTROL SYSTEM .....7

**SECTION 4: SPECIAL EQUIPMENT BY FUNCTIONAL AREA .....8**

4.1 FUNCTIONAL AREAS .....8

4.2 ..FUNCTIONAL ROOM LIST ..... 10

**SECTION 5: SUMMARY PRICE SHEET**

**PART III: SCHEDULE B -- SPECIAL REQUIREMENTS**

**SECTION 1: INSTRUCTIONS FOR PRICING THIS SCHEDULE**

The Offeror shall submit lump-sum pricing for the purchase and installation of special equipment items specified in Schedule B for laboratory and clinic areas. Offers shall be evaluated in accordance with Part I of the Basic Solicitation. All property placed in, upon, or attached to the premises to be leased, and for which the Government pays by means of lump-sum, shall be and remain the property of the Government, and may be removed or otherwise disposed of by the Government.

As part of the rental consideration, the Offeror must include supporting construction, HVAC systems, utilities, and electrical distribution systems for Offeror furnished equipment and VA furnished equipment to be installed in the Outpatient Clinic. The price for each item in Schedule B shall include only the direct costs of obtaining and installing the item. Supporting structure(s) and distribution systems are included in the basic rent. Therefore, no additional costs relating to the distribution of services (including plumbing, sewage or electricity) or supporting construction should be ascribed to the special equipment costs in Schedule B.

Special equipment items for the clinic are listed in Sections 3 and 4 below. Pricing lines have been provided at each item to be included for pricing purposes in the offer. The Offeror is required to identify the total price involved for each line item. Totals for each Department or Service in the clinic must be entered on the Summary Price Sheet in the Schedule B document.

The Schedule B document is available as a convenience to Offerors in the form of an Excel workbook (electronic spreadsheet file). The individual worksheets (spreadsheets) in the file have been linked and formulas have been provided to facilitate computation of extended prices and totals. Electronic files are provided without warranty or obligation on the part of the government as to the accuracy or suitability for use. Users of electronic files shall agree to indemnify and hold the VA harmless from any and all claims, damages, losses and expenses including, but not limited to, attorney's fees arising from the use of the electronic files.

Offerors are responsible for the accuracy and completeness of the quantities, costs, subtotals, and totals in their proposals.

Items not listed in Schedule B are to be provided by the Lessor as part of the rental consideration. Such items are either specifically called for in the Basic Solicitation (e.g., drinking fountains) or identified in a paragraph specifying an allowance for payment under the provisions of the Basic Solicitation (e.g., telecommunications outlets) and are not identified for pricing purposes in Schedule B.

Estimated quantities have been provided in Schedule B for use in preparation of offers. An adjustment will be made at the time of final inspection on those items specified in Schedule B if there is any deviation between the quantity actually provided and the Government's estimated quantity.

**SECTION 2: GENERAL INFORMATION AND INSTRUCTIONS FOR USERS**

**Brand Names:** Certain equipment may be identified by make and model. Identification of these items in this Solicitation by a "brand name" description is intended to indicate the quality and characteristics of products that will be satisfactory and is not intended to be restrictive. Unless clearly indicated in the offer that an "equal" product is offered, the offer shall be considered as offering a referenced brand name product. Offers of "equal" products or equipment will be considered for this award if such product or equipment is clearly identified in the offer and is determined by the Government to fully meet the salient characteristics of the product or equipment named in this Solicitation. The Government's determination as to the acceptability of the "equal" product shall be based on information furnished or otherwise identified in the offer, as well as other information reasonably available to the VA. If the equipment cited in the Solicitation is no longer available, the manufacturer's currently available equipment that replaces the cited model shall be provided.

**Caution to Offerors:** The VA is not responsible for locating or securing any information not identified in the offer and not reasonably available to the VA. Accordingly, the Offeror shall furnish with its offer the manufacturer and model of equipment proposed and sufficient descriptive material such as cuts, illustrations, drawings, or other information for the VA to determine whether the product offered meets the specified salient characteristics and establishes exactly what the Offeror proposes to furnish. **The quantities between schedules B and C should be coordinated to prevent double counting.**

**Basis of Design:** Offerors are advised that room layouts and equipment guide lists used in the development of this solicitation were based on VA PG-18-12, *Outpatient (SOC/CBOC) Design Guide* and VA PG-18-5, *Equipment Guide List*. These documents are the basis of design for VA facilities nationwide and may be found in VA's Technical Library at <http://www.cfm.va.gov/TIL/>.

**SECTION 3: SPECIAL ITEMS FOR THE ENTIRE CLINIC**

Placement of special systems required by the entire clinic will be shown on telecommunications drawings. Please price as totally installed and provide a unit cost for each item as listed in this Schedule. Adjustments in the contract at the time of approval of the equipment drawings will be made based on prices provided by the Offeror in this Schedule B document.

Specific Telecommunications Systems (all systems must be approved by the Contracting Officer or the Contracting Officer's designee.)

**3.1 PUBLIC ADDRESS SYSTEM**

Provide a public address system. The system will also allow each area receptionist to address their specific waiting areas. Public address central equipment shall be located in Telephone Equipment Room. System(s) shall be as manufactured by Bogen, JBL, Dukane, or approved equivalent, as updated to most current technology or manufacturer.

**3.2 AUDIO VISUAL, NURSE CALL, AND CODE ONE (BLUE) SYSTEM**

Provide a complete nurse call system. System(s) shall be as manufactured by Rauland Borg, General Electric, Simplex, or approved equivalent, as updated to most current technology or manufacturer.

**3.3 MASTER ANTENNA TELEVISION (BROADBAND) SYSTEM**

Provide a master antenna television (broadband) system. System(s) shall be as manufactured by Blonder Tongue, Scientific Atlanta, Olson Technologies, or approved equivalent, as updated to most current technology or manufacturer.

**3.4 SECURITY MANAGEMENT AND CONTROL, AND CENTRALIZED POLICE SECURITY MANAGEMENT SYSTEMS**

Provide security management and control, and centralized police security management systems. System(s) shall be as manufactured by Lockheed, Viper, Access Gold, Casi-Rusco, or approved equivalent, as updated to most current technology or manufacturer. LAN/WAN based systems must be on a separate and standalone system and NOT connected to the Facility's LAN/WAN.

**3.5 PATIENT (ALSO STAFF) ANNUNCIATOR/LOCATOR SYSTEM**

Provide patient and staff annunciator/locator system. System(s) shall be as manufactured by Viking, Radiance, Secur Trak, Patient Central, or approved equivalent, as updated to most current technology or manufacturer.

**3.6 MOTION INTRUSION DETECTOR (MID)**

Provide a motion intrusion detection system. System shall be Security Metrics, Ademco, Honeywell, or approved equivalent, as updated to most current technology or manufacturer.

**3.7 RADIO ENTERTAINMENT DISTRIBUTION (RED)**

Provide radio entertainment distribution (RED) systems as required. System(s) shall be as manufactured by Bogen, JBL, Dukane, or approved equivalent, as updated to most current technology or manufacturer.

**Part III: Schedule B – Special Requirements --Page 5 of 49**

**3.8 DURESS ALARM AND EMERGENCY NOTIFICATION SYSTEM**

Provide a duress alarm and emergency notification panic system with visual and audible annunciation at Security Office and Central Reception Area, connected to selected locations throughout the facility. System shall be Code Blue Pole Systems or approved equivalent, as updated to most current technology or manufacturer. Under no circumstance shall the telephone system be used to provide duress alarm functions.

**3.9 RADIO PAGING SYSTEM**

Provide radio paging system (identified as Public Safety Operation and upgraded to Life Safety when interfaced to Code One (Blue)) as required. System(s) shall be as manufactured by Motorola, Johnson, Kenwood, or approved equivalent, as updated to most current technology or manufacturer.

**3.10 TWO-WAY RADIO SYSTEM**

Provide two-way radio systems as required. System(s) shall be as manufactured by Motorola, Johnson, Vertex Standard, or approved equivalent, as updated to most current technology or manufacturer.

**3.11 SECURITY SURVEILLANCE TELEVISION (SSTV)**

Provide a complete operational SSTV monitoring system with cameras monitoring the building interior, exterior, and parking lot. Provide equipment to monitor each camera. System(s) shall be as manufactured by Panasonic, Video Tek, Pelco, or approved equivalent, as updated to most current technology or manufacturer.

**3.12 INTERCOMMUNICATION SYSTEM**

Provide an intercommunication system. System(s) shall be as manufactured by Bogen, Aiphone, Leviton, or approved equivalent, as updated to most current technology or manufacturer.

**3.13 VIDEO TELECONFERENCING SYSTEM (VTEL)**

Provide cabling and outlets for the VTEL system. The VA shall provide equipment required for the VTEL system. Install a CAT 6 cable from a data outlet in designated Treatment, Telemedicine, and Classroom to Telephone Equipment Room. Cable from each room shall terminate in center of Telephone Equipment room with thirty (30) feet of excess cable and shall be tagged to indicate room that cable serves. System(s) shall be as manufactured by Polycom, Tandberg, HP, or approved equivalent, as updated to most current technology or manufacturer.

**3.14 VA SATELLITE TV SYSTEM**

Provide cabling, outlets, and roof support for VA satellite TV system for reception of VA internal programming. VA shall provide satellite dish for Lessor installation. The VA shall furnish and install system equipment. Provide coaxial cable, Belden 7731A, from TV outlets in Classroom and Conference Room to Telephone Equipment Room. Cable from each room shall be installed to center of Telephone Equipment Room above ceiling with thirty (30) LF of excess cable. Cables shall be tagged to identify room that cable serves. Provide coaxial cable from Telephone Equipment Room to Satellite Dish location on roof (250 LF). Provide roof support for satellite dish and means of anchoring satellite dish to roof. System(s) shall be

as manufactured by Scientific Atlanta, Blonder Tongue, Pico Macom, or approved equivalent, as updated to most current technology or manufacturer.

**3.15 ELECTRONIC ACCESS AND DOOR CONTROL SYSTEM**

Provide complete, operational electronic card keypad access and door control system. All access control system products shall be furnished and installed by the same company. System shall be Dyna Lock, Locknetics, Sentrol, or approved equivalent, as updated to most current technology or manufacturer.

**SECTION 4: SPECIAL EQUIPMENT BY FUNCTIONAL AREA** This document lists the special equipment required for each room type in each Functional Area. Although every room type in the Outpatient Clinic is listed, not every room will have special equipment. Where (NR) is indicated, there are no "special requirements" in that room.

**4.1 FUNCTIONAL AREAS**

- 1 - ERRERA CENTER - LOBBY
- 2 - ERRERA CENTER - HEALTHCARE ADMINISTRATION
- 3 - ERRERA CENTER - PRIMARY CARE
- 4 - ERRERA CENTER - MENTAL HEALTH
- 5 - ERRERA CENTER - SUBSTANCE ABUSE
- 6 - ERRERA CENTER - WELLNESS
- 7 - OFFICE SPACE - NATIONAL PROGRAMS
- 8 - CANTEEN
- 9 - POLICE AND SECURITY
- 10 - LOGISTICS
- 11 - INFORMATION RESOURCE MANAGEMENT
- 12 - BUILDING SUPPORT
- 13 - BUILDING CIRCULATION

PART III: SCHEDULE B--SPECIAL REQUIREMENTS (cont.)

4.2--Functional Room List

SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List										
Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
<b>1 - ERRERA CENTER - LOBBY</b>										
LOBBY	CLSC2	1	Patient Education						\$0.00	
				A1012	Telephone, Wall mounted, one line	4		\$0.00		Telephone, Wall Mounted, 1 Line
LOBBY	LOB02	1	Vestibule							No Additional Schedule B Items
LOBBY	SRLW1	1	Storage, Wheelchair							No Additional Schedule B Items
LOBBY	TLTU1	2	Toilet - Family						\$0.00	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A4995	Table, Diaper Changing, Wall Mounted	1		\$0.00		Wall mounted diaper changing table for use in public restrooms. Unit is a fold down system that folds upward when not in use for minimal intrusion into the room. Changing surface is contoured and has safety belt to insure that an infant will not fall from the table. Table is designed to hold no less than 250 pounds static weight. Closed dimensions are approximately 21" H x 36" W x 5" D. Open dimensions vary according to style. One system's open dimensions are 15" high, 32" wide and 19" deep.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>LOBBY</b>	<b>TLTU1</b>	<b>1</b>	<b>Toilets, Public (Male)</b>						<b>\$0.00</b>	
				A1085	Mirror, SS, With SS Frame, 36x18	2		\$0.00		A highly polished, stretcher leveled, stainless steel mirror, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For use in areas of a facility where a float glass mirror is not desired for reasons of patient and staff safety. This mirror is not intended for use in a maximum-security patient area.
				A4995	Table, Diaper Changing, Wall Mounted	1		\$0.00		Wall mounted diaper changing table for use in public restrooms. Unit is a fold down system that folds upward when not in use for minimal intrusion into the room. Changing surface is contoured and has safety belt to insure that an infant will not fall from the table. Table is designed to hold no less than 250 pounds static weight. Closed dimensions are approximately 21" H x 36" W x 5" D. Open dimensions vary according to style. One system's open dimensions are 15" high, 32" wide and 19" deep.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	2		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				C0041	Rail, Apron, 4x60x1	1		\$0.00		Apron rail. Also referred to as an apron front, apron panel, or knee space rail. Used to close in front knee space area and/or provide work surface support between two base cabinets or a base cabinet and wall. Apron rails should be ordered in pairs to provide both front and rear work surface support.
				CT030	Countertop, High Pressure Laminate	5		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backslash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				P3070	Lavatory, Vitreous China, Under or Counter Top Mtd	2		\$0.00		An undercounter or countertop mounted vitreous china lavatory (approximate bowl size 6"x17"x14") with gooseneck spout, wrist blade handles, and grid drain. Counter top mounted lavatory to be self rimming with mounting kit provided. Undercounter lavatory to have unglazed rim with a mounting kit also provided. For general purpose use in vanity tops in public, patient and staff toilet rooms.
				P8150	Urinal, Wall Hung	2		\$0.00		A low consumption (1.0 gallon per flush) vitreous china, wall hung, washout flush action urinal with extended sides, flushing rim, 3/4" inlet spud, 2" I.P.S. female outlet connection and stainless steel strainer. For general purpose use in male toilet rooms.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>LOBBY</b>	<b>TLTU1</b>	<b>1</b>	<b>Toilets, Public (Male)</b>						<b>\$0.00</b>	
				A1085	Mirror, SS, With SS Frame, 36x18	2		\$0.00		A highly polished, stretcher leveled, stainless steel mirror, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For use in areas of a facility where a float glass mirror is not desired for reasons of patient and staff safety. This mirror is not intended for use in a maximum-security patient area.
				A4995	Table, Diaper Changing, Wall Mounted	1		\$0.00		Wall mounted diaper changing table for use in public restrooms. Unit is a fold down system that folds upward when not in use for minimal intrusion into the room. Changing surface is contoured and has safety belt to insure that an infant will not fall from the table. Table is designed to hold no less than 250 pounds static weight. Closed dimensions are approximately 21" H x 36" W x 5" D. Open dimensions vary according to style. One system's open dimensions are 15" high, 32" wide and 19" deep.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	2		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				C0041	Rail, Apron, 4x60x1	1		\$0.00		Apron rail. Also referred to as an apron front, apron panel, or knee space rail. Used to close in front knee space area and/or provide work surface support between two base cabinets or a base cabinet and wall. Apron rails should be ordered in pairs to provide both front and rear work surface support.
				CT030	Countertop, High Pressure Laminate	5		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				P3070	Lavatory, Vitreous China, Under or Counter Top Mtd	2		\$0.00		An undercounter or countertop mounted vitreous china lavatory (approximate bowl size 6"x17"x14") with gooseneck spout, wrist blade handles, and grid drain. Counter top mounted lavatory to be self rimming with mounting kit provided. Undercounter lavatory to have unglazed rim with a mounting kit also provided. For general purpose use in vanity tops in public, patient and staff toilet rooms.
				P8150	Urinal, Wall Hung	1		\$0.00		A low consumption (1.0 gallon per flush) vitreous china, wall hung, washout flush action urinal with extended sides, flushing rim, 3/4" inlet spud, 2" I.P.S. female outlet connection and stainless steel strainer. For general purpose use in male toilet rooms.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>LOBBY</b>	<b>TLTU1</b>	<b>1</b>	<b>Toilets, Public (Female)</b>						<b>\$0.00</b>	

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A1085	Mirror, SS, With SS Frame, 36x18	2		\$0.00		A highly polished, stretcher leveled, stainless steel mirror, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For use in areas of a facility where a float glass mirror is not desired for reasons of patient and staff safety. This mirror is not intended for use in a maximum-security patient area.
				A4995	Table, Diaper Changing, Wall Mounted	1		\$0.00		Wall mounted diaper changing table for use in public restrooms. Unit is a fold down system that folds upward when not in use for minimal intrusion into the room. Changing surface is contoured and has safety belt to insure that an infant will not fall from the table. Table is designed to hold no less than 250 pounds static weight. Closed dimensions are approximately 21" H x 36" W x 5" D. Open dimensions vary according to style. One system's open dimensions are 15" high, 32" wide and 19" deep.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	3		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	3		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	2		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				C0041	Rail, Apron, 4x60x1	1		\$0.00		Apron rail. Also referred to as an apron front, apron panel, or knee space rail. Used to close in front knee space area and/or provide work surface support between two base cabinets or a base cabinet and wall. Apron rails should be ordered in pairs to provide both front and rear work surface support.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	5		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				P3070	Lavatory, Vitreous China, Under or Counter Top Mtd	2		\$0.00		An undercounter or countertop mounted vitreous china lavatory (approximate bowl size 6"x17"x14") with gooseneck spout, wrist blade handles, and grid drain. Counter top mounted lavatory to be self rimming with mounting kit provided. Undercounter lavatory to have unglazed rim with a mounting kit also provided. For general purpose use in vanity tops in public, patient and staff toilet rooms.
				P9050	Toilet, Wall Hung, Siphon Jet	3		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>LOBBY</b>	<b>TLTU1</b>	<b>1</b>	<b>Toilets, Public (Female)</b>						<b>\$0.00</b>	
				A1085	Mirror, SS, With SS Frame, 36x18	2		\$0.00		A highly polished, stretcher leveled, stainless steel mirror, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For use in areas of a facility where a float glass mirror is not desired for reasons of patient and staff safety. This mirror is not intended for use in a maximum-security patient area.
				A4995	Table, Diaper Changing, Wall Mounted	1		\$0.00		Wall mounted diaper changing table for use in public restrooms. Unit is a fold down system that folds upward when not in use for minimal intrusion into the room. Changing surface is contoured and has safety belt to insure that an infant will not fall from the table. Table is designed to hold no less than 250 pounds static weight. Closed dimensions are approximately 21" H x 36" W x 5" D. Open dimensions vary according to style. One system's open dimensions are 15" high, 32" wide and 19" deep.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and uni-sex toilet rooms.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	2		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				C0041	Rail, Apron, 4x60x1	1		\$0.00		Apron rail. Also referred to as an apron front, apron panel, or knee space rail. Used to close in front knee space area and/or provide work surface support between two base cabinets or a base cabinet and wall. Apron rails should be ordered in pairs to provide both front and rear work surface support.
				CT030	Countertop, High Pressure Laminate	5		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				P3070	Lavatory, Vitreous China, Under or Counter Top Mtd	2		\$0.00		An undercounter or countertop mounted vitreous china lavatory (approximate bowl size 6"x17"x14") with gooseneck spout, wrist blade handles, and grid drain. Counter top mounted lavatory to be self rimming with mounting kit provided. Undercounter lavatory to have unglazed rim with a mounting kit also provided. For general purpose use in vanity tops in public, patient and staff toilet rooms.
				P9050	Toilet, Wall Hung, Siphon Jet	2		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>LOBBY</b>	<b>WRC01</b>	<b>3</b>	<b>Waiting Area</b>						<b>\$0.00</b>	
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				R2201	Fountain, Water, CRS, Wall Mounted, 2 Level	1		\$0.00		Drinking water fountain. This unit is a wall mounted, combination handicap and general public (2 level) dispenser. It contains an air cooled compressor with CRS wall protector. Specify with or without glass filler. It provides cool fresh drinking water, for hospitals and commercial office buildings.
<b>2 - ERRERA CENTER - HEALTHCARE ADMINISTRATION</b>										
HEALTHCARE ADMINISTRATION	OFA01	2	Flex Office						\$0.00	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
HEALTHCARE ADMINISTRATION	RECP1	1	Central Reception Counter and Supplemental Office Equipment						\$0.00	
				A1015	Telephone, Desk, Multiple Line	2		\$0.00		Telephone, desk, multiple line.
				A6105	Counter, Reception Control, Built-In	1		\$0.00		Counter, control, inpatient, built-in. Consists of two 18" wide base cabinets with two drawers and file drawer, two 30" wide pencil drawers and two 18" wide base cabinet with four drawers. The countertop shall be a composition of wood particle core with plastic laminate surface having a hard smooth surface finish, standard thickness of 1" and a 4" butt backsplash/curb. Pricing based on a 30" depth.
HEALTHCARE ADMINISTRATION	RECP3	1	Volunteer Alcove						\$0.00	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	2		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				CB020	Cabinet, W/H, 2 Shelf, 1 DO, Sloping Top, 38x24x13	2		\$0.00		Wall hung cabinet with two adjustable shelves, solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings), and sloping top. Also referred to as a solid hinged single door case. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	6		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
HEALTHCARE ADMINISTRATION	RECP4	1	Check-In Kiosks							No Additional Schedule B Items
HEALTHCARE ADMINISTRATION	SEC01	1	Office, Secretary / Clerical						\$0.00	
				A1011	Telephone, Desk, 1 Line	1		\$0.00		Telephone, desk, 1 line.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
<b>3 - ERRERA CENTER - PRIMARY CARE</b>										
PRIMARY CARE		1	Department Circulation							No Additional Schedule B Items
PRIMARY CARE	EXPA1	6	Exam Room						\$0.00	
				A1012	Telephone, Desk, With Speaker	1		\$0.00		Telephone, Wall Mounted, 1 Line
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5180	Track, Cubicle, Surface Mounted, With Curtain	12		\$0.00		Surface mounted cubicle track, with curtain. Track constructed of thick extruded aluminum. Equipped with self lubricating carriers, beaded drop chain hooks, and flame resistant curtain. To include removable end caps. Designed to be suspended around patient areas where privacy is needed. Price listed is per foot of the track, curtains to be priced per quote.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	3		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				F2310	Rack, Pamphlet, Wall Mounted	1		\$0.00		Wall mounted pamphlet rack up to 12 (twelve) pamphlet holding pockets. Unit is used to store and display educational pamphlets.
				F3025	Board, Bulletin, Wood Framed, 36 x 24	1		\$0.00		Bulletin board. Wood framed 1/2" cork posting panel with moisture proof backing. Units are factory assembled and have keyhole hangers for easy installation.
PRIMARY CARE	UCCL1	1	Utility Alcove, Clean							No Additional Schedule B Items
PRIMARY CARE	MEDP1	1	Medication Room / Omnicell Alcove						\$0.00	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
PRIMARY CARE	MEDP1	1	Medication Room / Omnicell Alcove						\$0.00	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
PRIMARY CARE	PEHW1	1	Height/Weight Screening							No Additional Schedule B Items
PRIMARY CARE	RPR01	1	Copy						\$0.00	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
PRIMARY CARE	USCL1	1	Soiled Utility Room						\$0.00	
				A1012	Telephone, Desk, With Speaker	1		\$0.00		Telephone, Wall Mounted, 1 Line
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C05P0	Cabinet, Sink, U/C/B, 2 Door, 36x48x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CS200	Sink, SS, Single Compartment, 12x28x16 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface.
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt back splash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				E1500	Rail, MOD, W/MNTD, HX144XD	1		\$0.00		Wall mounted rail used for hanging (mounting) lockers, shelves drawers on a wall.
PRIMARY CARE	SRS01	1	Equipment and Storage Space							No Additional Schedule B Items
PRIMARY CARE	TLTU1	2	Toilet						<b>\$0.00</b>	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List										
Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>PRIMARY CARE</b>	<b>TLTU1</b>	<b>1</b>	<b>Toilet</b>						<b>\$0.00</b>	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				L1200	Cabinet, Specimen, Pass Thru, CRS	1		\$0.00		Pass-through specimen cabinet. The unit has a sight-proof interlocking door that permits only one door to open at a time. It also includes a removable spill tray, corrosion resistant stainless steel welded construction with seamless corners and burr-free edges and is able to adjust to wall thickness between 3-6 inches. Used for passage of specimens from patient area to laboratory.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>PRIMARY CARE</b>	<b>TRPR1</b>	<b>1</b>	<b>Procedure Room</b>						<b>\$0.00</b>	
				A1011	Telephone, Desk, 1 Line	1		\$0.00		Telephone, desk, 1 line.
				A1200	Lift System, Overhead, Patient Room	1		\$0.00		An overhead rail system specifically designed for patient lifting and movement for a single bed patient room. The system will consist of recessed or ceiling mounted primary and secondary rails, lift motor with rolling carriage, patient harness or seat, and a hand controller or control box with charger. System will facilitate lifting and movement of patient to and from bed to gurney, chair or other requirement. Minimum lift capability is 550 pounds. Custom design of track layout by manufacturer is essential to meet individual facility requirements. lift system should extend into attached toilet
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5180	Track, Cubicle, Surface Mounted, With Curtain	14		\$0.00		Surface mounted cubicle track, with curtain. Track constructed of thick extruded aluminum. Equipped with self lubricating carriers, beaded drop chain hooks, and flame resistant curtain. To include removable end caps. Designed to be suspended around patient areas where privacy is needed. Price listed is per foot of the track, curtains to be priced per quote.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	3		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				E0915	Locker, Supply, Medication, Wall Mtd, 23"W x 20"D	1		\$0.00		THIS TYPICAL INCLUDES: 1 Wall Mounted Rail 1 Locked Storage Container 2 Tray/Shelves 1 Locked Drawer w/Locked Lid, 6"H 5 Drawers, 3"H 3 Drawers, 6"H 2 Tray/Shelves Divider Drawer Organizer Bins Consider the need for an E0921 to transport the locker from place to place.
				F3010	Board, Bulletin, 48 x 48	1		\$0.00		Open face bulletin board. Cork posting panel with moisture proof backing. Variety of frames to choose from. Used for posting notes and messages.
				M7405	Light, Exam, Ceiling Mounted	1		\$0.00		Ceiling exam light. Consists of a lightheaded reflector supported by a ceiling mounted radial arm assembly that provides a wide range of positioning capabilities. Halogen bulbs and an intensity control provide cool, color corrected light. The minimum ceiling height in most cases is 8'-0"; refer to each manufacturer's specific installation requirements. Physical dimensions refer to the retracted light; one length of the dual swing arm around the center mount in width and depth and the combined height of the lamp head and folded arms. Unit may also have a center mount detachable and sterilizable control handle. For use in minor procedure or examination room applications.
<b>PRIMARY CARE</b>	<b>UCCL1</b>	<b>1</b>	<b>Utility Room, Clean</b>						<b>\$0.00</b>	
				P8710	Utility Center, Plumbing Connection	1		\$0.00		Plumbing connection utility center, sometimes referred to as a 'GUY GRAY BOX'. This recessed utility center provides for hot and cold water connections and a drain connection at sink and other equipment locations. The utility center includes cutoff valves for the water connections, a plug seal for the drain and an outside cover to provide an aesthetic appearance when connections are no longer required. This center may be installed in locations where no plumbing fixtures are included in a design as a future flexibility device, saving many dollars for later facility modifications to incorporate sinks as functions change.
<b>PRIMARY CARE</b>	<b>WRTM1</b>	<b>1</b>	<b>Team Room (Providers/RN's/Clinicians)</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	4		\$0.00		Telephone, Desk, Multiple Line
<b>PRIMARY CARE</b>	<b>WRTM2</b>	<b>1</b>	<b>Tele-Retinal Room</b>						<b>\$0.00</b>	
				A1012	Telephone, Wall Mounted, 1 Line	1		\$0.00		Telephone, Wall Mounted, 1 Line
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5180	Track, Cubicle, Surface Mounted, With Curtain	12		\$0.00		Surface mounted cubicle track, with curtain. Track constructed of thick extruded aluminum. Equipped with self lubricating carriers, beaded drop chain hooks, and flame resistant curtain. To include removable end caps. Designed to be suspended around patient areas where privacy is needed. Price listed is per foot of the track, curtains to be priced per quote.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT030	Countertop, High Pressure Laminate	3		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				F2310	Rack, Pamphlet, Wall Mounted	1		\$0.00		Wall mounted pamphlet rack up to 12 (twelve) pamphlet holding pockets. Unit is used to store and display educational pamphlets.
				F3025	Board, Bulletin, Wood Framed, 36 x 24	1		\$0.00		Bulletin board. Wood framed 1/2" cork posting panel with moisture proof backing. Units are factory assembled and have keyhole hangers for easy installation.
<b>4 - ERRERA CENTER - MENTAL HEALTH</b>										
MENTAL HEALTH		2	Department Circulation							No Additional Schedule B Items
MENTAL HEALTH	CLR03	1	Classroom, Computer						\$0.00	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
MENTAL HEALTH	CRA01	2	Conference Room, Small						\$0.00	
				A1011	Telephone, Desk, 1 Line	1		\$0.00		Telephone, desk, 1 line.
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
MENTAL HEALTH	FSCD1	1	DTC: Social Activities / Dining / Multipurpose						\$0.00	
				A1012	Telephone, Wall Mounted, 1 Line	1		\$0.00		Telephone, wall mounted, 1 line.
				A1080	Mirror, Posture, Wall Mounted	1		\$0.00		Wall mounted posture mirror. Consists of a 1/4" plate glass in a sturdy corrosion resistant frame with water proof back. For educational and therapy programs.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
MENTAL HEALTH	FSNP1	1	DTC: Social Activities Space / Kitchen						\$0.00	
				A1012	Telephone, Wall mounted, one line	1		\$0.00		Telephone, wall mounted, 1 line.
				A1080	Mirror, Posture, Wall Mounted	1		\$0.00		Wall mounted posture mirror. Consists of a 1/4" plate glass in a sturdy corrosion resistant frame with water proof back. For educational and therapy programs.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				C04E0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 2 DO, 36x36x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above solid hinged doors. Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C04P0	Cabinet, Sink, U/C/B, 2 Door, 36x36x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CB020	Cabinet, W/H, 2 Shelf, 1 DO, Sloping Top, 38x24x13	2		\$0.00		Wall hung cabinet with two adjustable shelves, solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings), and sloping top. Also referred to as a solid hinged single door case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT020	Countertop, Solid Surface (Corian) (LF)	8		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
<b>MENTAL HEALTH</b>	<b>OFA03</b>	<b>60</b>	<b>60 Counselor Cubicle</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
<b>MENTAL HEALTH</b>	<b>OFDC1</b>	<b>12</b>	<b>Program Manager Office</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
<b>MENTAL HEALTH</b>	<b>OFDC1</b>	<b>4</b>	<b>Program Manager Office</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
<b>MENTAL HEALTH</b>	<b>OPMH1</b>	<b>7</b>	<b>Meeting</b>						<b>\$0.00</b>	
				F0435	Cabinet, Storage, Multi Media	1		\$0.00		Multi media storage cabinet, approximately 60" high X 36" wide X 14" deep. For the storage of various types of audio or video cassettes, DVDs, CDs, and other media material.
				F3060	Whiteboard, Projection Screen Combination	1		\$0.00		Whiteboard and projection screen combination approximately 48" H x 72" W. Magnetic surface with matte finish for projection. Hard board stabilizer with aluminum foil back. For use with water color pens. Smart Interactive Board
<b>MENTAL HEALTH</b>	<b>RPR01</b>	<b>1</b>	<b>Copy</b>						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				CA040	Cabinet, Open, W/H, 2 Shelf, Sloping Top, 38x36x13	2		\$0.00		Wall hung open front cabinet with two adjustable shelves and sloping top. Also referred to as an open case. For general purpose use throughout the facility.
				CT020	Countertop, Solid Surface (Corian) (LF)	5		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
<b>MENTAL HEALTH</b>	<b>SL001</b>	<b>1</b>	<b>Break Room</b>						<b>\$0.00</b>	
				A1012	Telephone, Wall mounted, one line	1		\$0.00		Telephone, wall mounted, 1 line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				C04P0	Cabinet, Sink, U/C/B, 2 Door, 36x36x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.
				CB020	Cabinet, W/H, 2 Shelf, 1 DO, Sloping Top, 38x24x13	2		\$0.00		Wall hung cabinet with two adjustable shelves, solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings), and sloping top. Also referred to as a solid hinged single door case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT020	Countertop, Solid Surface (Corian) (LF)	7		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
MENTAL HEALTH	SRS01	3	Social Activities Space / Storage							No Additional Schedule B Items
MENTAL HEALTH	TLTU1	4	Toilet, Staff						<b>\$0.00</b>	

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front tinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seal with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>5 - ERRERA CENTER - SUBSTANCE ABUSE</b>										
SUBSTANCE ABUSE		2	Department Circulation							No Additional Schedule B Items
SUBSTANCE ABUSE	OFA01	2	Flex Office						<b>\$0.00</b>	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
SUBSTANCE ABUSE	OFDC1	14	14 Counselor Cubicle						\$0.00	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
SUBSTANCE ABUSE	OFDC1	10	Office						\$0.00	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
SUBSTANCE ABUSE	OFDC1	4	Office						\$0.00	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backslash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
<b>6 - ERRERA CENTER - WELLNESS</b>										
WELLNESS		1	Department Circulation						\$0.00	
				R2201	Fountain, Water, CRS, Wall Mounted, 2 Level	1		\$0.00		Drinking water fountain. This unit is a wall mounted, combination handicap and general public (2 level) dispenser. It contains an air cooled compressor with CRS wall protector. Specify with or without glass filler. It provides cool fresh drinking water, for hospitals and commercial office buildings.
WELLNESS	LR002	2	Wellness Locker Room						\$0.00	

SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List										
Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A1080	Mirror, Posture, Wall Mounted	1		\$0.00		Wall mounted posture mirror. Consists of a 1/4" plate glass in a sturdy corrosion resistant frame with water proof back. For educational and therapy programs.
				A1090	Mirror, Float Glass, With SS Frame & Shelf, 36X1	1		\$0.00		A high quality 1/4" polished float glass mirror, approximately 36" H X 18" W framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners and an integral stainless steel, stain finish, shelf. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in restroom areas, Doctor examination areas, offices, etc. May also be used above double lavatories, either wall or countertop mounted.
				A5145	Hook, Garment, Double, SS, Surface Mounted	12		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5165	Shelf, 5" Depth, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, shelf with a maximum depth of 5". Mounting brackets are welded to shelf. Shelf is available in various widths. For general purpose use in scrub areas/rooms or other areas of the facility where a SS shelf is required. Pricing based upon a 48" width.
<b>WELLNESS</b>	<b>OFDC1</b>	<b>1</b>	<b>Patient Education</b>						<b>\$0.00</b>	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.

SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List										
Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
<b>WELLNESS</b>	<b>PTEA1</b>	<b>1</b>	<b>Wellness Fitness Room</b>						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A1080	Mirror, Posture, Wall Mounted	1		\$0.00		Wall mounted posture mirror. Consists of a 1/4" plate glass in a sturdy corrosion resistant frame with water proof back. For educational and therapy programs.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5180	Track, Cubicle, Surface Mounted, With Curtain	12		\$0.00		Surface mounted cubicle track, with curtain. Track constructed of thick extruded aluminum. Equipped with self lubricating carriers, beaded drop chain hooks, and flame resistant curtain. To include removable end caps. Designed to be suspended around patient areas where privacy is needed. Price listed is per foot of the track, curtains to be priced per quote. Private Treatment Area
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
<b>WELLNESS</b>	<b>USCL1</b>	<b>1</b>	<b>Soiled Utility Room</b>						<b>\$0.00</b>	
				A1012	Telephone, Desk, With Speaker	1		\$0.00		Telephone, Wall Mounted, 1 Line

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C05P0	Cabinet, Sink, U/C/B, 2 Door, 36x48x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.
				CS200	Sink, SS, Single Compartment, 12x28x16 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface.
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backslash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				E1500	Rail, MOD, W/MNTD, HX144XD	1		\$0.00		Wall mounted rail used for hanging (mounting) lockers, shelves drawers on a wall.
<b>WELLNESS</b>	<b>TLTS1</b>	<b>2</b>	<b>Wellness Showers</b>						<b>\$0.00</b>	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5030	Bench, Stall, Shower, Built In	1		\$0.00		Shower bench; built-in. Eighteen (18) gauge stainless steel frame with anchors built-in into the wall. Size and shape as required.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5110	Grab Bar, 1-1/4" Dia., SS, 2 Wall, Shower Use	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall shower, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical applications in shower stalls where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5170	Rod, Shower Curtain, 1"Diameter, W/Curtain & Hooks	1		\$0.00		A concealed mounted, 1" outside diameter, satin finish stainless steel, shower curtain rod with white vinyl shower curtain (72" H) and SS shower curtain hooks. Rod and curtain available in various widths. For general purpose use at shower stall or bathtub locations. Pricing based upon standard shower stall dimensions of 36" x 36" and a standard curtain height of 72".
				A5175	Soap Dish, With Bar, SS, Recessed	1		\$0.00		A recessed mounted, satin finish stainless steel, soap dish with bar. Soap dish furnished with retaining lip and mounting clamp for installation in stud walls or countertop aprons. For general purpose use in shower stalls or at bathtub locations.
				A5205	Bar, Towel, 1" Diameter, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, 1" diameter, towel bar. Support posts and flanges are one piece, chrome-plated, cast heavy brass with satin finish. Towel bar shall not rotate within support posts. Available in 18", 24" and 30" widths. For general purpose use in shower or bathtub rooms. Pricing based upon a suggested standard width of 18".
				P5040	Shower, Single, Hand-Held	1		\$0.00		A complete, barrier-free, single hand-held, personal shower system. The shower system includes: pressure balanced mixing valve with high temperature limit stop; personal hand shower; shower hose; wall supply; and slide bar. For general purpose use throughout the facility in shower stalls.
<b>WELLNESS</b>	<b>TLTU1</b>	<b>2</b>	<b>Wellness Toilets</b>						<b>\$0.00</b>	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.

SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List										
Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>WELLNESS</b>	<b>UCCL1</b>	<b>1</b>	<b>Utility Room, Clean</b>						<b>\$0.00</b>	
				P8710	Utility Center, Plumbing Connection	1		\$0.00		Plumbing connection utility center, sometimes referred to as a 'GUY GRAY BOX'. This recessed utility center provides for hot and cold water connections and a drain connection at sink and other equipment locations. The utility center includes cutoff valves for the water connections, a plug seal for the drain and an outside cover to provide an aesthetic appearance when connections are no longer required. This center may be installed in locations where no plumbing fixtures are included in a design as a future flexibility device, saving many dollars for later facility modifications to incorporate sinks as functions change.
<b>7 - OFFICE SPACE - NATIONAL PROGRAMS</b>										
NATIONAL PROGRAMS		3	Department Circulation							No Additional Schedule B Items
NATIONAL PROGRAMS	CRA01	3	Conference Room, Small						<b>\$0.00</b>	
				A1011	Telephone, Desk, 1 Line	1		\$0.00		Telephone, desk, 1 line.
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
<b>NATIONAL PROGRAMS</b>	<b>EXRG0</b>	<b>2</b>	<b>Exam Room - Research Programs</b>						<b>\$0.00</b>	
				A1012	Telephone, Desk, With Speaker	1		\$0.00		Telephone, Wall Mounted, 1 Line
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5180	Track, Cubicle, Surface Mounted, With Curtain	12		\$0.00		Surface mounted cubicle track, with curtain. Track constructed of thick extruded aluminum. Equipped with self lubricating carriers, beaded drop chain hooks, and flame resistant curtain. To include removable end caps. Designed to be suspended around patient areas where privacy is needed. Price listed is per foot of the track, curtains to be priced per quote.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT030	Countertop, High Pressure Laminate	3		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backslash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				F2310	Rack, Pamphlet, Wall Mounted	1		\$0.00		Wall mounted pamphlet rack up to 12 (twelve) pamphlet holding pockets. Unit is used to store and display educational pamphlets.
				F3025	Board, Bulletin, Wood Framed, 36 x 24	1		\$0.00		Bulletin board. Wood framed 1/2" cork posting panel with moisture proof backing. Units are factory assembled and have keyhole hangers for easy installation.
<b>NATIONAL PROGRAMS</b>	<b>OFA01</b>	<b>2</b>	<b>Flex Office</b>						<b>\$0.00</b>	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
NATIONAL PROGRAMS	OFA02	1	Office - National DSS Office							
NATIONAL PROGRAMS	OFA02	1	Office - National Hepatitis C Resource Center							
NATIONAL PROGRAMS	OFA02	1	Office - National HIV Office							
NATIONAL PROGRAMS	OFA02	8	Office - National PTSD							
NATIONAL PROGRAMS	OFA02	1	Office - National Women's Center							
NATIONAL PROGRAMS	OFA02	2	Office - PRIME Center							
		14	TOTAL						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
NATIONAL PROGRAMS	OFA02	9	Office - Tele-Mental Health						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	2		\$0.00		Telephone, desk, multiple line.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
NATIONAL PROGRAMS	OFA03	1	1 CUBICLE - National DSS Office							
NATIONAL PROGRAMS	OFA03	1	1 CUBICLE, National Hepatitis C Resource Center							
NATIONAL PROGRAMS	OFA03	2	2 CUBICLE, National Women Center							
NATIONAL PROGRAMS	OFA03	7	7 Flex CUBICLE							
NATIONAL PROGRAMS	OFA03	8	8 CUBICLE, Prime Center							
NATIONAL PROGRAMS	OFA03	9	9 CUBICLE, Tele-Mental Health							
NATIONAL PROGRAMS	OFA03	17	17 CUBICLE, National PTSD							
		45	Total						<b>\$0.00</b>	
				A1016	Telephone, Desk, With Speaker	1		\$0.00		Telephone, desk, with speaker.
NATIONAL PROGRAMS	OFDC1	1	Flex Office						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	2		\$0.00		Telephone, desk, multiple line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock, front hinged at bottom, and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	2		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				CD040	Cabinet, W/H, 2 Shelf, 2 DO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, solid hinged doors, and sloping top. Also referred to as a solid hinged double door wall case. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT030	Countertop, High Pressure Laminate	3		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
<b>NATIONAL PROGRAMS</b>	<b>RPR01</b>	<b>1</b>	<b>Support: Copy Room</b>						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				C02C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x24x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				CA040	Cabinet, Open, W/H, 2 Shelf, Sloping Top, 38x36x13	2		\$0.00		Wall hung open front cabinet with two adjustable shelves and sloping top. Also referred to as an open case. For general purpose use throughout the facility.
				CT020	Countertop, Solid Surface (Corian) (LF)	5		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
<b>NATIONAL PROGRAMS</b>	<b>SL001</b>	<b>1</b>	<b>Break Room</b>						<b>\$0.00</b>	
				A1012	Telephone, Wall mounted, one line	1		\$0.00		Telephone, wall mounted, 1 line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5210	Bracket, Television, Wall Mounted, w/Adjust Arm	1		\$0.00		Wall mounted television bracket with adjustable arm. Consists of platform movable arm with full 120 degree swivel. Designed for holding wall mounted television units in patient rooms.
				A5220	Bracket, Television, Wall Backing	1		\$0.00		Wall mounted television bracket backing which provides additional support and strength for the installation of the television bracket. Option available for interior or exterior plate and sized for 12" 16" or 24" stud spacing.
				C02D0	Cabinet, U/C/B, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				C04E0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 2 DO, 36x36x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above solid hinged doors. Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C04P0	Cabinet, Sink, U/C/B, 2 Door, 36x36x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.
				CB020	Cabinet, W/H, 2 Shelf, 1 DO, Sloping Top, 38x24x13	2		\$0.00		Wall hung cabinet with two adjustable shelves, solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings), and sloping top. Also referred to as a solid hinged single door case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
				CT020	Countertop, Solid Surface (Corian) (LF)	8		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
NATIONAL PROGRAMS	SRSE1	1	Shared Storage Space							No Additional Schedule B Items
NATIONAL PROGRAMS	TLTU1	4	Toilet						<b>\$0.00</b>	

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front tinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seal with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>8 - CANTEEN</b>										
<b>CANTEEN</b>	<b>FSCD1</b>	<b>1</b>	<b>Canteen</b>						<b>\$0.00</b>	
				A6030	Machine, Vending	2		\$0.00		This JSN is to be used for determining and defining the requirement for vending machines. Item is normally leased. VA provided

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.
<b>CANTEEN</b>	<b>SRS01</b>	<b>1</b>	<b>Canteen Storage</b>						<b>\$0.00</b>	
				F3025	Board, Bulletin, Wood Framed	1		\$0.00		Bulletin board approximately 36"W x 24"H. Wood framed 1/2" cork posting panel with moisture proof backing. Units are factory assembled and have keyhole hangers for easy installation.
				CT020	Countertop, Solid Surface (Corian) (LF)	8		\$0.00		A solid, nonporous countertop with a smooth seamless appearance. Easy to clean and maintain and with proper cleaning does not support the growth of mold. An acrylic-based solid surface product. Standard thickness of 1", and a 4" bull backsplash/curb. Also referred to as a work surface or work top. Available in a choice of colors and depths. Used in lab and other hospital areas requiring optimum physical and chemical resisting properties.
				C04E0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 2 DO, 36x36x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above solid hinged doors. Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02D0	Cabinet, Base, 4 Drawer, 36x24x22	1		\$0.00		Standing height under counter base cabinet with four full width drawers of equal height. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				C04P0	Cabinet, Sink, U/C/B, 2 Door, 36x36x22	1		\$0.00		Standing height under counter base sink cabinet with solid hinged doors. Also referred to as a double-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.
				CB020	Cabinet, W/H, 2 Shelf, 1 DO, Sloping Top, 38x24x13	2		\$0.00		Wall hung cabinet with two adjustable shelves, solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings), and sloping top. Also referred to as a solid hinged single door case. For general purpose use throughout the facility.
				CS010	Sink, SS, Single Compartment, 7.5x12x12 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				K6660	Sink, Scullery, Triple Compartment	1		\$0.00		Three compartment scullery sink with drainboards. The sink bowls are one piece, deep drawn, seamless 16 gauge stainless steel with coved corners. This unit is often modified on site to include a hot water dispenser, a disposal unit (see JSN K2620) and a whirlpool for water circulation and cleaning. It is also frequently a component of a dish-table system leading to a dishwasher. The database pricing is for the sink only. This unit is used in large production kitchens to clean dishes.
<b>9 - POLICE AND SECURITY</b>										
POLICE AND SECURITY	LR001	1	Locker Room							No Additional Schedule B Items
POLICE AND SECURITY	SRS01	1	Holding Room						\$0.00	
				A5020	Bench, Locker Room, Floor Mounted	1		\$0.00		Locker room bench. Floor mounting -1-1/4" thick. Benches are sanded smooth with two coats of moisture-resistant sealer to ensure a protective, satin gloss surface, and mounted on strong steel pedestal anchored to the floor. Over all height of 18" includes pedestal. Size as required.
POLICE AND SECURITY	SSS01	1	Secure Storage, Safe							No Additional Schedule B Items
POLICE AND SECURITY	TLTU1	1	Toilet, Staff						\$0.00	
				A1066	Mirror, Float Glass, With SS Frame	1		\$0.00		A high quality 1/4" polished float glass mirror 36X18, framed in a one-piece, bright polished, stainless steel channel frame with 90° mitered corners. All edges of the mirror are protected by absorbing filler strips. Mirror has a galvanized steel back with integral horizontal hanging brackets and wall hanger for concealed mounting. For mounting above single wall mounted lavatories located in toilet areas, Doctors examination offices, etc. May also be used above double lavatories, either wall or countertop mounted, found in restroom areas.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				A5090	Disposal, Sanitary Napkin, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, sanitary napkin disposal. Disposal features a flip-up cover, secured to the container by a heavy duty stainless steel piano-hinge. Disposal may be secured to wall or toilet partition. For general purpose use in female toilet stalls or rooms and unisex toilet rooms.
				A5109	Grab Bar, 1-1/4" Dia., SS, 2 Wall, W/C Accessible	1		\$0.00		A 1-1/4" diameter, satin finish stainless steel, peened gripping surface, 2 wall toilet stall/ room, grab bar with concealed mounting flanges. Snap over flanges are provided to conceal mounting screws. A selection of mounting kits and concealed anchor devices are available from the manufacturers for different types of installations. Grab bar shall comply with barrier-free accessibility guidelines for structural strength. For typical water closet applications in toilet stalls and rooms where ADA (American's With Disabilities Act) requirements must be met.
				A5145	Hook, Garment, Double, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, double garment hook. Equipped with a concealed mounting bracket that is secured to a concealed wall plate. For general purpose use throughout the facility to hang various items of apparel.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A5200	Dispenser, Toilet Tissue, SS, 2-Roll, Surface Mntd	1		\$0.00		A concealed surface mounted, double roll, satin finish stainless steel, toilet tissue dispenser. Unit accommodates two standard-core toilet tissue rolls through 5" in diameter. Spindles are chrome plated plastic with a heavy-duty internal spring and turn freely for non-controlled delivery. For general purpose use in restrooms.
				P3100	Lavatory, Vitreous China, Slab Type	1		\$0.00		Wall mounted, slab type, vitreous china, lavatory (approximate bowl size 7"x15"x10") with: faucet holes on 4" centers; gooseneck spout; wrist blade handles; and grid strainer. It shall be suitable for use in clinics, offices, washrooms or patient care area.
				P9050	Toilet, Wall Hung, Siphon Jet	1		\$0.00		Siphon jet water closet/ toilet. This unit is wall hung with an elongated bowl, top spud flush valve, seat with open front and check hinge, and carrier. Used throughout the health care facility in restrooms.
<b>POLICE AND SECURITY</b>	<b>XXYYZ</b>	<b>1</b>	<b>Operations Room</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				A5120	Window, Observation, One Way	2		\$0.00		One way observation window. Window frame mounted inside wall opening on an aluminum frame. Size as required. For use in pediatrics, occupational therapy and psychiatry. Typical size is 36" x 36".
				C0045	Frame, Apron, 1 Drawer, 4x36x22	1		\$0.00		Apron frame with one standard drawer. Also referred to as a drawer frame or table frame. Used for a knee space as a combination frame and drawer to support a top between base cabinets or a base cabinet and a wall. Constructed of steel.
				C0046	Frame, Apron, 2 Drawer, 4x48x22	1		\$0.00		Apron frame with two standard drawers. Also referred to as a drawer frame or table frame. Used for a knee space as a combination frame and drawers to support a top between base cabinets or a base cabinet and a wall.
				C06M0	Cabinet, U/C/B, 1 PBD, 2 DR, 1 File DR, 30x18x22	1		\$0.00		Sitting height under counter base cabinet with a pullboard above two drawers and file drawer. Also referred to as a drawer cabinet. For general purpose use throughout the facility.
				C09F0	Cabinet, U/C/B, 2 Half Drawer, 2 Door, 36" W	1		\$0.00		Sitting height under counter base cabinet, 30" H x 36" W x 22" D with two half width drawers above solid hinged doors. Also referred to as a combination cabinet or drawer and cupboard cabinet. For general purpose use throughout the facility.
				C09G0	Cabinet, U/C/B, 1 Shelf, 2 Door, 30x36x22	1		\$0.00		Sitting height under counter steel base cabinet with one adjustable shelf and solid hinged doors. Also referred to as a cupboard or door cabinet. For general purpose use throughout the facility.
				CG040	Cabinet, W/H, 2 SH, 2 SGDO, Sloping Top, 38x36x13	1		\$0.00		Wall hung cabinet with two adjustable shelves, framed-glass sliding doors, and sloping top. Also referred to as a framed-glass sliding double door wall case. For general purpose use throughout the facility.
				CG050	Cabinet, W/H, 2 SH, 2 SGDO, Sloping Top, 38x48x13	1		\$0.00		Wall hung steel cabinet with two adjustable shelves, framed-glass sliding doors, and sloping top. Also referred to as a framed-glass sliding double door wall case. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	1		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
				F3050	Whiteboard, Dry Erase	1		\$0.00		Whiteboard unit, approximately 36" H x 48" W consisting of a white porcelain enamel writing surface with an attached chalk tray. Magnetic surface available. Image can be easily removed with a standard chalkboard eraser. For use with water color pens. Unit is ready to hang.
<b>10 - LOGISTICS</b>										
<b>LOGISTICS</b>	<b>BMER1</b>	<b>1</b>	<b>Biomedical Engineering Repair Shop</b>						<b>\$0.00</b>	
				A1011	Telephone, Desk, 1 Line	1		\$0.00		Telephone, desk, 1 line.
				A5080	Dispenser, Paper Towel, SS, Surface Mounted	1		\$0.00		A surface mounted, satin finish stainless steel, single-fold, paper towel dispenser. Dispenser features: tumbler lock; front hinged at bottom; and refill indicator slot. Minimum capacity 400 single-fold paper towels. For general purpose use throughout the facility.
				C01C0	Cabinet, U/C/B, 1 Shelf, 1 Drawer, 1 DO, 36x18x22	1		\$0.00		Standing height under counter base cabinet with an adjustable shelf and a full width drawer above a solid right or left-hinged door (appropriate door hinge configuration to be indicated on equipment elevation drawings). Also referred to as a combination cabinet or a drawer and cupboard cabinet. For general purpose use throughout the facility.
				C02Q0	Cabinet, Sink, U/C/B, 1 Door, 36x24x22	1		\$0.00		Standing height under counter base sink cabinet with a solid right or left-hinged door (appropriate door configuration to be indicated on equipment elevation drawings). Also referred to as a single-door sink cabinet. For general purpose use throughout the facility where a sink is to be used. Coordinate actual clear cabinet dimension with the actual outside dimension of sink that is specified to ensure that they are compatible.
				CS150	Sink, SS, Single Compartment, 10x19x16 ID	1		\$0.00		Single compartment stainless steel sink, drop-in, self-rimming, ledge-type, connected with a drain and provided with a mixing faucet. It shall also be provided with pre-punched fixture holes on 4" center, integral back ledge to accommodate deck-mounted fixtures, brushed/polished interior and top surfaces, and sound deadened. Recommended for use in suspended or U/C/B sink cabinets having a high plastic laminate or Chemsurf laminate countertop/work surface. Coordinate actual outside sink dimensions with the actual clear dimension of cabinet specified to ensure that they are compatible. For general purpose use throughout the facility.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				CT030	Countertop, High Pressure Laminate	4		\$0.00		High pressure laminate countertop (composition of wood particle core with plastic laminate surface) having a hard smooth surface finish, standard thickness of 1", and a 4" butt backsplash/curb. Also referred to as a work surface or work top. Available in a wide choice of colors, patterns, and depths. Used in general purpose areas requiring a basic work surface arrangement with limited heat resistance and poor chemical resistance. Pricing based upon a 24" depth.
<b>LOGISTICS</b>	<b>DOCK1</b>	<b>1</b>	<b>Receiving and Shipping Dock</b>						<b>\$0.00</b>	
				K0450	Curtain, Air	1		\$0.00		Air curtain. The unit is generally fabricated to size for operation. This unit is used at entrances and docks to prevent cold and humid or dry and hot air from entering through openings which are exposed to weather conditions. The database pricing reflects an unheated air door 6-1/2' wide with a 3" or 6" deep discharge nozzle to cover a standard two-door width entry. Some units run on 120V power; refer to the manufacturer's specifications for the model chosen. Larger width and industrial duty air doors are available.
<b>LOGISTICS</b>	<b>MMGS1</b>	<b>1</b>	<b>Storage, Medical and General</b>							No Additional Schedule B Items
<b>LOGISTICS</b>	<b>MMRP1</b>	<b>1</b>	<b>Receiving and Issue area</b>						<b>\$0.00</b>	
				A1015	Telephone, Desk, Multiple Line	1		\$0.00		Telephone, desk, multiple line.
				P1950	Eyewash, Floor Mounted	1		\$0.00		Pedestal standing eye wash station. Unit is hand operated to provide streams of water to clean foreign particles or liquids from the eyes in emergency situations. Used in laboratories and hospital areas where employees are susceptible to exposure to foreign, caustic or irritating matter to the eyes.
<b>LOGISTICS</b>	<b>SRGC1</b>	<b>1</b>	<b>Storage, Medical Gas</b>						<b>\$0.00</b>	
				M2025	Rack, Storage, Cylinder, Gas	2		\$0.00		Medical gas cylinder storage rack. Unit is a modular cage frame for holding various sizes of gas cylinders. Nylon or fabric securing straps can be attached to the frame bars to stabilize gas cylinders. Add additional units or specify size as required when ordering. This item is often locally fabricated.
<b>LOGISTICS</b>	<b>SRHM1</b>	<b>1</b>	<b>Storage, Bio-hazard Waste</b>						<b>\$0.00</b>	
				M2020	Cabinet, Storage, Safety, Built-In, Vented	1		\$0.00		Safety storage cabinet. This unit is of double steel wall construction, with vented grounding attachment, raised leak proof door sill, and adjustable shelving. Equipped with two doors and three-point key lock. The construction meets standards set by OSHA and NFPA Code 30 requirements. Designed for storage of flammable type liquids. The cabinet fits into a laboratory casework configuration and its ventilation ports are in the back to leave the counterspace free. The cabinet requires ventilation ducting and an exhaust fan as part of the HVAC (heating, ventilation and air conditioning) system.
				P2450	Valve, Mixing, Thermostatic	1		\$0.00		Thermostatic mixing valve with washout hose. Used with portable whirlpool equipment. Thermostatic valve is used to maintain temperature between 70 and 110 degree Fahrenheit, with a flow rate of 20 gallons a minute. The washout hose assembly used to wash out tanks after treatment. Used in physical therapy department to provide comfortable water temperature for patient treatments.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				P5210	Shower, Safety, Freestanding, With Eye/Face Wash	1		\$0.00		Deluge safety shower. This is a complete, maximum protection safety station consisting of a free-standing emergency shower and an eye/face wash fixture. Used anywhere exposure to hazardous substances may occur.
LOGISTICS	SRSE1	1	EMS Storage							No Additional Schedule B Items
<b>11 - INFORMATION RESOURCE MANAGEMENT</b>										
IRM	COMC1	2	Communications Room							No Additional Schedule B Items
IRM	TEDR1	1	OIT: Demarc						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				A0926	Cabinet, Fiber Optic, Enclosure/Housing	1		\$0.00		A wall mountable cabinet/enclosure to provide fiber optic interconnection or cross-connection capabilities between electronics and outside the facility distribution cables. Cabinets will be designed to maximize utility and ease of installation. The cabinets will support a wide range of facility applications from data centers to building backbone, horizontal and entrances. The cabinets shown are for pricing purposes and are approximately 16"H x 19W x 6"D. Cabinets come in numerous sizes and specific applications that are to be determined at time of purchase.
				R3000	Air Conditioner, Computer Room	1		\$0.00		Process cooling, split system or chilled water, air conditioning unit(s) designed for computer room use. Unit(s) shall be packaged, factory assembled, prewired, and pre-piped; consisting of cabinet, fans, filters, humidifier, and controls.
IRM	TETR1	2	OIT						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.
				A0926	Cabinet, Fiber Optic, Enclosure/Housing	1		\$0.00		A wall mountable cabinet/enclosure to provide fiber optic interconnection or cross-connection capabilities between electronics and outside the facility distribution cables. Cabinets will be designed to maximize utility and ease of installation. The cabinets will support a wide range of facility applications from data centers to building backbone, horizontal and entrances. The cabinets shown are for pricing purposes and are approximately 16"H x 19W x 6"D. Cabinets come in numerous sizes and specific applications that are to be determined at time of purchase.
				M0446	Miscellaneous Medical Systems	1		\$0.00		Equipment as required for installation and connection of the miscellaneous medical equipment and systems, including: Psychiatric (mental health) Security Unit Door Signal Systems; Narcotics Storage Signal Systems; and Elapsed Time Indicators.
				A1052	Fire Detection and Alarm System	1		\$0.00		Equipment as required for fully functioning Fire Detection and Alarm system.
				R3000	Air Conditioner, Computer Room	1		\$0.00		Process cooling, split system or chilled water, air conditioning unit(s) designed for computer room use. Unit(s) shall be packaged, factory assembled, prewired, and pre-piped; consisting of cabinet, fans, filters, humidifier, and controls.
IRM	TETR1	2	Yale CIs						<b>\$0.00</b>	
				A1014	Telephone, Wall Mounted, 1 Line, With Speaker	1		\$0.00		Telephone, wall mounted, 1 line, with speaker.

**SCHEDULE B--SPECIAL REQUIREMENTS: Functional Room List**

Department / Functional Area	Room Code	Qty of Rooms	Function	Equipment Symbol or JSN Code	Item Description	Qty	Unit Cost	Extension	Subtotal	Notes
				A0926	Cabinet, Fiber Optic, Enclosure/Housing	1		\$0.00		A wall mountable cabinet/enclosure to provide fiber optic interconnection or cross-connection capabilities between electronics and outside the facility distribution cables. Cabinets will be designed to maximize utility and ease of installation. The cabinets will support a wide range of facility applications from data centers to building backbone, horizontal and entrances. The cabinets shown are for pricing purposes and are approximately 16"H x 19W x 6"D. Cabinets come in numerous sizes and specific applications that are to be determined at time of purchase.
				R3000	Air Conditioner, Computer Room	1		\$0.00		Process cooling, split system or chilled water, air conditioning unit(s) designed for computer room use. Unit(s) shall be packaged, factory assembled, prewired, and pre-piped; consisting of cabinet, fans, filters, humidifier, and controls.
<b>12 - BUILDING SUPPORT</b>										
BUILDING SUPPORT		1	Electrical Room							Provided by Lessor
BUILDING SUPPORT		2	Electrical Room							Provided by Lessor
BUILDING SUPPORT		1	Fire							Provided by Lessor
BUILDING SUPPORT		1	Mech/Elec							Provided by Lessor
<b>BUILDING SUPPORT</b>	<b>JANC1</b>	<b>3</b>	<b>Janitors Closet</b>						<b>\$0.00</b>	
				A5135	Shelf, Utility W/ Mop/Broom Holders, SS, Surf Mntd	1		\$0.00		A surface mounted, satin finish stainless steel, utility shelf with a maximum of 6 mop/broom holders and 5 rag hooks. Utility shelf features: 8" deep shelf; mounting brackets welded to shelf; spring activated rubber cam holders; and drying rod. Unit is available in various widths 30" (minimum, 3 holders and 2 hooks) to 48" (maximum, 6 holders and 5 hooks). For use in janitor closets. Pricing based on a 36" width.
				P4700	Sink, Mop, Molded Stone	1		\$0.00		Mop service sink approximately 10"H x 36"W x 24"D. Also called a mop service basin and a mop receptor. Unit is made of molded stone and is a one piece item. It shall include a service faucet hose, hose bracket and mop hanger
<b>13 - BUILDING CIRCULATION</b>										
BUILDING CIRCULATION		2	Building Circulation							No Additional Schedule B Items

**PART III: SCHEDULE B--SPECIAL REQUIREMENTS (cont.)**

**SECTION 5--SUMMARY PRICE SHEET**

		Qty	Unit	Unit Cost	Cost	Total
<b>SPECIAL ITEMS FOR THE ENTIRE CLINIC</b>						
<b>Public Address and Mass Notification Systems</b>						
JSN A1051 -Equipment as required for fully operating Emergency/Public Safety Public Address and Mass Notification communication (PA) system.						
	Central Equipment	1	ls		\$0.00	
	Speakers	11	ea		\$0.00	
						\$0.00
<b>Audio Visual, Nurse Call and Code One (Blue) System</b>						
JSN A1050 -Equipment as required for fully operating Critical Service Nurse-Call and Life Safety Code Blue communication system.						
	Central Equipment	1	ls		\$0.00	
	Master Station, Nurse Call, Duty Station	5	ea		\$0.00	
	Nurse Call Emergency Station w/ corridor signal light	18	ea		\$0.00	
						\$0.00
<b>Master Antenna Television (Broadband) System</b>						
JSN M0445 -Equipment as required for fully operating Master Antenna Television (TV) system.						
	Central Equipment	1	ls		\$0.00	
	Outlets	24	ea		\$0.00	
						\$0.00
<b>Motion Intrusion Detector (MID)</b>						
JSN A1023 -Equipment as required for fully functioning Intrusion Detection System, referred to as IDS.						
	Central Equipment	1	ls		\$0.00	
	Annunciation Panels	1	ea		\$0.00	
	Detectors	6	ea		\$0.00	
						\$0.00
<b>Security Management and Control, and Centralized Police Security Management Systems</b>						
	Central Equipment	1	ls		\$0.00	
	Annunciation Panels	1	ea		\$0.00	
	Outlets	13	ea		\$0.00	
						\$0.00
JSN A1026 -Equipment as required for fully functioning Detection and Screening System, referred to as the Security Access Detection system.						
	Security Access Detection	1	ea		\$0.00	
						\$0.00
<b>Radio Paging System</b>						
	Central Equipment	1	ls		\$0.00	
	Radio Devices	1	ea		\$0.00	
						\$0.00
<b>Two-Way Radio System</b>						
	Central Equipment	1	ls		\$0.00	
	Radio Devices	3	ea		\$0.00	
						\$0.00
<b>Patient (also Staff) Locator/Annunciator System</b>						
	Central Equipment	1	ls		\$0.00	
	Annunciation Panels	1	ea		\$0.00	
	Devices	1	ea		\$0.00	
						\$0.00
<b>Radio Entertainment Distribution (RED)</b>						
	Central Equipment	1	ls		\$0.00	
	Annunciation Panels	1	ea		\$0.00	
	Detectors	5	ea		\$0.00	
						\$0.00
<b>Security Emergency Call / Duress Alarm / Telecommunications Systems (Panic Button)</b>						

**PART III: SCHEDULE B--SPECIAL REQUIREMENTS (cont.)**

**SECTION 5--SUMMARY PRICE SHEET**

	Qty	Unit	Unit Cost	Cost	Total
JSN A1022 -Equipment as required for fully operating Security Emergency Call / Duress Alarm / Telecommunications systems.					
Central Equipment	1	ls		\$0.00	
Annunciation Panels	1	ea		\$0.00	
Panic Buttons	97	ea		\$0.00	
JSN A1025 -Equipment as required for fully functioning Duress-Panic Alarms, Emergency Phones/ CallBoxes, and Intercom Systems, referred to as EPPS System.					
Electronic Personal Protection	5	ea		\$0.00	\$0.00
<b>Video Surveillance CCTV Monitoring</b>					
JSN M0436 -Equipment as required for fully functioning Video Surveillance System, which is identified as the Closed Circuit Television System, referred to as the CCTV System.					
Central Equipment	1	ls		\$0.00	
Monitoring Stations	1	ea		\$0.00	
Cameras	5	ea		\$0.00	\$0.00
<b>Intercommunications and Program Systems</b>					
JSN A1040(2) -Equipment as required for fully operating Intercommunications system.					
Central Equipment	1	ls		\$0.00	
Master Station	1	ea		\$0.00	
Staff Stations	2	ea		\$0.00	\$0.00
<b>Video Teleconferencing System (VTEL)</b>					
Central Equipment	1	ls		\$0.00	
Outlets	12	ea		\$0.00	
JSN M0400 Screen, Projection, 144x144, Remote Control					
Screen, Projection	3	ea		\$0.00	\$0.00
<b>VA Satellite TV System</b>					
Installation of VA Furnished Satellite Dish and Head-end Equipment	1	ls		\$0.00	
Outlets	14	ea		\$0.00	\$0.00
<b>Electronic Access Control, Database Management, And Door Control</b>					
JSN A1020 -Equipment as required for fully functioning Access Control System and Database Management system.					
Central equipment, annunciator panel, programming, 500 cards	1	ls		\$0.00	
Cards	1	per 100		\$0.00	\$0.00
<b>The quantities between the Schedules B and C should be coordinated to prevent double counting.</b>					
<b>SUBTOTAL SPECIAL ITEMS FOR THE ENTIRE CLINIC</b>					<b>\$0.00</b>

**PART III: SCHEDULE B--SPECIAL REQUIREMENTS (cont.)**

**SECTION 5--SUMMARY PRICE SHEET**

	Qty	Unit	Unit Cost	Cost	Total
<b>FUNCTIONAL ROOM LISTINGS</b>					
1 - ERRERA CENTER - LOBBY					\$0.00
2 - ERRERA CENTER - HEALTHCARE ADMINISTRATION					\$0.00
3 - ERRERA CENTER - PRIMARY CARE					\$0.00
4 - ERRERA CENTER - MENTAL HEALTH					\$0.00
5 - ERRERA CENTER - SUBSTANCE ABUSE					\$0.00
6 - ERRERA CENTER - WELLNESS					\$0.00
7 - OFFICE SPACE - NATIONAL PROGRAMS					\$0.00
8 - CANTEEN					\$0.00
9 - POLICE AND SECURITY					\$0.00
10 - LOGISTICS					\$0.00
11 - INFORMATION RESOURCE MANAGEMENT					\$0.00
12 - BUILDING SUPPORT					\$0.00
13 - BUILDING CIRCULATION					\$0.00
<b>SUBTOTAL FUNCTIONAL ROOM LISTINGS</b>					<b>\$0.00</b>
<b>TOTAL PRICE FOR SCHEDULE B--SPECIAL REQUIREMENTS</b>					<b>\$0.00</b>