



## **SCOPE OF WORK**

### **Manufacture Fire Sprinkler Materials**

**Renovate 7<sup>th</sup> Floor, Building 1 for Administrative Offices**

**Project # 570-13-202**

**March 11, 2016**

The project scope of work is: Manufacturer shall provide all necessary piping, fittings and components for the complete fire sprinkler system for the 7<sup>th</sup> floor of Building 1. Scope of work to include all material as necessary to complete the work described below.

All work shall be completed at the Central California Healthcare System located at 2615 E. Clinton Fresno, California 93703. Prior to the award, the contractor shall submit to the Contracting Officer a fee proposal and their proposed schedule for review and written acceptance.

#### **Statement of Work:**

Provide the following material as described below.

- Provide a complete material manifest, hydraulic calculations and plans stamped and signed by Fire Protection Engineer.
- Address review comments arising from VA plan review.
- All materials, fittings and components shall comply with applicable Codes and the attached specifications.

#### **Inclusions:**

Contract duration for the completion of the fire sprinkler system material is 45 calendar days after the NTP.

- Furnish all required piping, fittings, components, sprinkler heads and seismic braces as necessary for complete system. Manufacturer shall include the required fittings to tie into the existing fire sprinkler risers.
- Close-out manuals on supplied material, components and sprinkler heads.
- Spare parts to include sprinkler cabinet, 5% spare sprinklers with escutcheons with a minimum of two of each type/or as required by NFPA 13, whichever is greater, and two of each type of sprinkler wrenches used.
- Proposal shall include freight charges to deliver all material FOB to the address listed above.

**Exclusions:**

- Installation labor and equipment.

Technical Point of Contact: James Everett (559) 225-6100 x4535