TEST THE DOMESTIC WATER SYSTEM BY FILLING IT WITH WATER AND THEN ISOLATING THE SYSTEM FROM ITS SOURCE. KEEP THE SYSTEM CLOSED FOR A PERIOD OF TWENTY-FOUR HOURS, WITH NO FIXTURE BEING USED. THE PRESSURE DIFFERENTIAL FOR THIS TEST PERIOD SHALL NOT EXCEED 10 PSIG. TEST WATER PIPING TO A 125 PSI HYDROSTATIC PRESSURE.

15B GUARANTEE

THE WORK TO BE PERFORMED UNDER THIS CONTRACT SHALL INCLUDE THE FURNISHING, INSTALLATION, AND CONNECTION OF PLUMBING SYSTEMS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS. BY SIGNING THE CONTRACT, THE CONTRACTOR ACKNOWLEDGES THAT HE HAS ACQUAINTED HIMSELF WITH THE SITE AND THE EXISTING CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED, AND THE DRAWINGS AND SPECIFICATIONS PERTAINING THERETO, AND HE INDICATES THAT HE WILL COMPLY WITH THE REQUIREMENTS AND INTENT OF PERTINENT DOCUMENTS IN THE PERFORMANCE OF THE WORK.

GUARANTEE THAT THE PLUMBING INSTALLED UNDER THIS CONTRACT IS FREE OF DEFECTS IN WORKMANSHIP AND MATERIALS FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF JOB ACCEPTANCE BY THE OWNER. THIS SHALL INCLUDE A GUARANTEE OF FREE CIRCULATION OF LIQUIDS THROUGHOUT THE SYSTEM AS INTENDED WITHOUT LEAKS, EXCESSIVE NOISE, OR WATER HAMMER.

IF DEFECTS OCCUR DURING THE ONE YEAR GUARANTEE PERIOD, REPAIR OR REPLACE SUCH DEFECTS AT NO EXPENSE TO THE OWNER, AND TO THE SATISFACTION OF THE OWNER, ARCHITECT AND ENGINEER.

15B VIBRATION ISOLATION

MANUFACTURERS: PROVIDE VIBRATION ISOLATION EQUIPMENT AND MATERIALS BY A SINGLE MANUFACTURER. APPROVED MANUFACTURERS PROVIDED THEIR SYSTEMS ARE IN COMPLIANCE WITH THE SPECIFIED DESIGN AND PERFORMANCE REQUIREMENTS INCLUDE AMBER BOOTH, KINETICS NOISE CONTROL, MASON INDUSTRIES, INC., VIBRATION ELIMINATOR CO., INC., AND VIBRATION MOUNTING AND CONTROLS.

GENERAL REQUIREMENTS: SELECT VIBRATION ISOLATORS BY THE WEIGHT DISTRIBUTION TO PRODUCE UNIFORM DEFLECTION. VIBRATION ISOLATORS SHALL HAVE EITHER KNOWN UN-DEFLECTED HEIGHTS OR CALIBRATION MARKINGS SO THAT, AFTER ADJUSTMENT, THE STATIC DEFLECTION CAN BE VERIFIED, THUS DETERMINING THAT THE LOAD IS WITHIN THE PROPER RANGE OF THE ISOLATOR. ISOLATORS SHALL OPERATE IN THE LINEAR PORTION OF THEIR LOAD VERSUS DEFLECTION CURVES. SPRING ISOLATORS SHALL HAVE 50 PERCENT EXCESS CAPACITY WITHOUT BECOMING COIL BOUND. COAT VIBRATION ISOLATORS WITH FACTORY-APPLIED PAINT. INSTALL AND ADJUST VIBRATION ISOLATORS IN ACCORDANCE WITH MANUFACTURERS WRITTEN INSTRUCTIONS.

PIPE CONNECTIONS. PROVIDE FLEXIBLE CONNECTORS FOR PIPING SYSTEM CONNECTIONS ON EQUIPMENT SIDE OF SHUTOFF VALVES FOR VACUUM PUMPS AND AIR COMPRESSORS. FLEXIBLE PIPING CONNECTORS SHALL BE BRAIDED HOSE TYPE AS RECOMMENDED BY THE MANUFACTURER FOR THE APPLICATION.

PROVIDE TYPE MWP (METAL AND WAFFLE SANDWICH PADS) FOR EQUIPMENT MOUNTED ON EQUIPMENT PADS CONSISTING OF TWO 5/16 INCH THICK RIBBED OR WAFFLE NEOPRENE PADS SANDWICHING A 16 GAUGE STAINLESS STEEL SHIM PLATE WITH BRIDGE BEARING QUALITY NEOPRENE WITH A MAXIMUM DUROMETER OF 50 AND DESIGNED FOR 15% STRAIN. IF THE ISOLATOR IS BOLTED TO THE STRUCTURE, PROVIDE A NEOPRENE VIBRATION ISOLATION WASHER AND SLEEVE (UNIROYAL TYPE 620/660, OR AS APPROVED) INSTALLED UNDER THE BOLT HEAD BETWEEN THE STEEL WASHER AND THE BASE PLATE. PROVIDE MASON INDUSTRIES TYPE WSW OR EQUAL.

PROVIDE TYPE DDNM (DOUBLE DEFLECTION NEOPRENE MOUNTS) FOR PIPING SUSPENDED FROM THE STRUCTURE WITHIN 50 FEET OF ROTATING EQUIPMENT, CONSISTING OF DOUBLE DEFLECTING, MOLDED NEOPRENE ISOLATORS AND BE LATERALLY STABILIZED WITH ALL METAL SURFACES COVERED WITH NEOPRENE. TOP AND BOTTOM SURFACES SHALL BE RIBBED AND BOLT HOLES SHALL BE PROVIDED IN THE BASE. THE MOUNTS SHALL HAVE LEVELING BOLTS RIGIDLY SECURED TO THE EQUIPMENT. THE ISOLATOR SHALL BE MANUFACTURED WITH BRIDGE BEARING QUALITY NEOPRENE, AND SELECTED FOR A MAXIMUM DUROMETER OF 50 AND DESIGNED FOR 15% STRAIN. DDNM MOUNTS SHALL BE SELECTED FOR A STATIC DEFLECTION OF 3/8 INCH UNLESS OTHERWISE SPECIFIED. PROVIDE MASON INDUSTRIES TYPE ND OR AS EQUAL.

PROVIDE TYPE DDNH (DOUBLE DEFLECTION NEOPRENE HANGERS) FOR PIPING SUPPORTED ON THE FLOOR WITHIN 50 FEET OF ROTATING EQUIPMENT, CONSISTING OF A MOLDED NEOPRENE ISOLATING ELEMENT IN A STEEL HANGER BOX. A NEOPRENE SLEEVE SHALL BE PROVIDED WHERE THE LOWER HANGER ROD PASSES THROUGH THE STEEL HANGER BOX, SUCH THAT THE HANGER ROD CANNOT CONTACT THE STEEL HANGER. THE DIAMETER OF THE CLEAR HOLE IN THE HANGER BOX SHALL BE AT LEAST 3/4 INCH LARGER THAN THE DIAMETER OF THE HANGER ROD AND PERMIT THE HANGER ROD TO SWING THROUGH A 30 DEGREE ARC. WHEN INSTALLED, THE HANGER BOX SHALL BE ALLOWED TO ROTATE THROUGH A FULL 360 DEGREES WITHOUT ENCOUNTERING ANY OBSTRUCTIONS. THE ISOLATOR SHALL BE MANUFACTURED WITH BRIDGE BEARING QUALITY NEOPRENE, AND SELECTED FOR A MAXIMUM DUROMETER OF 50 AND DESIGNED FOR 15% STRAIN. UNLESS OTHERWISE SPECIFIED, THE STATIC DEFLECTION OF DDNH HANGERS SHALL BE 0.3 INCHES. PROVIDE MASON INDUSTRIES TYPE HD OR AS EQUAL.

15B PLUMBING PIPING

15B PIPING MATERIALS

MATERIALS SPECIFIED OR NOTED ON THE DRAWINGS ARE SUBJECT TO THE APPROVAL OF LOCAL CODE AUTHORITIES. VERIFY APPROVAL BEFORE INSTALLING ANY MATERIAL OR JOINING METHOD.

DOMESTIC WATER (COLD AND HOT): DOMESTIC WATER PIPING INSTALLED ABOVE THE FLOOR SLAB INSIDE THE BUILDING SHALL BE TYPE "L" HARD TEMPER COPPER TUBE WITH WROUGHT COPPER FITTINGS AND SOLDERED CONNECTIONS MADE UP WITH 95/5 SOLDER. BRAZED MECHANICALLY FORMED TEE CONNECTIONS (T-DRILL) MAY BE USED IN COPPER LINES WHERE APPROVED BY CODE; CONNECTION SHALL BE MADE WITH BRAZED SILVER SOLDER (SILFOS) JOINTS IN CONFORMANCE WITH MANUFACTURER'S INSTRUCTIONS.

UNDERGROUND DOMESTIC WATER PIPING 2" AND SMALLER SHALL BE TYPE "K" SOFT TEMPER COPPER TUBING WITH FLARED COPPER ALLOY FITTINGS AND CONNECTIONS, OR TYPE "K" HARD TEMPER COPPER TUBING WITH CONVENTIONAL WROUGHT COPPER FITTINGS AND SILVER SOLDER (SILFOS) JOINTS. INSTALL AS FEW UNDERGROUND COPPER PIPING JOINTS AS POSSIBLE. AT BUILDING SERVICE ENTRANCE, NO JOINTS SHALL BE INSTALLED UNDER OR WITHIN 5 FEET OF THE BUILDING. INSTALL DOMESTIC WATER PIPING BELOW GRADE OUTSIDE BUILDING AT ADEQUATE DEPTH TO PREVENT FREEZING.

INTERIOR WASTE AND VENT ABOVE SLAB: WASTE AND VENT PIPE ABOVE SLAB INSIDE BUILDING SHALL BE HUBLESS CAST IRON SOIL PIPE AND FITTINGS, MEETING ASTM A888 AND CISPI 301, MANUFACTURED BY AB & I FOUNDRY, CHARLOTTE OR TYLER PIPE AND BEARING THE TRADEMARK OF THE CISPI AND NSF. PVC SCHEDULE 40 DWV ASTM D2665 PIPE WITH PVC MEETING ASTM B1784, "SOLID WALL" CELL CLASS 12454-B WITH ASTM 2665 SOCKET FITTINGS WITH SOLVENT WELD JOINTS IS ALSO PERMITTED WHERE APPROVED BY CODE. (NOTE: PVC PIPING IS NOT ALLOWED IN CEILING RETURN AIR PLENUMS)

CONNECTIONS TO PLUMBING FIXTURES AND EQUIPMENT: 1-1/4" AND LARGER WASTE CONNECTIONS FROM FIXTURE TRAPS TO CAST IRON PIPE SHALL BE "DWV" COPPER WITH WROUGHT COPPER DRAINAGE PATTERN FITTINGS WITH COPPER SWEAT OR COMPRESSION JOINTS AT FIXTURE TRAP CONNECTIONS AND THREADED JOINTS AT CONNECTIONS TO CAST IRON PIPE.

15B PIPING AND EQUIPMENT INSULATION

DOMESTIC COLD WATER AND HOT WATER (WITHIN BUILDING) 1" ONE-PIECE FIBERGLASS COVERING WITH FIRE-RESISTANT JACKET WITH SELF-SEALING LAP TO PROVIDE A CONTINUOUS VAPOR BARRIER BY CERTAINTEED, OWENS-CORNING OR ARMSTRONG. FOR HOT PIPING, PROVIDE PIPE HANGERS AND RISER CLAMPS SIZED FOR THE OUTSIDE DIAMETER OF PIPING. BUTT INSULATION TO HANGER OR RISER CLAMP FOR VERTICAL PIPE. SEAL EXPOSED INSULATION WITH INSULATION SEALER. EXCEPTION FOR VERTICAL PIPING: PROVIDE CLAMPS SIZED FOR THE OUTSIDE DIAMETER OF THE VERTICAL PIPE AND EXTEND CLAMP THROUGH INSULATION. SEAL PENETRATIONS OF INSULATION AND VAPOR BARRIER WITH WET COAT OF VAPOR BARRIER LAP CEMENT. FOR COLD PIPING AT HANGERS PROVIDE 8" LONG SECTIONS OF HIGH DENSITY, HIGH TEMPERATURE CALCIUM SILICATE BY JOHNS-MANVILLE, FIBERGLASS BY KNAUF, OR 8" LONG STYROFOAM BILLETS BY DOW OR FLEXIBLE UNICELLULAR PIPING INSULATION MEETING ASTM C 534-01A, TYPE I WITH INTEGRAL HIGH DENSITY PIPE SUPPORTS AND ENCASED IN STEEL INSULATION SHIELD BY COOPER B-LINE / ARMACELL OR APPROVED EQUAL. INSULATION SHALL BE CONTINUOUS ALONG THE PIPE SURFACE, EXCEPT AT VALVES, UNIONS, AND WHERE PIPING IS EXPOSED AT FIXTURES. PROVIDE 1" FIBERGLASS INSULATION ON VENT PIPING WITHIN SIX FEET OF VENT THROUGH THE OF ROOF. PROVIDE FIBERGLASS INSULATION ON DOMESTIC COLD AND HOT WATER PIPES INSTALLED IN WALLS AND CHASES. PROVIDE FIBERGLASS INSULATION ON DOMESTIC COLD AND HOT WATER PIPES INSTALLED IN WALLS AND CHASES. PROVIDE INSULATION PROTECTION SHIELD AT EACH HANGER FOR INSULATED PIPING.

COVER FITTINGS WITH ZESTON, KNAUF, OR EQUAL ONE-PIECE PVC PREMOLDED INSULATING COVERS. FITTING COVERS, JACKETS AND ADHESIVES SHALL NOT EXCEED FLAME SPREAD RATING OF 25 AND SMOKE DEVELOPMENT RATING OF 50 PER ASTM E84. AT ALL ELBOWS AND TEES, FILL VOIDS BETWEEN COVERS AND PIPING WITH FIBERGLASS INSULATION AND TAPE JOINTS. INSTALL PIPE INSULATION IN COMPLIANCE WITH MANUFACTURER'S RECOMMENDATIONS. WHERE PREMOLDED INSULATING FITTINGS ARE NOT APPROVED BY LOCAL AUTHORITIES, MITER INSULATION AT FITTINGS.

INSULATE WATER HEATERS, STORAGE TANKS, HOT WATER PUMPS, ETC. THAT ARE NOT FACTORY INSULATED.

15B PIPING JOINTS

COPPER TUBING: JOINTS IN HARD TEMPER TUBING SHALL BE SOLDERED JOINTS USING LEAD-FREE 95/5 SOLDER EXCEPT WHERE TUBING IS INSTALLED BELOW GRADE OR BELOW THE BASE SLAB, IN WHICH CASE JOINTS SHALL BE SOLDERED WITH SILVER SOLDER (SILFOS). JOINTS IN SOFT TEMPER COPPER TUBING SHALL BE OF THE FLARED TYPE INSTALLED IN COMPLIANCE WITH THE FITTING MANUFACTURER'S RECOMMENDATIONS.

THREADED STEEL PIPE: THREADED JOINTS SHALL BE FULL AND CLEAN, CUT WITH NOT MORE THAN THREE (3) THREADS EXPOSED BEYOND THE FITTINGS. MAKE JOINTS TIGHT WITH GRAPHITE BASE PIPE JOINT COMPOUND AND PAINT EXPOSED THREADS OF FERROUS PIPE WITH ACID-RESISTING PAINT AFTER PIPING HAS BEEN TESTED AND PROVEN TIGHT. NO CAULKING, LAMP-WICK OR OTHER MATERIAL WILL BE PERMITTED FOR CORRECTION OF DEFECTIVE JOINTS.

WELDED STEEL PIPE: WELDED JOINTS SHALL BE OF THE BUTT WELDED SINGLE "VEE" TYPE. BEVEL PIPE AT A 45 DEGREE ANGLE TO WITHIN 1/16" OF THE INSIDE WALL, AND BUILD UP THE WELD TO ONE FOURTH GREATER DEPTH THAN THE PIPE WALL THICKNESS. WELDING SHALL BE EITHER ELECTRIC OR OXY-ACETYLENE, PERFORMED IN CONFORMANCE WITH THE ASME CODE FOR PRESSURE PIPE WELDING, AND ONLY BY EXPERIENCED CERTIFIED WELDERS.

CAST IRON PIPE BELOW GRADE: JOINTS IN BELL AND SPIGOT CAST IRON WASTE AND VENT PIPE SHALL BE NEOPRENE COMPRESSION GASKETS, TYSEAL OR EQUAL.

PIPE ADAPTERS: MAKE CONNECTION OF NEW WASTE PIPE TO NEW OR EXISTING DISSIMILAR WASTE PIPE USING ADAPTER COUPLINGS. PROVIDE FERNCO, PROFLEX 3000 SERIES OR MISSION FLEXSEAL MR56 SERIES WITH NEOPRENE ADAPTER GASKET WITH STAINLESS STEEL SHIELD AND HOSE CLAMPS FOR CONNECTING DISSIMILAR PIPES ABOVE GRADE. PROVIDE FERNCO, 1056 SERIES OR MISSION SEWER COUPLINGS WITH NEOPRENE ADAPTER GASKET AND HOSE CLAMPS FOR CONNECTING DISSIMILAR PIPES BELOW GRADE AND COAT STAINLESS STEEL BANDS WITH MASTIC.

15B PIPING INSTALLATION

GENERAL: CLEAN PIPE THOROUGHLY PRIOR TO INSTALLATION. REAM ENDS OF PIPE TO REMOVE BURRS. CUT PIPE ACCURATELY TO MEASUREMENTS TAKEN ON THE JOB. INSTALL WITH ADEQUATE CLEARANCE FOR INSTALLATION OF COVERINGS WHERE REQUIRED. PIPE SHALL NOT BE SPRUNG OR BENT. NEATLY ALIGN PIPE, CONNECT IT SECURELY, AND SUPPORT IT FROM THE BUILDING STRUCTURE WITH HANGERS AS SPECIFIED BELOW. PROVIDE CHROME-PLATED ESCUTCHEONS ON PIPES PASSING THROUGH CEILINGS, FLOORS OR WALLS OF FINISHED SPACES. RUN PIPES FREELY THROUGH FLOOR AND WALL PENETRATIONS USING PIPE SLEEVES. DO NOT GROUT IN PLACE UNLESS REQUIRED FOR STRUCTURAL FIRE INTEGRITY. INSTALL PIPE CONCEALED IN FINISHED SPACES WHEREVER POSSIBLE. USE A DIELECTRIC UNION WHERE FERROUS AND COPPER PIPE CONNECT. DIELECTRIC UNION SHALL HAVE A ZINC-PLATED STEEL BODY, A THREADED NYLON INSERT, AND INSULATING PRESSURE GASKET. NO FERROUS METAL-TO-COPPER CONNECTION MADE WITHOUT INSULATING UNIONS WILL BE ALLOWED.

HANGER & SUPPORTS: PIPE HANGERS SHALL BE AS DESCRIBED IN THE SPECIFICATIONS BY B-LINE OR EQUAL BY ANVIL, MICHIGAN, TRUSCON, OR UNISTRUT. CONNECT HANGERS TO THE STRUCTURE WITH SIDE BEAM CONNECTORS AND ALL THREAD HANGER RODS. PROVIDE ENGINEERED SUPPORT STRUTS BETWEEN JOISTS AND OTHER STRUCTURAL MEMBERS AS REQUIRED TO PROVIDE A RIGID HANGING INSTALLATION. DO NOT HANG PIPES FROM OTHER PIPES, CONDUIT OR DUCTWORK. PROVIDE HANGER RODS AND SPACE HANGERS AT INTERVALS AS SPECIFIED IN "HANGER SPACING". PROVIDE SUPPORT WITHIN 1' OF EACH ELBOW AND TEE. PROVIDE SUPPORTS WITHIN 1' OF EACH EQUIPMENT CONNECTION. PROVIDE TWO NUTS ON THREADED SUPPORTS TO SECURELY FASTEN THE SUPPORT. INSTALL HANGER TYPES OR SUPPORTS FOR VARIOUS PIPING AS FOLLOWS:

COPPER TUBE: ADJUSTABLE BAND HANGERS FOR BARE COPPER TUBE 3" AND SMALLER SHALL BE B-LINE #B3170 CT COPPER PLATED ADJUSTABLE BAND SWIVEL RING TYPE. ADJUSTABLE BAND HANGERS FOR INSULATED COPPER TUBE AND 3" SMALLER SHALL BE B-LINE #B3170 NF ADJUSTABLE BAND SWIVEL RING TYPE. CLEVIS HANGERS FOR INSULATED COPPER TUBE 4" AND LARGER SHALL BE B-LINE #B3100 GALVANIZED STEEL CLEVIS TYPE. SUPPORT EXPOSED COPPER TUBE 2" AND SMALLER TO WALLS OR IN CHASES WITH B-LINE #B3198RCT COPPER COATED EXTENSION SPLIT RING PIPE CLAMPS. 3/8" THREADED ROD AND B-LINE #B3199CT CEILING FLANGES. SUPPORT COPPER TUBE IN CHASES AND WALLS AT PLUMBING FIXTURES WITH PLASTIC OR COPPER BRACKETS SECURED TO STRUCTURE AND U-BOLTS SIZED TO BARE ON THE PIPE. RISER CLAMPS TO SUPPORT VERTICAL COPPER TUBE SHALL BE B-LINE #B3373CT COPPER COATED STEEL, CUT INSULATION, SEAL VAPOR BARRIER, AND ATTACH TO BARE TUBE.

STEEL PIPE: ADJUSTABLE BAND HANGERS FOR 2" AND SMALLER SHALL BE B-LINE #B3170 NF ADJUSTABLE BAND SWIVEL RING TYPE. CLEVIS HANGERS FOR 2-1/2" AND LARGER SHALL BE B-LINE #B3100 GALVANIZED STEEL CLEVIS TYPE. RISER CLAMPS TO SUPPORT VERTICAL PIPE SHALL BE B-LINE #B3373 GALVANIZED STEEL.

CAST IRON PIPE: ADJUSTABLE BAND HANGERS FOR 2" AND SMALLER. CLEVIS HANGERS FOR 3" AND LARGER SHALL BE B-LINE #B3100 GALVANIZED STEEL CLEVIS TYPE. RISER CLAMPS TO SUPPORT VERTICAL PIPE SHALL BE B-LINE #B3373 GALVANIZED STEEL.

INSULATION PROTECTION SHIELDS: B-LINE #B3151 OF 18 GAUGE GALVANIZED SHEET METAL. SHIELD SHALL COVER HALF OF THE CIRCUMFERENCE OF THE PIPE AND SHALL BE OF LENGTH INDICATED BY MANUFACTURER FOR PIPE SIZE AND THICKNESS OF INSULATION.

HANGER SPACING, ROD SIZES & CONNECTORS: CONNECT RODS TO STEEL BEAMS OR JOISTS WITH B-LINE #B3031 OR #B3033BEAM CLAMPS AS REQUIRED. CONNECT RODS TO CONCRETE WITH B-LINE #3014 MALLEABLE IRON SINGLE TYPE INSERTS WITH MALLEABLE IRON NUT. CONNECT RODS IN WOOD CONSTRUCTION WITH B-LINE #B3058 SIDE BEAM CONNECTORS. HANG AND SUPPORT PIPING WITH SPACING AND ROD SIZES AS FOLLOWS:

COPPER TUBE: 1-1/2" AND SMALLER - EVERY 6' WITH 3/8"HANGER RODS; 2" EVERY 10' WITH 3/8"HANGER RODS; 2-1/2" EVERY 10' WITH 3/8" HANGER RODS; 3" EVERY 10' WITH 1/2" RODS, 4" EVERY 10' WITH 5/8" HANGER RODS. SUPPORT VERTICAL COPPER TUBE EVERY 10'.

STEEL PIPE: 1" AND SMALLER - EVERY 8' WITH 3/8" HANGER RODS; 1-1/4" TO 2" EVERY 10' WITH 3/8" HANGER RODS; 2-1/2" AND 3" EVERY 10' WITH 1/2" HANGER RODS, 4" EVERY 10' WITH 5/8" HANGER RODS. SUPPORT VERTICAL STEEL PIPE EVERY 10'.

CAST IRON PIPE: EVERY 10' AND WITHIN 1' OF EACH JOINT. 2" AND SMALLER WITH 3/8" HANGER RODS; 3" WITH 1/2" HANGER RODS; 4" WITH 5/8" HANGER RODS; 6" WITH 3/4" HANGER RODS; 8" AND LARGER WITH 7/8" HANGER RODS. SUPPORT VERTICAL CAST IRON PIPE EVERY 15'.

PLUMBING VENT: CONNECT PLUMBING VENT PIPES TO FIXTURE DRAIN PIPES AS INDICATED ON THE DRAWINGS OR AS REQUIRED BY THE INSTALLATION PRACTICES ADOPTED AND ENFORCED BY LOCAL CODES OFFICIAL, AND EXTEND VENT PIPES FULL SIZE THROUGH THE ROOF LINE. GRADE PIPE TO A UNIFORM SLOPE SO AS TO DRAIN BACK BY GRAVITY TO THE DRAINAGE PIPING SYSTEM. VENTS PASSING THROUGH THE ROOF SHALL BE MINIMUM 3" SIZE EXCEPT IN TROPICAL CLIMATES, PER LOCAL CODES. TURN FLASHING DOWN INTO STACKS AT LEAST 2", AND EXTEND FLASHING 24" IN ALL DIRECTIONS FROM THE PIPE AT THE ROOF LINE. APPLY WHITE LEAD PIPE DOPE ON MALE STEEL PIPE THREADS. VENT LINES SHALL BE AIR AND WATER TIGHT. VENT FLOOR DRAINS INDIVIDUALLY OR CONNECT THEM TO A HORIZONTALLY VENTED LINE AS SHOWN ON THE DRAWINGS.

15B PIPING SANITIZATION

SANITIZE THE DOMESTIC WATER PIPING SYSTEM WITHIN SCOPE OF WORK (COLD, AND HOT) WITH A SOLUTION CONTAINING NOT LESS THAN 50 PPM AVAILABLE CHLORINE. KEEP SOLUTION IN THE SYSTEM FOR A MINIMUM OF 24 HOURS, WITH EACH VALVE BEING OPERATED SEVERAL TIMES DURING THE PERIOD. AFTER COMPLETION, FLUSH SYSTEM WITH CITY WATER UNTIL CHLORINE RESIDUAL IS LOWERED TO INCOMING CITY WATER LEVEL.

15B PIPE AND VALVE MARKERS

PROVIDE MANUFACTURER'S STANDARD PRE-PRINTED, SEMI-RIGID SNAP-ON OR PERMANENT ADHESIVE, PRESSURE-SENSITIVE VINYL PIPE MARKERS. PIPE MARKERS SHALL BE COLOR-CODED COMPLYING WITH ANSI A13.1.

INSTALL PIPE MARKERS ON EACH PLUMBING PIPING SYSTEM AND INCLUDE ARROWS TO SHOW NORMAL DIRECTION OF FLOW.

LOCATE PIPE MARKERS AND COLOR BANDS WHEREVER PIPING IS EXPOSED TO VIEW IN OCCUPIED SPACES, MACHINE ROOMS, ACCESSIBLE MAINTENANCE SPACES (SHAFTS, TUNNELS, PLENUMS) AND EXTERIOR NON-CONCEALED LOCATIONS.

PROVIDE PLASTIC LAMINATE OR BRASS VALVE TAG ON EVERY VALVE, COCK AND CONTROL DEVICE IN EACH PLUMBING PIPING SYSTEM; EXCLUDE CHECK VALVES, VALVES WITHIN FACTORY-FABRICATED EQUIPMENT UNITS, PLUMBING FIXTURE FAUCETS, CONVENIENCE AND LAWN-WATERING HOSE BIBBS, AND SHUT-OFF VALVES AT PLUMBING FIXTURES AND SIMILAR ROUGH-IN CONNECTIONS OF END-USE FIXTURES AND UNITS.

15B PLUMBING SPECIALTIES

15B CLEANOUTS

CLEANOUTS SHALL BE BY ONE MANUFACTURER IF POSSIBLE. ACCEPTABLE MANUFACTURERS ARE JOSAM, SIOUX CHIEF, SMITH, WADE, WATTS, AND ZURN. PROVIDE LONG SWEEP FITTINGS FOR CLEANOUT EXTENSIONS; SHORT SWEEPS AT START OF RUNS OR CHANGE IN DIRECTION AND COMBINATION WYE AND EIGHT BEND FITTINGS IN HORIZONTAL RUNS. INSTALL CLEANOUTS WITH A MINIMUM OF 18" CLEAR ALL AROUND, CONSULT LOCAL CODES FOR OTHER REQUIREMENTS, FOR EASY SYSTEM MAINTENANCE. INSTALL PLUG WITH TEFLON JOINT COMPOUND.

FLOOR CLEANOUTS: SHALL BE AS SCHEDULED ON THE DRAWINGS. INSTALL CLEANOUTS AT POINTS AS NOTED ON THE DRAWINGS, AT THE BUILDING EXIT; AT A MINIMUM OF EVERY 50 FEET IN HORIZONTAL SOIL AND WASTE LINES; AND AT TURNS OF PIPE GREATER THAN 45 DEGREES CLEANOUTS SHALL BE FULL SIZE OF THE PIPE UP TO 4", AND 4" SIZE FOR PIPES LARGER THAN 4". DETERMINE THE TYPE OF FLOOR COVERING TO BE USED AT EACH FLOOR CLEANOUT LOCATION AND PROVIDE TOP WITH VARIATIONS SUITABLE FOR FLOOR COVERING (CARPET MARKERS, RECESSED FOR TILE AND SCORIATED FOR UNFINISHED FLOOR). ROUGH-IN AND INSTALL EACH FLOOR CLEANOUT FLUSH WITH THE FINISHED FLOOR CONSTRUCTION.

15B PLUMBING FIXTURES AND EQUIPMENT

15B PLUMBING FIXTURES

FURNISH AND INSTALL COMMERCIAL GRADE PLUMBING FIXTURES, SEE THE DRAWINGS FOR QUANTITIES AND DESCRIPTIONS. PROVIDE CHINA FIXTURES AS SCHEDULED BY AMERICAN-STANDARD OR APPROVED EQUAL BY CRANE, GERBER, KOHLER, SLOAN VALVE CO, TOTO-KIKI OR ZURN. PROVIDE STAINLESS STEEL SINKS AS SCHEDULED BY ELKAY OR EQUAL BY JUST. PROVIDE ELECTRIC WATER COOLERS AS SCHEDULED BY ELKAY OR APPROVED EQUAL BY ACORN / AQUA, HALSEY TAYLOR OR HAWS. PROVIDE MOP SINKS AS SCHEDULED BY STERN-WILLIAMS OR EQUAL BY ACORN ENGINEERING CO., FIAT OR FLORESTONE. PROVIDE EMERGENCY EQUIPMENT AS SCHEDULED BY BRADLEY OR EQUAL BY CHICAGO, ENCON, GUARDIAN, HAWS OR SPEAKMAN. PROVIDE FIXTURES OF SAME MANUFACTURER WHERE POSSIBLE.

FIXTURES SHOWN ON THE DRAWINGS OR SPECIFIED HEREIN SHALL BE FURNISHED AND INSTALLED, SET FIRM AND TRUE, CONNECTED TO REQUIRED PIPING SERVICES, THOROUGHLY CLEANED, LEFT CLEAN AND READY FOR USE. EXPOSED FITTINGS AND PIPING AT THE FIXTURES SHALL BE CHROME-PLATED, AND WATER SUPPLY PIPING SHALL BE VALVED AT EACH FIXTURE.

VITREOUS CHINA FIXTURES SHALL BE OF THE BEST GRADE VITREOUS WARE, WITHOUT PIT HOLES OR BLEMISHES, AND THE OUTLINES SHALL BE GENERALLY TRUE. THE ENGINEER RESERVES THE RIGHT TO REJECT ANY PIECES WHICH, IN HIS OPINION, ARE FAULTY. FIXTURES SET AGAINST WALLS SHALL HAVE GROUND BACKS AND SHALL BE CAULKED WITH SILICONE SEALANT OF A MATCHING COLOR.

15B WATER HEATER

SPECIFIER: USE THIS PARAGRAPH FOR ELECTRICAL STORAGE TYPE WITH TANKS 119 GALLONS AND SMALLER. WATER HEATER SHALL BE BY A.O.SMITH, BRADFORD-WHITE, LOCHINVAR, STATE, RHEEM OR RUUD WITH CAPACITY AS SCHEDULED ON THE DRAWINGS. UNIT SHALL BE ELECTRIC GLASSLINED TANK TYPE COMPLETE WITH STEEL JACKET, FIBERGLASS INSULATION, MAGNESIUM ANODE, INTEGRAL THERMOSTATS AND CONTROLS, AND TEMPERATURE & PRESSURE RELIEF VALVE. WATER HEATER SHALL BE UL LISTED AND MEET ASHRAE 90.1B STANDARDS FOR THERMAL EFFICIENCY AND STANDBY HEAT LOSS.

RELIEF VALVE: WATER HEATER RELIEF VALVE SHALL BE OF THE TEST LEVER TYPE, WITH AUTOMATIC RESET, COMBINATION TEMPERATURE AND PRESSURE RELIEF, APPROVED AND STAMPED BY THE AMERICAN GAS ASSOCIATION. IT SHALL BE INSTALLED DIRECTLY ON THE HEATER TANK, OR IN THE HOT WATER OUTLET, NOT MORE THAN 3" FROM THE TANK. THE TEMPERATURE SHALL BE NORMALLY SET TO RELIEVE AT 210'F AND THE PRESSURE RELIEF SHALL BE AT 125 PSI. THE RELIEF VALVE DISCHARGE LINE SHALL BE PIPED DOWN AND TERMINATE 6" ABOVE A FLOOR DRAIN.

15B TRAP SEAL

PROVIDE TRAP SEAL PER SPECIFICATIONS FOR ACTUAL FLOOR DRAIN MODEL AND SIZE.

TRAP SEALS SHALL BE BY PROSET SYSTEMS OR EQUAL BY SURE SEAL SYSTEMS OR MIFAB OF MOLDED PVC ELASTOMER THAT ALLOWS THE FLOW OF WASTE WATER AND CLOSES UPON TERMINATION OF FLOW. INSTALL PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. DO NOT TOUCH ELASTOMERIC PLUG OR ALLOW CONTACT WITH PRIMER OR SOLVENT CEMENT. OR, SHALL BE BY SURE SEAL, INC. OF SMOOTH, SOFT, FLEXIBLE, ELASTOMERIC PVC MATERIAL WITH A FLAPPER CLOSURE. THE FLOW OF WASTEWATER ALLOWS FLAPPER TO OPEN AND ADEQUATELY DISCHARGE TO FLOOR DRAIN THROUGH ITS INTERIOR. THE FLAPPER CLOSES AND RETURNS TO ORIGINAL MOLDED SHAPE AFTER WASTEWATER DISCHARGE IS COMPLETE.

SECTION 16A GENERAL ELECTRICAL REQUIREMENTS:

16A GENERAL INSTRUCTIONS

16A GENERAL REQUIREMENTS

ALL REQUIREMENTS UNDER DIVISION 1 AND THE GENERAL AND SUPPLEMENTARY CONDITIONS OF THESE SPECIFICATIONS APPLY TO THIS SECTION AND DIVISION. WHERE THE REQUIREMENTS OF THIS SECTION AND DIVISION EXCEED THOSE OF DIVISION 1, THIS SECTION AND DIVISION TAKE PRECEDENCE. BECOME THOROUGHLY FAMILIAR WITH ALL THEIR CONTENTS AS TO REQUIREMENTS THAT AFFECT THIS DIVISION, SECTION OR BOTH. WORK REQUIRED UNDER THIS DIVISION INCLUDES ALL MATERIAL, EQUIPMENT, APPLIANCES, AND LABOR REQUIRED TO COMPLETE THE ENTIRE ELECTRICAL SYSTEM AS REQUIRED BY THE DRAWINGS AND SPECIFICATIONS, OR REASONABLY INFERRED TO BE NECESSARY TO FACILITATE EACH SYSTEM'S FUNCTIONING AS IMPLIED BY THE DESIGN AND THE EQUIPMENT SPECIFIED.

THE SPECIFICATIONS AND DRAWINGS FOR THE PROJECT ARE COMPLEMENTARY, AND PORTIONS OF THE WORK DESCRIBED IN ONE, SHALL BE PROVIDED AS IF DESCRIBED IN BOTH. IN THE EVENT OF DISCREPANCIES, NOTIFY THE ENGINEER AND REQUEST CLARIFICATION PRIOR TO PROCEEDING WITH THE WORK INVOLVED.

DRAWINGS ARE GRAPHIC REPRESENTATIONS OF THE WORK UPON WHICH THE CONTRACT IS BASED. THEY SHOW THE MATERIALS AND THEIR RELATIONSHIP TO ONE ANOTHER, INCLUDING SIZES, SHAPES, LOCATIONS, AND CONNECTIONS. THEY ALSO CONVEY THE SCOPE OF WORK, INDICATING THE INTENDED GENERAL ARRANGEMENT OF THE EQUIPMENT, FIXTURES, OUTLETS AND CIRCUITS WITHOUT SHOWING ALL OF THE EXACT DETAILS AS TO ELEVATIONS, OFFSETS, CONTROL LINES, AND OTHER INSTALLATION REQUIREMENTS. USE THE DRAWINGS AS A GUIDE WHEN LAYING OUT THE WORK AND TO VERIFY THAT MATERIALS AND EQUIPMENT WILL FIT INTO THE DESIGNATED SPACES, AND WHICH, WHEN INSTALLED PER MANUFACTURERS' REQUIREMENTS, WILL ENSURE A COMPLETE, COORDINATED, SATISFACTORY AND PROPERLY OPERATING SYSTEM.

DRAWINGS ARE SCHEMATIC IN NATURE, SHOW THE VARIOUS COMPONENTS OF THE SYSTEMS APPROXIMATELY TO SCALE AND ATTEMPT TO INDICATE HOW THEY SHALL BE INTEGRATED WITH OTHER PARTS OF THE WORK. FIGURED DIMENSIONS TAKE PRECEDENCE TO SCALED DIMENSIONS. DETERMINE EXACT LOCATIONS BY JOB MEASUREMENTS, BY CHECKING