

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			BPA NO.		1. CONTRACT ID CODE		PAGE 1		OF PAGES 12		
2. AMENDMENT/MODIFICATION NO. A00005			3. EFFECTIVE DATE 03-17-2016		4. REQUISITION/PURCHASE REQ. NO. 675-16-1-3418-0001			5. PROJECT NO.(If applicable) 675-16-604			
6. ISSUED BY Department of Veterans Affairs Orlando VA Medical Center 13800 Veterans Way Orlando FL 32827			CODE 675		7. ADMINISTERED BY (If other than Item 6) Department of Veterans Affairs Network Contracting Activity 8 (NCO 8) Orlando VA Medical Center 13800 Veterans Way Orlando FL 32827			CODE 00675			
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code) To all Offerors/Bidders					(X)		9A. AMENDMENT OF SOLICITATION NO. VA248-15-R-2123				
					X		9B. DATED (SEE ITEM 11)				
							10A. MODIFICATION OF CONTRACT/ORDER NO.				
							10B. DATED (SEE ITEM 13)				
CODE					FACILITY CODE						
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS											
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.											
12. ACCOUNTING AND APPROPRIATION DATA (If required)											
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.											
CHECK ONE A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.											
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).											
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:											
D. OTHER (Specify type of modification and authority)											
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.											
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is to provide an updated RFI Tracking Log that contains RFIs 1 - 65 and corresponding responses. The RFI submission period is closed.											
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.											
15A. NAME AND TITLE OF SIGNER (Type or print)					16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)						
15B. CONTRACTOR/OFFEROR (Signature of person authorized to sign)					15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY (Signature of Contracting Officer)			16C. DATE SIGNED	

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

RFI NBR	Question Response	Submitted By	Dated Received
1.	Please provide record drawings for the above project which clearly delineates the amount of stairwells, location of stairwells, and size of landings in the SOW.	Midwestern Construction Services	02/22/16
Response	Drawings that are available are provided in amendments to solicitation VA248-15-R-2123. These drawings are in PDF format and sizes would need to be site verified.		
2.	Please provide record drawings for buildings 504 and 519a Roofs and the interior so that all site conditions may be verified, if possible, prior to the site visit. In the event these cannot be produced prior to the site visit, we would like to request a second site visit once information is available.	Midwestern Construction Services	02/22/16
Response	Drawings that are available are provided are provided in amendments to solicitation VA248-15-R-2123. All site conditions would need to be verified during the site visit and not depend on as-built drawings. Drawings are for informational use only and not to be considered exact.		
3	Please provide exterior elevations for building 500, if possible, prior to the site visit to allow for proper field verifications. In the event these cannot be produced prior to the site visit, we would like to request a second site visit once information is available	Midwestern Construction Services	02/22/16
Response	Drawings that are available are provided are provided in amendments to solicitation VA248-15-R-2123. All field conditions are to be verified during a site visit and not depend on what is shown in the drawings.		
4	Please clarify if this project is a bid-build or if it is a design-build. It appears that the SOW has provided a clear basis of design, however, upon review of the solicitation, we were unable to find the edited design specifications and drawings for each task described under the solicitation. Is it the intent of the VA for the contractor to go to the Technical Information Library (TIL) for each task, edit the generic specifications and produce these design documents based on our individual bid strategy or will the VA be producing these documents?	Midwestern Construction Services	02/22/16
Response	This is not a Design-Build project. There will not be a design required. The contractor will be required to edit the specs from the TIL and develop submittal packages for the items in the SOW. The contractor shall provide Redline drawings for the roofing portion of the project.		
5	For the Past Performance Questionnaire, can forms filled out prior to this solicitation by contracting officers be utilized as long as they are still valid?	Midwestern Construction Services	02/22/16
Response	Yes; Past Performance Questionnaires form filled out by contracting Officers prior to this solicitation may be submitted. However the questionnaires shall meet the criteria specified in		

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	this solicitation.		
6	Under the scope of work, Item B, Line c. the VA is asking for new 12" X 12" Luxury Vinyl Tile and requiring the Tile to fit in the VA Planetree design philosophy. What types (examples) of 12" X 12" vinyl floor tile does the VA considers to be Luxury Vinyl Tile? Also, please clarify what the VA Planetree design philosophy is.?	Midwestern Construction Services	02/22/16
Response	A luxury vinyl tile example could be found with major flooring brands such as Armstrong where the LVT typically has a higher level of performance and a vast array of color selections. Planetree design is based off of aesthetics and color selection which will be chosen by the Orlando VA interior design.		
7	The above referenced solicitation was released on 2/19/16, however, there were no plans or specifications attached. Will these come out in an Amendment?	Biosphere	02/22/16
Response	Yes. See drawings in Amendment A0002		
8	What is the deadline to submit RFIs for this project?	MULE Engineering & Construction	02/22/16
Response	We have not established a deadline to submit RFIs yet. When a RFI deadline is established, it will be communicated via an amendment to the solicitation. For a timely and proper response, Offerors should submit RFIs as soon as possible so we can research the issue.		
9	Can you please confirm that no hand delivered bids will be accepted? All bids must be mailed or FedEx or similar service and must thereby effectively be mailed out on the Friday before.	Moran Construction	02/24/16
Response	<u>TO ALL OFFEREORS: HAND DELIEVERED, FAXED OR EMAILED PROPOSALS WILL NOT BE ACCEPTED</u>		
10	1. This RFP is to be mailed only (not hand delivered), and we were told at the site visit that is the policy going forward. Will this be the standard procedure for all RFP's coming out of the Orlando VA office going forward? Or is this policy specific to this contracting officer?	MULE Engineering & Construction	03/01/16
Response	The process of not accepting hand delivered, faxed or emails proposals from offerors are specific to solicitation VA248-15-R-2123. A solicitation specifies the designated location for receipt of proposals.		
11	2. For the stairwell work in building 500, please provided specs for all vinyl tile, cove base, treads, door thresholds and any other materials that are to be replaced.	MULE Engineering & Construction	03/01/16
Response	Products must comply with the Buy American Act. Style, color and specs are to be equivalent to, or better than, the following examples.		

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	<p>Rubber Stair Treads (Black): http://www.surefootcorp.com/files/4613/7226/7087/Modern_Rubber_Tread_tech_data.pdf Tile (0024 Barma Pure): http://www.gerflorusa.com/media/17-usa-website/7-technical-doc/saga-2-technical-datasheet.pdf Cove Base: Base - Roppe Visuelle Rubber Cove Base, Size: 7-3/4" H,Color: Sahara (631).</p>		
12	3. For the stairwell work in building 500, are existing thresholds to be replaced?	MULE Engineering & Construction	03/01/16
Response	Yes, replace to match existing thresholds.		
13	4. For the stairwell work in building 500, are the first floor entryway/landing areas to be retiled? This question applies to all three stairwells	MULE Engineering & Construction	03/01/16
Response	If flooring is not damaged contractor will only be responsible to replace the first floor entryway/landing stairwell by the back loading dock.		
14	5. Please provide specs for the exterior coating(s) to be used for the pressure washing and painting portion of the SOW.	MULE Engineering & Construction	03/01/16
Response	Sherwin Williams Super Paint: exterior, acrylic, latex satin or equal		
15	6. Please provide specs or preferences for the type and method of pressure washing.	MULE Engineering & Construction	03/01/16
Response	Pressure washing shall be at a minimum of 2800 psi, 2.8 gpm, and at a temperature of 100 degrees F.		
16	7. Please provide specs for all roofing materials and re-roofing methods for buildings 504 and 519a.	MULE Engineering & Construction	03/01/16
Response	Materials are to meet the Buy American Act and are to be determined by contractor and shall be approved by the VA during submittal the phase. Basis of design shall be modified bituminous torch grade roof system.		
17	8. What thickness, or minimum thickness, of insulation is required for re-roofing?	MULE Engineering & Construction	03/01/16
Response	For building 504 a minimum insulation value of R-20, not to be achieved through any roof coatings.		

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

18	9. What type of deck materials currently existing for Building 519a?	MULE Engineering & Construction	03/01/16
Response	Metal Deck		
19	10. Confirm that a UL lightning protection certificate is required at the finish of each re-roofing.	MULE Engineering & Construction	03/01/16
Response	Yes, UL lightning protection certificate is required upon completion of work		
20	11. Please specify materials/procedures to be used to protect the fresh air supply during re-roofing.	MULE Engineering & Construction	03/01/16
Response	Contractor shall choose procedure and materials to prevent contamination of fresh air supply. Work and fumes cannot impact or disturb patient care during operational hours.		
21	12. Clarify if coping and flashing is to be new or reused.	MULE Engineering & Construction	03/01/16
Response	Clean and reuse existing coping and flashing. Contractor to replace any coping or flashing damaged by construction with new		
	13. Please provide a cross-section/cut-out drawing of the stairwells showing elevations.	MULE Engineering & Construction	03/02/16
Response	Yes. See amendment A00003		
22.	Thank you for meeting with us on Friday regarding the above referenced project. Being that time ran short; USA Tampa would like know when it would be possible to gain access to Building 500 in order to get a stair count & square footage of the landing?	USA Tampa	02/29/16
Response	On 02/26/2016, the site visit lasted from 2:00 PM -3: 45 PM. During that time Government representatives escorted vendors to Building 500 to view the stairwells. More than ample time was given to all vendors that wanted to see the stairwell during the site visit. The sign in sheet reflects a representative from USA Tampa attended the site visit.		
23	The Volume I Technical Proposal Evaluation Factors provided on Pages 10-11 in the solicitation doesn't match the Volume I Technical Proposal Format provided on Pages 13-14. There's several tabs listed under the Proposal Format that aren't provided under the Evaluation Factors. Can you please provide	Harper Consulting, LLC <i>Marketing Consultant</i>	03/02/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	clarification on the Proposal Format?	<i>for BES Design/Built, LLC</i>	
Response	An amendment to the solicitation will be posted to FBO that will provide clarification to what is required in the proposal format.		
24	1. What thickness or R-value should there be for the reroof insulation?	Nichols Services Inc.	03/02/16
Response	See response to question 17.		
25	2. Will we be able to shutdown the roof mounted air ventilation systems temporarily during the roofing process? Or will we need use a filter system for those ventilation systems?	Nichols Services Inc.	03/02/16
Response	Not during normal working hours, also see response to question 20.		
26	3. What are the specifications for the paint being used on building 500 exterior wall?	Nichols Services Inc.	03/02/16
Response	See response to RFI #14		
27	4. Is there any elevation plans with specifications and details on the stairways?	Nichols Services Inc.	03/02/16
Response	Yes. See amendment A00003		
28	1. Can we get a floor plan of each floor for all 4 stairways?	Valor Construction	03/02/16
Response	Yes. See amendment A00003		
29	2. Can we get a cut section plans of each stairway showing 1 st floor to top of stairway including interstitial floors?	.	03/02/16
Response	Yes. See amendment A00003		
30	3. Please spec what type of rubber floor treads will be excepted for this project. including color, thickness & type of tread surface	Valor Construction	03/02/16
Response	See response to question 11		
31	4. Will a stairway be able to be closed from Friday end of 1 st work shift through the weekend and ready to open on Monday 6am	Valor Construction	03/02/16
Response	Yes, but only one at a time.		
32	5. Are the stair risers to be repainted in this project?	Valor Construction	03/02/16
Response	Only if paint damaged by the construction process.		
31	6. Will we be able to work regular working hours on the roof the Building 504 & Building 519a?	Valor Construction	03/02/16
Response	As long as noise and vibration does not interfere with patient care.		
32	7. Will HVAC intake fans need to be filtered during roof	Valor	03/02/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	construction?	Construction	
	See response to question 20.		
33	8. Will there be a 2 nd site visit to access the Building 519a roof?	Valor Construction	03/02/16
Response	Yes: Wednesday March 9th, 2016 Time 1:00pm.		
34	9. Will there be a spec issued on the roofing materials to be used on this project?	Valor Construction	03/02/16
Response	No, see responses to questions 16 and 17		
35	10. Will there be a roof deck structural plan issued for both roofs?	Valor Construction	03/02/16
Response	All roof plan drawings available have been released in previous amendments		
36	1. During roofing operations, will the contractor be responsible for mitigating fumes/ odors through means such as carbon filters on intakes	Midwestern Construction Services	03/03/16
Response	Yes. See response to question 20.		
37	2. During site visit it was indicated that the stair treads and floor tile in the Stairwells were to match existing size with the exception that the flooring be Luxury Vinyl Tile per the Planetree Design. There are no 12" X 12" LVT available. Does the VA want us to utilize 16" X 16" or 18" X 18" LVT or should we price standard 12" X 12" VCT for the Stairwell Landings	Midwestern Construction Services	03/03/16
Response	Utilize LVT, up to 20"x20"		
38	3. Is there any ACM in the stairwells?	Midwestern Construction Services	03/03/16
Response	Not to the Government's knowledge.		
39	Please identify where the contractor laydown/dumpster area will be located for Bldg. 519A.	The Cherokee 8A Group	3/8/2016
	The Laydown/Dumpster Area will be identified after award.		
40.	1. Building 519 has 1/8" tapered insulation with 1/4" crickets on there now. Can the new insulation be 1/4" tapered with 1/2" crickets	J.A.M. Construction	03/09/16
Response	YES.		
41.	2. Is a 1/4" or 1/8" tapered insulation system required for this roof area?	J.A.M. Construction	03/09/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

Response	YES a tapered system is required.		
42.	<p>1. The relationship between one of the Technical Proposal Tabs that has been included within Amendment A00003's revised Technical Proposal Format List & the Evaluation Factors included within the original "Instructions, Conditions and Other Statements to Bidders/Offerors" Document still remain unclear. Can the Evaluation Factors relating to the following Tabs be clarified: Please See Below.</p> <p>1 "Tab D: Experience – (5 pages maximum)" 2 "Tab E: Past Performance – (Project descriptions narrative, photos, etc.)"</p>	Midwestern Construction Service	03/10/16
Response	<p>Experience refers to whether the firm has done similar work before. Past Performance describes how well they have done that work.</p>		
43.	1. Are there engineered design pressure requirements for the project, and if not can we request them?	ESA South	03/10/16
Response	It will be the responsibility of the selected contractor to provide this.		
44.	2. Scope requires compliance w/ High Velocity Hurricane Zone, is there a wind speed requirement? If so, will a wind speed warranty rider be required?	ESA South	03/10/16
Response	This will be the responsibility of the ROOFING contractor to have the adequate knowledge in local Florida codes along with the ability to install the modified bituminous roof system according to manufacturer's requirements.		
45.	3. Is there a MIN. or AVG. R-value requirement for the project, or are we to figure new insulation to match existing insulation heights?	ESA South	03/10/16
Response	See response to question 17		
46.	<p>4. Will this be a LEEDs project?</p> <p>a. Will a Leeds Cap Sheet be required to meet the Heat Island Effect Point?</p> <p>b. Will FSC lumber be required for sustainability points?</p> <p>c. Will local or regional materials be required? If so, LEEDs points will not be able to come from our roofing scope, thus excluded.</p>	ESA South	03/10/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

Response	No.		
47	5. Will there be an independent roofing consultant required on the project?	ESA South	03/10/16
Response	No		
48.	6. Will there be an independent 3 rd party safety professional required.	ESA South	03/10/16
Response	No.		
49.	7. Is the Buy American Act a requirement for all material, including fasteners?	ESA South	03/10/16
Response	Yes		
50.	8. What are the costs associated if any with Badging Employee's?	ESA South	03/10/16
Response	None, unless the provided badges are lost		
51.	9. Sheet Metal Flashing --- Will shop fabricated flashings be accepted on the project with job specific engineering or do all flashings need to meet a RoofNav / FM or NOA assembly? If so what criteria is required?	ESA South	03/10/16
Response	Shop fabricated flashings will be accepted.		
52.	10. Will any interior protection be required?	ESA South	03/10/16
Response	All existing facilities and government property is to be protected during construction		
53.	11. Does any of the existing assemblies contain or likely contain asbestos?.	ESA South	
Response	Not to our knowledge		
54.	12. Is the roofing contractor required to carry any allowances or unit cost for replacement in our base bid costs?	ESA South	03/10/16
Response	This is a Firm Fixed Price Contract Type. This is for the contractor to decide and account for all cost.		
55.	14. Will the contractor need a VA escort to access the Mental Health Dormitory area to conduct roof replacement at Building 519a? If so, will there be any restrictions on days and times an escort would be available?	MULE Engineering & Construction	03/10/16
Response	Access will be coordinated with the COR, but escorts will not be required.		
56.	15. Is the grassy/dirt area outside of the north east corner of the Mental Health Dormitories available for dumpsters and laydown?	MULE Engineering & Construction	03/10/16
Response	The Laydown/Dumpster Area will be identified after award		

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

57.	1.Regarding RFI Tracking Log - RFI #1-38 dated 3/4/16, Item #13 and response, as the site visits were not mandatory and we were not able to attend, are the contractors to figure new flooring on all landings for stairs #1, 2 & 3 or just for the landing on stair #1 referenced in the response?	BES Design Build	03/10/16
Response	All landings		
58.	1. The VA stated previously that this was not a Design / Build project; therefore, can you provide the following: a) Roof Plan (to scale) b) Roof details c) Roof specifications	Biosphere International, Inc	03/10/16
Response	All of the Drawings in our possession were posted in the solicitation and amendments to the solicitation.		
59.	2. The current code requires calculations for anticipated wind loads and resulting wind pressures in the design of a roof system (see attached). These calculations establish the uplift resistance requirements for attaching the roof system to the existing structural roof deck (number of fasteners, spacing, etc.); and this will impact the cost of the roof work. Can the VA provided this information?	Biosphere International, Inc	03/10/16
Response	This will be the responsibility of the ROOFING contractor to have the adequate knowledge in local Florida codes along with the ability to install the modified bituminous roof system according to manufacturer's requirements.		
60.	3. Amendment 3 includes eight 8 ½"x11" pdf of drawings, these pdf's are not to scale and cannot be printed to scale on full-sized VA drawings (30 x 42). Can you provide original sized pdf of the drawings?	Biosphere International, Inc	03/10/16
Response	No		
61.	The example below shows the calculations required for a recent roofing project that we bid at a VA. It illustrates the design information that affects the selection of a roof system and details. This information is not found it the TIL. The VA needs to provide this if this is not a Design / Build project. Design Criteria 1. Building Code: This project will be constructed under the 2014 Florida Building Codes (Fifth Edition). 2. Design Wind Loads: The component and cladding wind load pressures were calculated in accordance with ASCE 7-10 for low sloped roofs. a. The wind loads were determined based in the following criteria: (1) Roof slope ≤ 7 degrees and height ≤ 60-ft.	Biosphere International, Inc	03/10/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	(2) Building Enclosure: Partially Enclosed; (3) Basic Wind Speed: 155 mph; (4) Risk Category: Category III-IV; (5) Exposure Category: D. b. The Design Wind Load pressures are: (1) Zone 1 (field): -51.7 psf (2) Zone 2 (perimeters): -78.4 psf (enhanced wind zone) (3) Zone 3 (corners): -111.7 psf (enhanced wind zone)		
Response	This will be the responsibility of the ROOFING contractor to have the adequate knowledge in local Florida codes along with the ability to install the modified bituminous roof system according to manufacturer's requirements.		
62.	<p>Related to the listing of required proposal Tabs versus the corresponding Evaluation Factors. For Technical Proposal Content: Tab D Experience - (5 pages maximum) Tab E Past Performance - (Project description narratives, photos, etc)</p> <p>The only Evaluation Factor which addresses these two tabs is: Evaluation Factor 3: Experience - all of the explanation for this Factor involves the reporting of past projects, as listed in Tab E - but there is nothing else to explain what you would want included under Tab D</p> <p>So our RFI is:What information do you want included under Tab D – Experience of the Technical Proposal Content?</p> <p>Just to clarify, then what goes in Tab E - Past Projects?</p>	MULE Engineering & Construction	
Response	<p>The Offeror should insert into their Technical Proposal at Tab D "Experience", the response to Paragraph D of VA248-15-R-2123 Pages 10 and 11 of 106. Offerors should include in Tab D all information that is related to "Experience", to include project descriptions narrative, photos, etc..</p> <p>Effective amendment A0004, NO INFORMATION IS REQUIRED TO BE INSERTED IN TAB E. Project descriptions narrative, photos etc., should be inserted in Tab D, Experience.</p>		
63.	<p>If RFIs can still be addressed, we have the following questions: 1. The scope of work indicates approximately 16 square of roof to be replaced at Building 519A. Can this quantity be confirmed? The drawing provided indicates roughly a 75'x75' roof, with a 32'x32' skylight. Backing out the skylight from the roof area,</p>	The Cherokee 8A Group	03/16/16

Request for Information (RFI) Tracking Log
Solicitation: VA-248-15-R-2023
Project: 675-16-604
Title: Correct Architectural Deficiencies
RFI Tracking Log_RFI# 1-65
3/17/2016

	results in just over 4500sf of roof system. Is the intent to only replace a portion of this roof?		
Response	The entire roof is to be replaced, it is the contractor's responsibility to verify measurements... Also, there are no skylights on building 519a.		
64.	Can a preliminary schedule, as required by the Evaluation Factor 2: Technical Approach, be submitted in Primavera?	The Cherokee 8A Group	03/16/16
Response	Yes, in PDF format		
65.	The referenced floor tile: Gerflor; Barma Pure (RFI response to question 11) is manufactured in France. Can the VA provide an example that complies with the Buy American Act?	Biosphere International	03/16/16
Response	Use the example tile as the benchmark. Similar style, color and specs are to be equivalent to, or better than the example.		