

**LEASE NO. VA249-16-L-0028****Warehouse Lease  
FORM L201WH (09/15)**

**INSTRUCTIONS TO OFFEROR:** Do not attempt to complete this lease form (Lease Form L201WH, hereinafter Lease Form). Upon selection for award, VA will transcribe the successful Offeror's final offered rent and other price data included on the lease proposal form (VA Lease Proposal Form 1364WH, hereinafter Lease Proposal Form) into a Lease Form, and transmit the completed Lease Form, together with appropriate attachments, to the successful Offeror for execution.

This Lease is made and entered into between

**Lessor's Name:** \_\_\_\_\_

(Lessor), whose principal place of business is \_\_\_\_\_, and whose interest in the Property described herein is that of Fee Owner, and

The United States of America

(Government), acting by and through the designated representative of the Department of Veteran Affairs (VA), upon the terms and conditions set forth herein.

Witnesseth: The parties hereto, for the consideration hereinafter mentioned, covenant and agree as follows:

Lessor hereby leases to the Government the Premises described herein, being all or a portion of the Property located at

\_\_\_\_\_ and more fully described in Section 1 and Exhibit A, together with rights to the use of parking and other areas as set forth herein, to be used for such purposes as determined by VA.

**LEASE TERM**

To Have and To Hold the said Premises with its appurtenances for the term beginning upon acceptance of the Premises as required by this Lease and continuing for a period of

**10 Years, 5 Years Firm,**

subject to termination and renewal rights as may be hereinafter set forth. The commencement date of this Lease, along with any applicable termination and renewal rights, shall be more specifically set forth in a Lease Amendment upon substantial completion and acceptance of the Space by the Government.

In Witness Whereof, the parties to this Lease evidence their agreement to all terms and conditions set forth herein by their signatures below, to be effective as of the date of delivery of the fully executed Lease to the Lessor.

**FOR THE LESSOR:**

\_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

Entity Name: \_\_\_\_\_

Date: \_\_\_\_\_

**FOR THE GOVERNMENT:**

\_\_\_\_\_

Name: \_\_\_\_\_

Title: Lease Contracting Officer

Department of Veteran Affairs

Date: \_\_\_\_\_

**WITNESSED FOR THE LESSOR BY:**

\_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_

The information collection requirements contained in this Solicitation/Contract, that are not required by the regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

<b>SECTION 1 THE PREMISES, RENT, AND OTHER TERMS</b>	<b>5</b>
1.01 THE PREMISES (WAREHOUSE) (SEP 2015)	5
1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)	5
1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)	5
1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.06 RENT AND OTHER CONSIDERATION (SEP 2015)	6
1.07 INTENTIONALLY DELETED	6
1.08 TERMINATION RIGHTS AFTER 5 YEARS	6
1.09 INTENTIONALLY DELETED	7
1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (APR 2015)	7
1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)	7
1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (SEP 2013)	7
1.13 TENANT IMPROVEMENT FEE SCHEDULE (JUN 2012)	7
1.14 INTENTIONALLY DELETED	7
1.15 INTENTIONALLY DELETED	7
1.16 INTENTIONALLY DELETED	7
1.17 INTENTIONALLY DELETED	7
1.18 INTENTIONALLY DELETED	7
1.19 RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)	7
1.20 INTENTIONALLY DELETED	8
1.21 24-HOUR HVAC REQUIREMENT (SEP 2014)	8
1.22 BUILDING IMPROVEMENTS (SEP 2012)	8
1.23 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAY 2012)	8
<b>SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS</b>	<b>9</b>
2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (MAY 2014)	9
2.02 AUTHORIZED REPRESENTATIVES (JUN 2012)	10
2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (SEP 2013)	10
2.04 WAIVER OF RESTORATION (APR 2011)	10
2.05 INTENTIONALLY DELETED	10
2.06 CHANGE OF OWNERSHIP (APR 2015)	11
2.07 INTENTIONALLY DELETED	11
2.08 ADJUSTMENT FOR VACANT PREMISES (SEP 2013)	11
2.09 INTENTIONALLY DELETED	11
2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)	11
2.11 INTENTIONALLY DELETED	12
<b>SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS</b>	<b>13</b>
3.01 LABOR STANDARDS (SEP 2013)	13
3.02 WORK PERFORMANCE (JUN 2012)	13
3.03 RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (MAY 2014)	13
3.04 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (JUN 2012)	13
3.05 CONSTRUCTION WASTE MANAGEMENT (SEP 2008)	13
3.06 WOOD PRODUCTS (MAY 2014)	14
3.07 ADHESIVES AND SEALANTS (AUG 2008)	14
3.08 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (MAY 2014)	14
3.09 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)	14
3.10 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)	15
3.11 VESTIBULES (APR 2011)	15
3.12 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)	15
3.13 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)	15
3.14 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)	15
3.15 ENERGY INDEPENDENCE AND SECURITY ACT (DEC 2011)	16
3.16 ELEVATORS (WAREHOUSE) (MAY 2014)	16
3.17 FLAGPOLE (SEP 2013)	16
3.18 DEMOLITION (JUN 2012)	16
3.19 ACCESSIBILITY (FEB 2007)	16
3.20 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)	17
3.21 DOORS: IDENTIFICATION (APR 2011)	17
3.22 WINDOWS (APR 2011)	17
3.23 PARTITIONS: GENERAL (APR 2015)	17
3.24 PARTITIONS: PERMANENT (APR 2015)	17
3.25 INSULATION: THERMAL, ACOUSTIC, AND HVAC (SEP 2013)	17
3.26 WALL FINISHES—SHELL (JUN 2012)	18
3.27 PAINTING—SHELL (JUN 2012)	18
3.28 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (APR 2015)	18
3.29 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)	18
3.30 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)	19
3.31 BUILDING SYSTEMS (APR 2011)	19
3.32 ELECTRICAL—SHELL (WAREHOUSE) (MAY 2014)	19

3.33	ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)	19
3.34	PLUMBING (JUN 2012)	19
3.35	DRINKING FOUNTAINS (WAREHOUSE) (MAY 2014)	19
3.36	RESTROOMS (WAREHOUSE) (MAY 2014)	19
3.37	PLUMBING FIXTURES: WATER CONSERVATION (DEC 2011)	20
3.38	JANITOR CLOSETS (JUN 2012)	20
3.39	HEATING AND VENTILATION—SHELL (WAREHOUSE) (MAY 2014)	20
3.40	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)	21
3.41	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)	21
3.42	LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (MAY 2014)	22
3.43	ACOUSTICAL REQUIREMENTS (JUN 2012)	22
3.44	INTENTIONALLY DELETED	22
3.45	INTENTIONALLY DELETED	22
3.46	INTENTIONALLY DELETED	22
3.47	INTENTIONALLY DELETED	22
3.48	INDOOR AIR QUALITY DURING CONSTRUCTION (SEP 2013)	23
3.49	SYSTEMS COMMISSIONING (APR 2011)	23
3.50	LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)	23
3.51	EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)	24
3.52	MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)	24
3.53	DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)	24
3.54	NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS - LEASE (SEP 2014)	25

#### **SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES..... 26**

4.01	SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (MAY 2014)	26
4.02	CONSTRUCTION DOCUMENTS (SEP 2012)	26
4.03	TENANT IMPROVEMENTS PRICE PROPOSAL (SEP 2013)	26
4.04	INTENTIONALLY DELETED	26
4.05	TENANT IMPROVEMENTS PRICING REQUIREMENTS (SEP 2013)	26
4.06	GREEN LEASE SUBMITTALS (JUN 2012)	27
4.07	CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)	28
4.08	PROGRESS REPORTS (JUN 2012)	28
4.09	ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)	28
4.10	CONSTRUCTION INSPECTIONS (APR 2011)	28
4.11	ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (MAY 2015)	28
4.12	LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)	28
4.13	AS-BUILT DRAWINGS (JUN 2012)	28
4.14	LIQUIDATED DAMAGES (JUN 2012)	29
4.15	INTENTIONALLY DELETED	29
4.16	LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)	29

#### **SECTION 5 TENANT IMPROVEMENT COMPONENTS..... 30**

5.01	TENANT IMPROVEMENT REQUIREMENTS (MAY 2014)	30
5.02	FINISH SELECTIONS (JUN 2012)	30
5.03	WINDOW COVERINGS (WAREHOUSE) (JUN 2012)	30
5.04	DOORS: SUITE ENTRY (SEP 2013)	30
5.05	DOORS: INTERIOR (SEP 2013)	30
5.06	DOORS: HARDWARE (SEP 2013)	30
5.07	DOORS: IDENTIFICATION (JUN 2012)	30
5.08	PARTITIONS: SUBDIVIDING (SEP 2015)	30
5.09	CEILINGS—TI (WAREHOUSE) (APR 2015)	31
5.10	WALL FINISHES (JUN 2012)	31
5.11	PAINTING—TI (WAREHOUSE) (MAY 2014)	31
5.12	FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (APR 2015)	32
5.13	HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)	32
5.14	ELECTRICAL: DISTRIBUTION—TI (WAREHOUSE) (MAY 2014)	32
5.15	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)	33
5.16	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)	33
5.17	DATA DISTRIBUTION (JUN 2012)	33
5.18	ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)	33
5.19	LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)	33
5.20	LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)	34

#### **SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM..... 35**

6.01	PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)	35
6.02	UTILITIES (APR 2011)	35
6.03	UTILITY CONSUMPTION REPORTING (SEP 2015)	35
6.04	HEATING AND AIR CONDITIONING (WAREHOUSE) (SEP 2014)	35
6.05	OVERTIME HVAC USAGE (JUN 2012)	35
6.06	JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)	36

6.06	SELECTION OF CLEANING PRODUCTS (APR 2015)	36
6.07	SELECTION OF PAPER PRODUCTS (APR 2015)	36
6.08	SNOW REMOVAL (WAREHOUSE) (MAY 2014)	36
6.09	MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)	36
6.10	MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (MAY 2014)	37
6.11	ASBESTOS ABATEMENT (APR 2011)	37
6.12	ONSITE LESSOR MANAGEMENT (APR 2011)	37
6.13	IDENTITY VERIFICATION OF PERSONNEL (MAY 2014)	37
6.14	SCHEDULE OF PERIODIC SERVICES (JUN 2012)	38
6.15	LANDSCAPING (JUN 2012)	38
6.16	LANDSCAPE MAINTENANCE (APR 2011)	38
6.17	RECYCLING—WAREHOUSE (JUN 2012)	38
6.18	RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)	39
6.19	INTENTIONALLY DELETED	39
6.20	INDOOR AIR QUALITY (MAY 2014)	39
6.21	RADON IN AIR (SEP 2013)	39
6.22	INTENTIONALLY DELETED	39
6.23	HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)	39
6.24	MOLD (SEP 2013)	40
6.25	OCCUPANT EMERGENCY PLANS (SEP 2013)	40
6.26	FLAG DISPLAY (SEP 2013)	40
6.27	PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)	40
6.28	TRASH DUMPSTER SERVICE (WAREHOUSE) (MAY 2014)	40
6.29	ACCESS TO BUILDING INFORMATION (MAY 2014)	40
<b>SECTION 7 ADDITIONAL TERMS AND CONDITIONS</b>		<b>42</b>
7.01	SECURITY REQUIREMENTS (MAY 2014)	42

## SECTION 1 THE PREMISES, RENT, AND OTHER TERMS

### 1.01 THE PREMISES (WAREHOUSE) (SEP 2015)

The Premises are described as follows:

- A. Warehouse and Related Space: \_\_\_\_\_ rentable square feet yielding \_\_\_\_\_ Net Usable Square Feet (NUSF) square feet (SF) of warehouse Space known as Suite(s) \_\_\_\_\_, of the Building, as depicted on the floor plan(s) attached hereto as Exhibit A.
- B. Common Area Factor: The Common Area Factor (CAF) is established as \_\_\_\_\_ percent. This factor, which represents the conversion from ABOA to rentable square feet, rounded to the nearest whole percentage, shall be used for purposes of rental adjustments in accordance with the Payment Clause of the General Clauses.

### 1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)

The Government shall have exclusive or non-exclusive (as identified) right to the use of Appurtenant Areas, and shall have the right to post Rules and Regulations Governing Conduct on Federal Property, Title 41, CFR, Part 102-74, Subpart C within such areas. The Government will coordinate with Lessor to ensure signage is consistent with Lessor's standards. Appurtenant to the Premises and included in the Lease are rights to use the following:

- A. Automobile Parking:  
\_\_\_\_\_ parking spaces for passenger vehicles as depicted on the plan attached hereto as Exhibit B of which \_\_\_\_\_ spaces shall be marked as reserved for the exclusive use of the Government. In addition, the Lessor shall provide any additional automobile parking spaces as required by the applicable code of the local government entity having jurisdiction over the Property. All spaces must be secured and lit in accordance with the Security Requirements set forth in this Lease. The cost of this parking shall be included as part of the rental consideration.
- B. INTENTIONALLY DELETED
- C. Delivery Route:  
(1) At least one unobstructed route having no steps or abrupt changes in level shall connect with all accessible elements, spaces, buildings, and courses of passage. The minimum clear width of a route shall be 36 inches. If a route is less than 60 inches in width then it shall have level passing zones, spaced at no more than 200 feet apart, measuring a minimum of 60 inches by 60 inches.
- (2) Objects projecting from walls with their leading edges between 27 and 80 inches above the finished floor shall protrude no more than 4 inches into an accessible route. Freestanding objects mounted on posts or pylons may overhang 12 inches maximum from 27 to 80 inches above the ground or the finished floor. Objects mounted with their leading edges at or below 27 inches above the finished floor may protrude any distance. However, no protruding objects shall reduce the clear width of an accessible route or maneuvering space. If vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches, a barrier to warn blind or visually impaired persons shall be provided.
- (3) Mechanical rooms and spaces which are not normally frequented by the public or occupants and are not part of an accessible or emergency route are excepted and need not be accessible.
- (4) Gratings in a route surface shall have spaces no wider than ½ inch in one direction and shall be placed so that the long dimension of openings is perpendicular to the dominant direction of travel.
- D. Delivery Ramps:  
(1) Any part of an accessible route with a slope greater than 1 foot rise in 20 feet shall be considered a ramp. Where ramps are necessary, they shall have a non-slip surface with a slope no greater than 1 foot rise in 12 feet. Ramps must have a minimum clear width of 3 feet with level landings at the top and bottom of each ramp run. Each landing shall be at least 5 feet in length and as wide as any ramp run leading into it. The maximum rise for any run shall be 30 inches. Intermediate landings for turning ramps shall measure a minimum of 5 feet by 5 feet.
- (2) Lessor shall provide handrails complying with "HANDRAILS" (36 CFR 1191) on both sides of all ramps with a vertical rise greater than 6 inches. Ramps with drop-offs shall have curbs (minimum 2 inches high), walls, railings or projecting surfaces. Lessor shall provide curb ramps wherever an accessible route crosses a curb. Curb ramps shall not interfere with walks or vehicular traffic. The maximum slope of a curb ramp shall be a 1 inch rise per 12 inch run. The maximum length of a curb ramp shall be 6 feet with a minimum width of 36 inches, exclusive of flared sides. If no other alternative is feasible, accessible platform lifts may be used in lieu of a ramp or elevator. Lifts shall have accessible controls and clearances, shall comply with applicable safety regulations, and should facilitate unassisted entry and exit.
- E. INTENTIONALLY DELETED
- F. Loading Docks. See "LOADING DOCKS SHELL WAREHOUSE" paragraph in Section 3 of this Lease.

### 1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)

At a minimum, a truck turning radius of 100 feet sized for 85 foot trucks shall be provided and maintained at all times for all loading docks designed for such sized trucks. One-way design for service traffic is preferred in order to avoid the need for large turning areas

**1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)**

A minimum of 14,000 NUSF must have a clear ceiling height of 25 feet, measured from floor to the lowest obstruction, with the balance of the space maintaining a clear ceiling height of a minimum of 30 feet. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided.

**1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)**

The following minimum requirements apply to this Lease:

Bay Width: 120 feet (the distance from one side of the bay to the other side of the bay in linear feet and inches)

Bay Depth: 120 feet (the distance from the front of the bay to the back of the bay in linear feet and inches)

Column Spacing: Columns shall be 10 feet linear feet apart from one another

**1.06 RENT AND OTHER CONSIDERATION (SEP 2015)**

A. The Government shall pay the Lessor annual rent, payable in monthly installments in arrears, at the following rates:

	FIRM TERM TBD	NON-FIRM TERM TBD	NON-FIRM TERM TBD	NON-FIRM TERM TBD	NON-FIRM TERM TBD	NON-FIRM TERM TBD
	ANNUAL	ANNUAL	ANNUAL	ANNUAL	ANNUAL	ANNUAL
SHELL RENT						
OPERATING COSTS						
TOTAL						

B. Rent is subject to adjustment based upon a mutual on-site measurement of the Space upon acceptance, not to exceed \_\_\_\_\_ NUSF based upon the methodology outlined under the "Payment" clause of Form 3517.

C. If the Government occupies the Premises for less than a full calendar month, then rent shall be prorated based on the actual number of days of occupancy for that month.

D. Rent shall be paid to the Lessor by electronic funds transfer in accordance with the provisions of the General Clauses. Rent shall be payable to the Payee designated by the Lessor in the System for Award Management (SAM). If the payee is different from the Lessor, both payee and Lessor must be registered in SAM.

E. The Lessor shall provide to the Government, in exchange for the payment of rental and other specified consideration, the following:

1. The leasehold interest in the Property described herein in the paragraph entitled "The Premises."
2. All costs, expenses, and fees to perform the work required for acceptance of the Premises in accordance with this Lease, including all costs for labor, materials, and equipment, professional fees, contractor fees, attorney fees, permit fees, inspection fees, and similar such fees, and all related expenses;
3. Performance or satisfaction of all other obligations set forth in this Lease; and all services, utilities, and maintenance required for the proper operation of the Property, the Building, and the Premises in accordance with the terms of the Lease, including, but not limited to, all inspections, modifications, repairs, replacements, and improvements required to be made thereto to meet the requirements of this Lease.

G. In accordance with the Lease negotiations, the Lessor has offered free rent to the Government for the first \_\_\_\_\_ months of the Lease. Therefore, the first \_\_\_\_\_ months of the Lease shall be provided at no cost to the Government.

**1.07 INTENTIONALLY DELETED****1.08 TERMINATION RIGHTS AFTER 5 YEARS**

Termination Right after 5 years. Notwithstanding anything to the contrary contained in this Lease, after completion of Year 5 of the lease term, the Government may terminate this Lease, in whole or in part, at any time by giving at least ninety (90) days written notice to the lessor, for any reason or no reason whatsoever. The effective date of such termination shall be the first calendar day occurring after such ninety (90) days. If this contract is terminated, the Government shall be liable only for rent payments due and owing to the Lessor prior to, but not including, the effective date of termination, and any unpaid tenant improvement costs identified in the Lease

**1.09 INTENTIONALLY DELETED****1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (APR 2015)**

The following documents are attached to and made part of the Lease:

DOCUMENT NAME	NO. OF PAGES	EXHIBIT
FLOOR PLAN(S)		A
PARKING PLAN(S)		B
SITE PLAN(S)		C
AGENCY SPECIAL REQUIREMENTS		D
SECURITY REQUIREMENTS		E
RACKING/STACKING PLAN(S)		F
FORM 3517B GENERAL CLAUSES		G
FORM 3518-SAM, ADDENDUM TO SYSTEM FOR AWARD MANAGEMENT (SAM) REPRESENTATIONS AND CERTIFICATIONS (ACQUISITIONS OF LEASEHOLD INTERESTS IN REAL PROPERTY)		H
SMALL BUSINESS SUBCONTRACTING PLAN		I

**1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)**

The Tenant Improvement Allowance (TIA) for purposes of this Lease is \$\_\_\_\_\_ per NUSF. The TIA is the amount that the Lessor shall make available for the Government to be used for TIs.

**1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (SEP 2013)**

- A. The Government, at its sole discretion, shall make all decisions as to the use of the TIA. The Government may use all or part of the TIA.
- B. INTENTIONALLY DELETED
- C. If it is anticipated that the Government will spend more than the allowance identified above, the Government may elect to:
1. Reduce the TI requirements;
  2. Pay lump sum for the overage upon substantial completion in accordance with the "Acceptance of Space and Certificate of Occupancy" paragraph;

**1.13 TENANT IMPROVEMENT FEE SCHEDULE (JUN 2012)**

For pricing TI costs, the following rates shall apply for the initial build-out of the Space.

	INITIAL BUILD-OUT
ARCHITECT/ENGINEER FEES ( \$ PER NUSF OR % OF TI CONSTRUCTION COSTS)	\$ OR %
LESSOR'S PROJECT MANAGEMENT FEE (% OF TI CONSTRUCTION COSTS)	%

**1.14 INTENTIONALLY DELETED****1.15 INTENTIONALLY DELETED****1.16 INTENTIONALLY DELETED****1.17 INTENTIONALLY DELETED****1.18 INTENTIONALLY DELETED****1.19 RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)**

In accordance with the paragraph entitled "Adjustment for Vacant Premises," if the Government fails to occupy or vacates the entire or any portion of the Premises prior to expiration of the term of the Lease, the operating costs paid by the Government as part of the rent shall be reduced by \$\_\_\_\_\_ per NUSF of Space vacated by the Government.

**1.20 INTENTIONALLY DELETED****1.21 24-HOUR HVAC REQUIREMENT (SEP 2014)**

- A. 14,000 NUSF of the Space shall receive cooling at all times (24 hrs a day, 365 days a year) for purposes of cooling the designated server room. The BTU output of this room is established as 238,000 BTU. The temperature of this room shall be maintained at 67 to 78 degrees F, with humidity control not to exceed 60% relative humidity, regardless of outside temperature or seasonal changes.

**1.22 BUILDING IMPROVEMENTS (SEP 2012)**

Before the Government accepts the Space, the Lessor shall complete the following additional Building improvements:

- A. \_\_\_\_\_  
 B. \_\_\_\_\_  
 C. \_\_\_\_\_

**1.23 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAY 2012)**

If the Lessor is a qualified HUBZone small business concern (SBC) that did not waive the price evaluation preference then as required by 13 C.F.R. 126.700, the HUBZone SBC must spend at least 50% of the cost of the contract incurred for personnel on its own employees or employees of other qualified HUBZone SBC's and must meet the performance of the work requirements for subcontracting in 13 C.F.R. § 125.6(c). If the Lessor is a HUBZone joint venture, the aggregate of the qualified HUBZone SBC's to the joint venture, not each concern separately, must perform the applicable percentage of work required by this clause.



## SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS

### 2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (MAY 2014)

Unless otherwise specifically noted, all terms and conditions set forth in this Lease shall be interpreted by reference to the following definitions, standards, and formulas:

- A. Appurtenant Areas. Appurtenant Areas are defined as those areas and facilities on the Property that are not located within the Premises, but for which rights are expressly granted under this Lease, or for which rights to use are reasonably necessary or reasonably anticipated with respect to the Government's enjoyment of the Premises and express appurtenant rights.
- B. INTENTIONALLY DELETED
- C. Building. The building(s) situated on the Property in which the Premises are located shall be referred to as the Building(s).
- D. INTENTIONALLY DELETED
- E. Common Area Factor (CAF). The Common Area Factor (CAF) is a conversion factor determined by the Building owner and applied by the owner to the NUSF to determine the RSF for the leased Space. The CAF is expressed as a percentage of the difference between the amount of rentable SF and NUSF, divided by the NUSF. For example 11,500 RSF and 10,000 NUSF will have a CAF of 15% [(11,500 RSF-10,000 NUSF)/10,000 NUSF].
- F. Contract. "Contract" shall mean this Lease.
- G. Contractor. "Contractor" shall mean Lessor.
- H. Days. All references to "day" or "days" in this Lease shall mean calendar days, unless specified otherwise.
- I. FAR. All references to the FAR shall be understood to mean the Federal Acquisition Regulation, codified at 48 CFR Chapter 1.
- J. Federal Holidays. Federal law (5 U.S.C. 6103) establishes the following public holidays for Federal employees: New Year's Day, Birthday of Martin Luther King, Jr., Washington's Birthday, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans Day, Thanksgiving Day, and Christmas Day. Please note that most Federal employees work on a Monday through Friday schedule. For these employees, when a holiday falls on a nonworkday -- Saturday or Sunday -- the holiday usually is observed on Monday (if the holiday falls on Sunday) or Friday (if the holiday falls on Saturday)].
- K. Firm Term/Non-Firm Term. The Firm Term is that part of the Lease term that is not subject to termination rights. The Non-Firm Term is that part of the Lease term following the end of the Firm Term.
- L. GSAR. All references to the GSAR shall be understood to mean the GSA supplement to the FAR, codified at 48 CFR Chapter 5.
- M. Lease Term Commencement Date. The date on which the lease term commences.
- N. Lease Award Date. The date the LCO executes the Lease and mailing or otherwise furnishes written notification of the executed Lease to the successful Offeror ( date on which the parties' obligations under the Lease begin).
- O. Net Usable Square Feet. For the purposes of this Lease, Space shall be measured in Net Usable Square Feet (NUSF). That portion of rentable space that is available for a tenant's personnel, furnishings, and equipment, and includes the floor area of full-height columns and projections enclosing the structural elements of the building within the space. Net usable space is the area for which VA will pay a square foot rate. It is determined as follows:

If the space is on a single tenancy floor, compute the inside area by measuring between the inside finish of the permanent exterior building walls or from the face of the convectors (pipes or other wall-hung fixtures) if the convector occupies at least 50% of the length of exterior walls.

If the space is on a multiple tenancy floor, measure from the exterior building walls as above and to the room side finish of the fixed shared public corridor and shaft walls and/or the centerline of tenant-separating fixed wall partitions.

Deduct the following from the inside gross area, including the enclosing walls, to arrive at the figure for net usable square feet:

- Housekeeping closets not contained in programmed areas
- Public restrooms and lounges
- Building equipment and service areas
- Public corridors and entrance lobbies
- Vertical circulation (elevators, escalators, and stairs)

- P. Premises. Defined as the total Warehouse Area, Office Area, and other type of Space, together with all associated common areas, described in Section 1 of this Lease, and delineated by plan in the attached exhibit. Parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease are not included in the Premises.
- Q. Property. Defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas, wareyards, loading docks, aprons, loading ramps) to which the Government is granted rights.
- R. Racking System Plan—A plan that at a minimum must include clear ceiling height requirement(s), aisle width(s), shelving depth(s) and type of material(s) to be stored. In addition such Plan shall identify locations and dimensions of storage of materials in packed piles, on pallets, in racks, or on shelves.
- S. Rentable Space or Rentable Square Feet (RSF). Rentable Space is the area for which a tenant is charged rent. It is determined by the Building owner and may vary by city or by building within the same city. The Rentable Space may include a share of Building support/common areas such as elevator lobbies, Building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The Rentable Space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts. Rentable Square Feet is calculated using the following formula for each type of Space (e.g., office, warehouse, etc.) included in the Premises:  $\text{NUSF of Space} \times (1 + \text{CAF}) = \text{RSF}$ .
- T. Space. The Space shall refer to that part of the Premises to which the Government has exclusive use, such as Office Area, or other type of Space. Parking areas, wareyards, loading docks, aprons, loading ramps to which the Government has rights under this Lease are not included in the Space.
- U. Warehouse and office space. For the purposes of this Lease, Space shall be measured in accordance with the standard (Z65.1-1996) provided by American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) for Office Area, which means "the area where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed." References to ABOA mean ANSI/BOMA Office Area.
- V. VAAR. All references to the VAAR shall be understood to mean the Veterans Administration Acquisition Regulation, codified in 38 U.S.C. §501, §8127, §8128, and §8151-8153; 40 U.S.C. §121©; and 48 CFR 1.301-1.304.
- W. Working Days. Working Days shall mean weekdays, excluding Saturdays and Sundays and Federal holidays.

## 2.02 AUTHORIZED REPRESENTATIVES (JUN 2012)

The signatories to this Lease shall have full authority to bind their respective principals with regard to all matters relating to this Lease. No other persons shall be understood to have any authority to bind their respective principals, except to the extent that such authority may be explicitly delegated by notice to the other party, or to the extent that such authority is transferred by succession of interest. The Government shall have the right to substitute its Lease Contracting Officer (LCO) by notice, without an express delegation by the prior LCO.

## 2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (SEP 2013)

A. The Government may request the Lessor to provide alterations during the term of the Lease. Alterations will be ordered by issuance of a Lease Amendment, GSA Form 300, Order for Supplies or Services, or, when specifically authorized to do so by the LCO, a tenant agency-approved form. The GSAM clause, 552.270-31, Prompt Payment, including its invoice requirements, shall apply to orders for alterations. All orders are subject to the terms and conditions of this Lease and may be placed by the LCO or a warranted contracting officer's representative (COR) in VA or the tenant agency when specifically authorized to do so by the Lease Contracting Officer, subject to the threshold limitation below.

B. Orders for alterations issued by an authorized COR are limited to no more than \$150,000 (LCOs are not subject to this threshold). This threshold will change according to future adjustments of the simplified acquisition threshold (see FAR 2.101). The LCO will provide the Lessor with a list of tenant agency officials authorized to place orders and will specify any limitations on the authority delegated to tenant agency officials. The tenant agency officials are not authorized to deal with the Lessor on any other matters.

C. Payments for alterations ordered by the tenant agency under the authorization described in sub-paragraph B will be made directly by the tenant agency placing the order.

## 2.04 WAIVER OF RESTORATION (APR 2011)

The Lessor shall have no right to require the Government to restore the Premises upon termination of the Lease, and waives all claims against the Government for waste, damages, or restoration arising from or related to (a) the Government's normal and customary use of the Premises during the term of the Lease (including any extensions thereof), as well as (b) any initial or subsequent alteration to the Premises regardless of whether such alterations are performed by the Lessor or by the Government. At its sole option, the Government may abandon property in the Space following expiration of the Lease, in which case the property will become the property of the Lessor and the Government will be relieved of any liability in connection therewith.

## 2.05 INTENTIONALLY DELETED

**2.06 CHANGE OF OWNERSHIP (APR 2015)**

A. If during the term of the Lease, title to the Property is transferred, the Lease is assigned, or the Lessor changes its legal name, the Lessor and its successor shall comply with the requirements of FAR Subpart 42.12. If title is transferred, the Lessor shall notify the Government within five days of the transfer of title.

B. The Government and the Lessor may execute a Change of Name Agreement if the Lessor is changing only its legal name, and the Government's and the Lessor's respective rights and obligations remain unaffected. A sample form is found at FAR 42.1205.

C. If title to the Property is transferred, or the Lease is assigned, the Government, the original Lessor (Transferor), and the new owner or assignee (Transferee) shall execute a Novation Agreement providing for the transfer of Transferor's rights and obligations under the Lease to the Transferee. When executed on behalf of the Government, a Novation Agreement will be made part of the Lease via Lease Amendment.

D. In addition to all documents required by FAR 42.1204, the LCO may request additional information (e.g., copy of the deed, bill of sale, certificate of merger, contract, court decree, articles of incorporation, operation agreement, partnership certificate of good standing, etc.) from the Transferor or Transferee to verify the parties' representations regarding the transfer, and to determine whether the transfer of the Lease is in the Government's interest.

E. If the LCO determines that recognizing the Transferee as the Lessor will not be in the Government's interest, the Transferor shall remain fully liable to the Government for the Transferee's performance of obligations under the Lease, notwithstanding the transfer. Under no condition shall the Government be obligated to release the Transferor of obligations prior to (a) the rent commencement date; and (b) any amounts due and owing to the Government under the Lease have been paid in full or completely set off against the rental payments due under the Lease.

F. As a condition for being recognized as the Lessor and entitlement to receiving rent, the Transferee must register in the System for Award Management (SAM) (See FAR 52.232-33), and complete and sign GSA Form 3518-SAM, Addendum to System for Award Management (SAM) Representations and Certifications (Acquisitions of Leasehold Interests in Real Property).

G. If title to the Property is transferred, or the Lease is assigned, rent shall continue to accrue, subject to the Government's rights as provided for in this Lease. However, the Government's obligation to pay rent to the Transferee shall be suspended until the Government has received all information reasonably required by the LCO under sub-paragraph D, the Government has determined that recognizing the Transferee as the Lessor is in the Government's interest (which determination will be prompt and not unreasonably withheld), and the Transferee has met all conditions specified in sub-paragraph F. So long as any delays in effecting the recognition of Transferee as Lessor are not the responsibility of the Government, no interest shall accrue on suspended rent.

**2.07 INTENTIONALLY DELETED****2.08 ADJUSTMENT FOR VACANT PREMISES (SEP 2013)**

A. If the Government fails to occupy any portion of the leased Premises or vacates the Premises in whole or in part prior to expiration of the term of the Lease, the rental rate and the base for operating cost adjustments will be reduced.

B. If no rate reduction has been established in this Lease, the rate will be reduced by that portion of the costs per NUSF of operating expenses not required to maintain the Space. Said reduction shall occur after the Government gives 30 calendar days' prior notice to the Lessor and shall continue in effect until the Government occupies the vacant Premises or the Lease expires or is terminated.

**2.09 INTENTIONALLY DELETED****2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)**

A. If the Lessor is a HUBZone small business concern (SBC) that did not waive the price evaluation preference, the Lessor shall provide a certification within 10 days after Lease award to the LCO (or representative designated by the LCO) that the Lessor was an eligible HUBZone SBC on the date of award. If it is determined within 20 days after award that a HUBZone SBC Offeror that has been awarded the Lease was not an eligible HUBZone SBC at the time of award, and the HUBZone SBC Lessor failed to provide the LCO with information regarding a change to its HUBZone eligibility prior to award, then the Lease shall be subject, at the LCO's discretion, to termination, and the Government will be relieved of all obligations to the Lessor in such an event and not be liable to the Lessor for any costs, claims or damages of any nature whatsoever.

B. Within **10** days after Lease award, the Lessor shall provide to the LCO (or representative designated by the LCO) evidence of:

1. A firm commitment of funds in an amount sufficient to perform the work.
2. The names of at least two proposed construction contractors, as well as evidence of the contractors' experience, competency, and performance capabilities with construction similar in scope to that which is required herein.
3. The license or certification to practice in the state where the Building is located from the individual(s) and/or firm(s) providing architectural and engineering design services.

C. The Government shall have the right to withhold approval of design intent drawings (DIDs) until the conditions specified in sub-paragraphs A and B have been satisfied.

D. Within ten (10) calendar days after the LCO issues the Notice To Proceed (NTP) for TI construction, the Lessor shall provide to the LCO evidence of:

1. Award of a construction contract for TIs with a firm completion date. This date must be in accordance with the construction schedule for TIs as described in the "Schedule for Completion of Space" paragraph of this Lease.
2. Issuance of required permits for construction of the TIs.

**2.11 INTENTIONALLY DELETED**

## SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS

### 3.01 LABOR STANDARDS (SEP 2013)

If the Lessor proposes to satisfy the requirements of this Lease through the construction of a new Building or the complete rehabilitation or reconstruction of an existing Building, and the Government will be the sole or predominant tenant such that any other use of the Building will be functionally or quantitatively incidental to the Government's use and occupancy, the following FAR clauses shall apply to all work (including shell and TIs) performed prior to the Government's acceptance of space as substantially complete. Full text versions of these clauses are available upon request from the LCO. Full text versions are also available at <https://www.acquisition.gov/far/>

- 52.222-4 Contract Work Hours and Safety Standards Act—Overtime Compensation
- 52.222-6 Davis-Bacon Act
- 52.222-7 Withholding of Funds
- 52.222-8 Payrolls and Basic Records
- 52.222-9 Apprentices and Trainees
- 52.222-10 Compliance with Copeland Act Requirements
- 52.222-11 Subcontracts (Labor Standards)
- 52.222-12 Contract Termination-Debarment
- 52.222-13 Compliance with Davis-Bacon and Related Act Regulations
- 52.222-14 Disputes Concerning Labor Standards
- 52.222-15 Certification of Eligibility

### 3.02 WORK PERFORMANCE (JUN 2012)

All work in performance of this Lease shall be done by skilled workers or mechanics and shall be acceptable to the LCO. The LCO may reject the Lessor's workers 1) if such are unlicensed, unskilled, or otherwise incompetent, or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other government or private contracts.

### 3.03 RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (MAY 2014)

A. The Lessor shall comply to the extent feasible with the Resource Conservation and Recovery Act (RCRA), Section 6002, 1976. The Lessor shall use recycled content products as indicated in this Lease and as designated by the U.S. Environmental Protection Agency (EPA) in the Comprehensive Procurement Guidelines (CPG), 40 CFR Part 247, and its accompanying Recovered Materials Advisory Notice (RMAN). The CPG lists the designated recycled content products. EPA also provides recommended levels of recycled content for these products. The list of designated products, EPA's recommendations, and lists of manufacturers and suppliers of the products can be found at <http://www.epa.gov/cpg>.

B. The Lessor, if unable to comply with both the CPG and RMAN lists, shall submit a Request for Waiver for each material to the LCO with the TI pricing submittal. The request for waiver shall be based on the following criteria:

1. The cost of the recommended product is unreasonable.
2. Inadequate competition exists.
3. Items are not available within a reasonable period.
4. Items do not meet Lease performance standards.

### 3.04 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (JUN 2012)

A. Items and materials existing in the Premises, or to be removed from the Premises during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in re-furnished condition and shall meet the quality standards set forth by the Government in this Lease. In the absence of definitive quality standards, the Lessor is responsible to confirm that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.

B. The Lessor shall submit a reuse plan to the LCO. The Government will not pay for existing fixtures and other TIs accepted in place. However, the Government will reimburse the Lessor, as part of the TIA, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the LCO.

### 3.05 CONSTRUCTION WASTE MANAGEMENT (SEP 2008)

A. Recycling construction waste is mandatory for initial space alterations for TIs and subsequent alterations under the Lease.

B. Recycling construction waste means providing all services necessary to furnish construction materials or wastes to organizations which will employ these materials or wastes in the production of new materials. Recycling includes required labor and equipment necessary to separate individual materials from the assemblies of which they form a part.

C. SUBMITTAL REQUIREMENT: Refer to the Green Lease Submittals paragraph of the Lease.

D. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility:

1. Ceiling grid and tile
2. Light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bulbs
3. Duct work and HVAC equipment
4. Wiring and electrical equipment
5. Aluminum and/or steel doors and frames
6. Hardware
7. Drywall
8. Steel studs
9. Carpet, carpet backing, and carpet padding
10. Wood
11. Insulation
12. Cardboard packaging
13. Pallets
14. Windows and glazing materials
15. All miscellaneous metals (as in steel support frames for filing equipment)
16. All other finish and construction materials.

E. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCBs) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with Federal and state laws and requirements concerning hazardous waste.

F. In addition to providing "one time" removal and recycling of large scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.

G. Construction materials recycling records shall be maintained by the Lessor and shall be accessible to the LCO. Records shall include materials recycled or land-filled, quantity, date, and identification of hazardous wastes.

### **3.06 WOOD PRODUCTS (MAY 2014)**

A. For all new installations of wood products, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Certification Resource Center ([www.certifiedwood.org](http://www.certifiedwood.org)), the Forest Stewardship Council United States ([www.fscus.org](http://www.fscus.org)), or the Sustainable Forestry Initiative ([www.sfiprogram.org](http://www.sfiprogram.org)).

B. New installations of wood products used under this contract shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at [www.cites.org/eng/resources/species.html](http://www.cites.org/eng/resources/species.html).

C. Particle board, strawboard, and plywood materials shall comply with Department of Housing and Urban Development (HUD) standards for formaldehyde emission controls. Plywood materials shall not emit formaldehyde in excess of 0.2 parts per million (ppm), and particleboard materials shall not emit formaldehyde in excess of 0.3 ppm.

D. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

### **3.07 ADHESIVES AND SEALANTS (AUG 2008)**

All adhesives employed on this project (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall be those with the lowest possible VOC content below 20 grams per liter and which meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no formaldehyde or heavy metals. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

### **3.08 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (MAY 2014)**

A. The Building Shell shall be designed, constructed, and maintained in accordance with the standards set forth herein and completed prior to acceptance of Space. For pricing, fulfillment of all requirements not specifically designated as TIs, Building Specific Amortized Capital, Operating Costs, or other rent components as indicated shall be deemed included in the Shell Rent.

B. Base structure and Building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and service areas, shall be complete. Restrooms shall be complete and operational with an adequate number of fixtures for men and women to meet current local codes based on building occupancy and use. All newly installed Building shell components, including but not limited to, heating and ventilation, electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with TIs. Circulation corridors are provided as part of the base Building only on multi-tenanted buildings where the corridor is common to more than one tenant. In single tenant buildings, only the fire egress corridor(s) necessary to meet code is provided as part of the shell.

### **3.09 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)**

A. The Lessor shall be responsible for the professional quality, technical accuracy, and the coordination of all designs, drawings, specifications, and other services furnished by the Lessor under this contract. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services.

B. THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Government retains the right to review and approve many aspects of the Lessor's design, including without limitation, review of the Lessor's design and construction drawings, shop drawings, product data, finish samples, and completed base building and TI construction. Such review and approval is intended to identify potential design flaws, to minimize costly misdirection of effort, and to assist the Lessor in its effort to monitor whether such design and construction comply with applicable laws and satisfy all Lease requirements.

C. Neither the Government's review, approval or acceptance of, nor payment through rent of the services required under this contract, shall be construed to operate as a waiver of any rights under this contract or of any cause of action arising out of the performance of this contract, and the Lessor shall be and remain liable to the Government in accordance with applicable law for all damages to the Government caused by the Lessor's negligent performance of any of the services required under this Lease.

D. Design and construction and performance information is contained throughout several of the documents which comprise this Lease. The Lessor shall provide to space planners, architects, engineers, construction contractors, etc., all information required whether it is found in this Lease, special requirements and attachments, price lists, or design intent drawings. Reliance upon one of these documents to the exclusion of any other may result in an incomplete understanding of the scope of the work to be performed and/or services to be provided.

### **3.10 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)**

The Building in which the leased Space is located shall be designed, built, and maintained in good condition, suitable for Lessee's use at all times, and in accordance with the requirements of this Lease.

### **3.11 VESTIBULES (APR 2011)**

A. Vestibules shall be provided at public entrances and exits wherever weather conditions and heat loss are important factors for consideration. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure.

B. The Lessor shall provide permanent entryway systems (such as grilles or grates) to control dirt and particulates from entering the Building at all primary exterior entryways.

### **3.12 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)**

A. Prior to occupancy, the Premises and any parking garage areas shall meet or will be upgraded to meet, either the applicable egress requirements in the National Fire Protection Association, Life Safety Code (NFPA 101), or the International Code Council, International Building Code (IBC), each current as of the Lease Award Date, or use an alternative approach or method that achieves an equivalent level of safety deemed acceptable by the Government.

B. The Space shall have unrestricted access to a minimum of two remote exits on each floor of Government occupancy.

C. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the IBC.

### **3.13 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)**

A. Any portion of the space located below-grade, including parking garage areas, and all areas in a building referred to as "hazardous areas" (defined in National Fire Protection Association (NFPA) 101) that are located within the entire Building (including non-Government areas) shall be protected by an automatic fire sprinkler system.

B. The entire warehouse building shall be protected throughout by an automatic fire sprinkler system(s) when the offered space exceeds 10,000 rentable square feet in area.

C. Automatic fire sprinkler system(s) shall be installed in accordance with the requirements of NFPA 13, Standard for the Installation of Sprinkler Systems that was in effect on the actual date of installation.

D. Automatic fire sprinkler system(s) shall be maintained in accordance with the requirements of NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-based Fire Protection Systems (current as of the Lease Award Date).

### **3.14 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)**

A. A Building-wide fire alarm system shall be installed.

B. The fire alarm system shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code that was in effect on the actual date of installation.

C. Fire alarm systems shall be maintained in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date).

D. The fire alarm system shall transmit all fire alarm signals to the local fire department via any of the following means: directly to the local fire department, to the (911) public communications center, to a central station, to a remote supervising station, or to a proprietary supervising station.

E. If the Building's fire alarm control unit is over 25 years old as of the date of award of this Lease, Lessor shall install a new fire alarm system in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date), prior to Government acceptance and occupancy of the Space.

### 3.15 ENERGY INDEPENDENCE AND SECURITY ACT (DEC 2011)

A. The Energy Independence and Security Act (EISA) establishes the following requirements for Government Leases in Buildings that have not earned the ENERGY STAR® Label conferred by the Environmental Protection Agency (EPA) within one year prior to the due date for final proposal revisions ("most recent year").

B. If this Lease was awarded under any of EISA's Section 435 statutory exceptions, the Lessor shall either:

1. Earn the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding Lease); or
2. Complete energy efficiency and conservation improvements if any, agreed to by Lessor in lieu of earning the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding Lease).

C. If this Lease was awarded to a Building to be built or to a Building predominantly vacant as of the due date for final proposal revisions and was unable to earn the ENERGY STAR Label for the most recent year (as defined above) due to insufficient occupancy, but was able to demonstrate sufficient evidence of capability to earn the ENERGY STAR Label, then Lessor must earn the ENERGY STAR Label within 18 months after occupancy by the Government.

(If new construction, see also: 1) Energy Efficiency and Conservation for New Construction, 2) Security for New Construction, and 3) Seismic Safety for New Construction).

### 3.16 ELEVATORS (WAREHOUSE) (MAY 2014)

A. Lessor shall provide suitable passenger elevator and, when required by Government, freight elevator service to any portion of the Premises not having ground level access. Service shall be available during the normal hours of operation specified in this Lease. However, one passenger elevator and, when required by Government, one freight elevator shall be available at all times for Government use. When a freight elevator is required by the Government, it shall be accessible to the loading areas. When possible, Lessor shall provide Government with 24-hour advance notice if the service is to be interrupted for more than 1-1/2 hours. Lessor shall schedule normal service interruption outside of the Government's normal working hours. Lessor shall also use best efforts to minimize the frequency and duration of unscheduled interruptions.

B. Code: Elevators shall conform to the current requirements of the American Society of Mechanical Engineers ASME A17.1/CSA B44, Safety Code for Elevators and Escalators (current as of the Lease Award Date). Elevators shall be provided with Phase I emergency recall operation and Phase II emergency in-car operation in accordance with ASME A17.1/CSA B44. Fire alarm initiating devices (e.g., smoke detectors) used to initiate Phase I emergency recall operation shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (actual date of installation). The elevators shall be inspected and maintained in accordance with the current edition of the ASME A17.2, Inspector's Manual for Elevators. Except for the reference to ASME A17.1 in ABAAS, Section F105.2.2, all elevators must meet ABAAS requirements for accessibility in Sections 407, 408, and 409 of ABAAS.

C. Safety Systems: Elevators shall be equipped with telephones or other two-way emergency communication systems. The system used shall be marked and shall reach an emergency communication location staffed 24 hours per day, 7 days per week.

D. Speed: The passenger elevators shall have a capacity to transport in 5 minutes 15 percent of the normal population of all upper floors (based on 150 SF per person). Further, the dispatch interval between elevators during the up-peak demand period shall not exceed 35 seconds.

E. Interior Finishes: Passenger elevator cab walls must present a quality image and be sufficiently durable to withstand heavy use. Materials must be installed on removable panels or other replaceable devices to facilitate maintenance and renewal of finishes and shall be subject to approval by the LCO. Ceilings must be replaceable. In passenger elevators recessed down lights or indirect fixtures should be used. Passenger elevator cab floors shall be approved by the LCO and shall be carpet, wood, or high-quality resilient flooring materials. If carpet, use materials with low pile height and high density, and otherwise conform to the requirements of this lease, including sustainability requirements. Finishes for freight elevators must be very durable and easy to clean. Stainless steel walls and doors are preferred. Flooring must be sheet vinyl or resilient vinyl tile. Ceiling light fixtures must be recessed and protected from possible damage.

### 3.17 FLAGPOLE (SEP 2013)

If the Government is the sole occupant of the Building, a flagpole shall be provided at a location to be approved by the LCO. The flag of the United States of America will be provided by the Lessor, as part of shell rent, and replaced at all times during the Lease term when showing signs of wear.

### 3.18 DEMOLITION (JUN 2012)

The Lessor shall remove existing abandoned electric, telephone, and data cabling and devices, as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

### 3.19 ACCESSIBILITY (FEB 2007)



The Building, leased Space, and areas serving the leased Space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

### **3.20 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)**

- A. Exterior Building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to TIs.
- B. Exterior doors shall be weather tight and shall open outward. Hinges, pivots, and pins shall be installed in a manner which prevents removal when the door is closed and locked. These doors shall have a minimum clear opening of 32" clear wide x 80" high (per leaf). Doors shall be heavy duty, flush, (1) hollow steel construction, (2) solid core wood, or (3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be fully insulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall be of durable finish and shall have an aesthetically pleasing appearance acceptable to the LCO. The opening dimensions and operations shall conform to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements. Fire door assemblies shall be listed and labeled. Labels on fire door assemblies shall be maintained in a legible condition. Fire door assemblies and their accompanying hardware, including frames and closing devices shall be installed in accordance with the requirements of NFPA 80, Standard for Fire Doors and Other Opening Protectives. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the International Building Code (IBC) as of the Award Date of this Lease.
- C. Exterior doors and all common area doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall or floor mounted) and silencers. All public use doors and restroom doors shall be equipped with kick plates. All doors shall have automatic door closers. All Building exterior doors shall have locking devices installed to reasonably deter unauthorized entry. The Lessor is encouraged to avoid the use of chrome-plated hardware.
- D. There shall be unrestricted access to a minimum of two remote exits on each floor of the Government's occupancy.
- E. Loading docks shall have a roll-up coiling type door with lock.

### **3.21 DOORS: IDENTIFICATION (APR 2011)**

All signage required in common areas unrelated to tenant identification shall be provided and installed by the Lessor.

### **3.22 WINDOWS (APR 2011)**

- A. Office Space shall have windows in each exterior bay unless waived by the LCO.
- B. All windows shall be weather tight. Operable windows that open shall be equipped with locks. Off-street, ground-level windows and those accessible from adjacent roofs, and other structures that can be opened must be fitted with a sturdy locking device.

### **3.23 PARTITIONS: GENERAL (APR 2015)**

Partitions in public areas shall be marble, granite, hardwood, or drywall covered with durable wall covering or high performance coating, or equivalent pre-approved by the LCO. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

### **3.24 PARTITIONS: PERMANENT (APR 2015)**

Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor as part of shell rent as necessary to surround the Space, stairs, corridors, elevator shafts, restrooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by the applicable building code, fire code and ordinances adopted by the jurisdiction in which the Building is located (such as the International Building Code, etc.) current as of the Lease Award Date. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

### **3.25 INSULATION: THERMAL, ACOUSTIC, AND HVAC (SEP 2013)**

- A. All insulation products shall contain recovered materials as required by EPA's CPG and related recycled content recommendations.
- B. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFCs), nor shall CFCs be used in the installation of the product.
- C. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.
- D. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.
- E. All insulation shall be low emitting with not greater than .05 ppm formaldehyde emissions.
- F. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the Lease Award Date) adopted by the jurisdiction in which the Building is located.

**3.26 WALL FINISHES—SHELL (JUN 2012)**

A. Prior to occupancy, all restrooms within the building common areas of government-occupied floors shall have 1) ceramic tile, recycled glass tile, or comparable wainscot from the finished floor to a minimum height of 4'-6" and 2) semigloss paint on remaining wall areas, or other finish approved by the government.

B. All elevator areas that access the Space and hallways accessing the Space shall be covered with wall coverings not less than 20 ounces per square yard, high performance paint, or an equivalent.

**3.27 PAINTING—SHELL (JUN 2012)**

A. The Lessor shall bear the expense for all painting associated with the Building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Space shall be spackled and prime painted with low VOC primer. If any Building shell areas are already painted prior to TIs, the Lessor shall repaint, at the Lessor's expense, as necessary during TIs.

B. The costs for cyclical painting requirements as outlined in Section 6 shall be included in the shell rent.

**3.28 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (APR 2015)**

A. All adjoining floor areas shall be of a common level, and meet ASTM Standard E1155, with a minimum levelness of Ff35 and FL25. Warehouse areas shall have a minimum live load capacity of [e.g., 350] pounds per square foot. The Government may require Lessor to provide written certification of the floor load capacity, at no cost to the Government, by a registered Professional Engineer. The Government may also require calculations and structural drawings at no cost to the Government, by a registered Professional Engineer.

B. Warehouse floor surfacing shall have the appropriate surface performance for the operations being performed as outlined in the following table and as verified with in situ testing. The appropriate surface performance shall be maintained throughout the life of the lease term. Periodic in situ testing shall be performed at a frequency appropriate for the expected useful life of the floor attribute required to be maintained:

	DUTY	APPLICATION	PERFORMANCE
a. Special	Unique requirements	One or more of the following attributes 1. Very heavy-duty operational or equipment traffic 2. Unique surface reflectance criteria 3. Anti slip/ anti skid 4. Chemical resistance 5. Anti static 6. Critical free movement floor 7. Critical defined movement floor 8. Critical dust control 9. Joint free	In addition to the Class 1-3 below  Note: should one or more of the application attributes be critical for the performance of the required operation seek specialized help in tailoring the appropriate requirements)
b. Class 1	Very High Abrasion, steel wheel traffic and impact	Heavy-duty duty impact from pallets/ skid steer forks	<.1mm abrasion resistance Maintenance free joints
c. Class 2	High-abrasion steel wheel or hard wheel traffic	Medium—	<.3 mm abrasion resistance Maintenance free joints
d. Class 3	light abrasion—rubber tire and foot traffic	Light-duty	Dust free finish

b. Floor Hardeners, or coatings shall be utilized to achieve the wear performance for the appropriate duty class required in the above table. Coatings, such as polyurethanes membranes are only acceptable for class 3. Should hardeners be required then nano-lithium silicates or other environmentally friendly practices must be employed.

c. In situ abrasion resistance required of class 2 or 3 shall be determined in accordance with BS EN 13892-4: 2002

C. For new lease construction projects, concrete material must have recycled content in the form of at least 25% fly ash or at least 15% ground granulated blast-furnace (GGBF) slag.

**3.29 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)**

A. Exposed interior floors in primary entrances and lobbies shall be marble, granite, or terrazzo. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, or terrazzo. Resilient flooring shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble, or carpet base.

B. Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all restroom and service areas of Government-occupied floors.

- C. Any alternate flooring must be pre-approved by the LCO
- D. The costs for cyclical carpet replacement requirements as outlined in Section 6 shall be included in the shell rent.

### **3.30 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)**

The Lessor shall provide and operate all Building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in the office Space.

### **3.31 BUILDING SYSTEMS (APR 2011)**

Whenever requested, the Lessor shall furnish to VA as part of shell rent, a report by a registered professional engineer(s) showing that the Building and its systems as designed and constructed will satisfy the requirements of this Lease.

### **3.32 ELECTRICAL—SHELL (WAREHOUSE) (MAY 2014)**

A. The Lessor shall be responsible for meeting the applicable requirements of local codes and ordinances. When codes conflict, the more stringent standard shall apply. The electrical panel supplying electrical service to the warehouse Space shall be located in an enclosed room. The enclosed room should only contain electrical infrastructure and not used for any other purpose. The enclosure must be located within the warehouse Space to be leased and not serve other non-leased facilities. The enclosure shall have door(s) fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch. The electrical distribution panels enclosed in the electrical room shall include both 277/480 volt 3-phase and 120/208 volt 3 phase. A minimum of 150 amps at 240/120 volts per 4,000 rentable square feet of leased Space inclusive of lighting circuits (but assuming no air conditioning mechanical load) shall be provided to circuit breaker panel boxes in the Space. All switchgear, fuses, and circuit breakers shall be plainly marked or labeled to identify circuits and/or equipment supplied through them. All office Space shall have 120/208 V, 3-phase, 4-wire with bond, 60 hertz electric service available. In no event shall such power distribution (not including lighting and HVAC) for the office Space fall below 4 watts per NUSF of Office area. Lessor must provide one watt per NUSF for electrical power distribution for warehouse areas.

B. Main power distribution switchboards and distribution and lighting panel boards shall be circuit breaker type with copper buses that are properly rated to provide the calculated fault circuits. All power distribution panel boards shall be supplied with separate equipment ground buses. All power distribution equipment shall be required to handle the actual specified and projected loads and 10 percent spare load capacity. Distribution panels are required to accommodate circuit breakers for the actual calculated needs and 10 percent spare circuits that will be equivalent to the majority of other circuit breakers in the panel system. Fuses and circuit breakers shall be plainly marked or labeled to identify circuits or equipment supplied through them.

C. Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent. The Lessor shall provide duplex utility outlets in restrooms, corridors, and dispensing areas.

### **3.33 ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)**

If the government pays separately for electricity, no more than 500 sf of office space may be controlled by one switch or automatic light control for all office space on the government meter, whether through a building automation system, time clock, occupant sensor, or other comparable system acceptable to the LCO.

### **3.34 PLUMBING (JUN 2012)**

The Lessor shall include the cost of plumbing in common areas. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for TIs, shall be included in the shell rent.

### **3.35 DRINKING FOUNTAINS (WAREHOUSE) (MAY 2014)**

Lessor shall provide at least one chilled water fountain for the Premises. If more than one fountain is required by local building codes based on general warehouse use of the premises, they also shall be provided by Lessor as part of the shell rental. The fountains shall comply with Section F211 of the Architectural Barriers Act Accessibility Standard.

### **3.36 RESTROOMS (WAREHOUSE) (MAY 2014)**

A. For Warehouse Area, Lessor shall provide at its cost, restroom facilities which are handicap accessible, with an adequate number of fixtures for men and women to meet current local codes based on general warehousing use.

B. For Office Area within the Warehouse Building, if this Lease is satisfied by new construction or major alterations, Lessor shall provide water closets, sinks and urinals on each floor that is partially or fully occupied by the government per the following schedule. The schedule is per floor and based on a density of one person for each 7,500 NUSF, allocated as 50% women and 50% men. If major alterations to the restrooms occur during the term of this Lease, the number of fixtures then must meet the schedule as part of the major alterations.

ESTIMATED TOTAL NUMBER OF PEOPLE FLOOR			(WOMEN'S) WATER CLOSETS	(WOMEN'S) SINKS	(MEN'S) WATER CLOSETS	(MEN'S) URINALS	(MEN'S) SINKS
1	to	8	2	1	1	1	1
9	to	24	3	2	2	1	1
25	to	36	3	2	2	1	2
37	to	56	5	3	3	2	2
57	to	75	6	4	4	2	2
76	to	96	6	5	4	2	3
97	to	119	7	5	5	2	3
120	to	134	9	5	6	3	4
Above 135			3/40	1/24	1/20	1/40	1/30

C. If no new construction or major renovation of a restroom is occurring, compliance with local code is sufficient. Separate restroom facilities for men and women shall be provided in accordance with local code or ordinances, on each floor occupied by the Government in the Building. The facilities shall be located so that employees will not be required to travel more than 200 feet on one floor to reach the restrooms. Each restroom shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.

D. Each main restroom shall contain the following:

1. A mirror and shelf above the lavatory.
2. A toilet paper dispenser in each water closet stall that will hold at least two rolls and allow easy, unrestricted dispensing.
3. A coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories.
4. At least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories.
5. A coin-operated sanitary napkin dispenser in women's restrooms with a waste receptacle in each water closet stall.
6. A disposable toilet seat cover dispenser.
7. A counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground-fault interrupter-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
8. A floor drain.
9. For new installations and major renovations, restroom partitions shall be made from recovered materials as listed in EPA's CPG.
10. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour. The exhaust fan systems shall be provided with a 24/7 seven day clock to allow programming.

### 3.37 PLUMBING FIXTURES: WATER CONSERVATION (DEC 2011)

For new installations and whenever plumbing fixtures are being replaced (replacement per floor is required prior to Lease commencement in all instances of nonconformance where the Government occupies the full floor):

- A. Water closets must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized.
- B. Urinals must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized. Waterless urinals are acceptable.
- C. Faucets must conform to EPA WaterSense or fixtures with equivalent flow rates must be utilized.

Information on EPA WaterSense fixtures can be found at <http://www.epa.gov/watersense/>.

### 3.38 JANITOR CLOSETS (JUN 2012)

- A. Janitor closets with service sink, hot and cold water, and ample storage for cleaning equipment, materials, and supplies shall be provided on all floors. Each janitor closet door shall be fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch.
- B. When not addressed by local code, Lessor shall provide containment drains plumbed for appropriate disposal of liquid wastes in spaces where water and chemical concentrate mixing occurs for maintenance purposes. Disposal is not permitted in restrooms.

### 3.39 HEATING AND VENTILATION—SHELL (WAREHOUSE) (MAY 2014)

A. Warehouse areas: Temperature control for all warehouse areas shall be provided by ceiling mounted heating equipment capable of maintaining a minimum temperature of 55 degrees Fahrenheit (with all doors closed) throughout the warehouse area during the heating season regardless of the outside temperature. Unit heaters shall be controlled by individual thermostats mounted in the area of the unit heaters, or controlled from a central master time clock of the 7-day type with a separate manual override switch (12 hours) or other automatic means to permit setback of temperature at night and on weekends. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative. Central air rotation units will be acceptable if loading dock areas are equipped with unit heaters for direct heating over doors. In the warehouse area, unit heaters shall be mounted tight to the ceiling for maximum headroom. Lessor shall provide ventilation/air circulation in accordance with [the latest version of ASHRAE 62.1].

B. Office Areas: Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all Building common areas. The Lessor shall provide conditioned air through medium

pressure duct work at a rate of .75 cubic feet per minute per NUSF and systems shall be designed with sufficient systems capacity to meet all requirements in this Lease.

C. Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.

D. Equipment Performance. Temperature control for office Spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain Space temperature control over a range of internal load fluctuations of plus 0.5 W/SF to minus 1.5 W/SF from initial design requirements of the tenant.

E. Ductwork Re-use and Cleaning. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.

F. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE) Standard 62.1, Ventilation for Acceptable Indoor Air Quality.

G. Air filtration shall be provided and maintained with filters having a minimum efficiency rating as determined by the latest edition of ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size. Pre-filters shall have a Minimum Efficiency Reporting Value (MERV) efficiency of 8. Final filters shall have a MERV efficiency of 13.

H. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour.

I. Where the Lessor proposes that the Government shall pay utilities, the following shall apply:

1. An automatic air or water economizer cycle shall be provided to all air handling equipment, and
2. The Building shall have a fully functional building automation system capable of control, regulation, and monitoring of all environmental conditioning equipment. The building automation system shall be fully supported by a service and maintenance contract.

J. Warehouse and Office areas: HVAC systems must conform to the locally approved building code.

### **3.40 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)**

A. Sufficient space shall be provided on the floor(s) where the Government occupies Space for the purposes of terminating telecommunications service into the Building. The Building's telecommunications closets located on all floors shall be vertically-stacked. Telecommunications switch rooms, wire closets, and related spaces shall be enclosed. The enclosure shall not be used for storage or other purposes and shall have door(s) fitted with an automatic door-closer and deadlocking latch bolt with a minimum throw of 1/2 inch. The telephone closets shall include a telephone backboard.

B. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable Telecommunications Industry Association (TIA) and Electronic Industries Alliance (EIA) standards. These standards include the following:

1. TIA/EIA-568, Commercial Building Telecommunications Cabling Standard,
2. TIA/EIA 569, Commercial Building Standard for Telecommunications Pathways and Spaces,
3. TIA/EIA-570, Residential and Light Commercial Telecommunications Wiring Standard, and
4. TIA/EIA-607, Commercial Building Grounding and Bonding Requirements for Telecommunications Standard.

C. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable NFPA standards. Bonding and grounding shall be in accordance with NFPA Standard 70, National Electrical Code, and other applicable NFPA standards and/or local code requirements. All cabling shall be installed in accordance with the most recent edition of BICSI publications.

D. The telecommunications closet shall have an independent air conditioner and be able to maintain the room at 70 degrees.

E. Install cabling in accordance with the most recent edition of BICSI® publications:

- 1) BICSI -- Telecommunications Distribution Methods Manual
- 2) BICSI -- Installation Transport Systems Information Manual
- 3) BICSI -- Network Design Reference Design Manual
- 4) BICSI --Outside Plant Design Reference Manual
- 5) BICSI -- Wireless Design Reference Manual
- 6) BICSI - Electronic Safety and Security Design Reference Manual
- 7) Infocomm/BICSI -- AV Design Reference Manual

### **3.41 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)**

A. The Government may elect to contract its own telecommunications (voice, data, video, Internet or other emerging technologies) service in the Space. The Government may contract with one or more parties to have INS wiring (or other transmission medium) and telecommunications equipment installed.

B. The Lessor shall allow the Government's designated telecommunications provider's access to utilize existing Building wiring to connect its services to the Government's Space. If the existing Building wiring is insufficient to handle the transmission requirements of the Government's

designated telecommunications providers, the Lessor shall provide access from the point of entry into the Building to the Government's floor Space, subject to any inherent limitations in the pathway involved.

C. The Lessor shall allow the Government's designated telecommunications providers to affix telecommunications antennas (high frequency, mobile, microwave, satellite, or other emerging technologies), subject to weight and wind load conditions, to roof, parapet, or Building envelope as required. Access from the antennas to the Premises shall be provided.

D. The Lessor shall allow the Government's designated telecommunications providers to affix antennas and transmission devices throughout the Space and in appropriate common areas frequented by the Government's employees to allow the use of cellular telephones and communications devices necessary to conduct business.

### 3.42 LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (MAY 2014)

#### Warehouse/Storage Space & Overall:

A. Lessor shall provide a minimum lighting level of 10 foot-candles, as measured 30 inches above the floor, in aisles and open storage areas in the warehouse Space with the storage racks full. Lessor shall provide a minimum lighting level in the shipping and receiving areas of 30 foot-candles, when measured 30 inches above the floor. Lessor must provide lighting that is equivalent to the energy efficiency requirements in any office areas. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all non-office areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided as part of Shell Rent in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.

B. Occupancy Sensors: The Lessor shall provide ceiling mount occupancy sensors (over aisles and open areas), or scheduling controls through a building automation system (BAS) throughout the storage portion of the Space in order to reduce the hours that the lights are on when a particular area is unoccupied. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

#### B. Building Perimeter:

1. Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels, (especially at loading dock doors), shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 foot-candles for transition areas and at least 1 foot-candle throughout the parking lot. Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 10:1. Sodium vapor lighting fixtures are prohibited.
2. If the leased space is 100 percent occupied by Government tenants, all exterior parking lot fixtures shall be "Dark Sky" compliant with no property line trespass. See [HTTP://DARKSKYSOCIETY.ORG/HANDOUTS/LIGHTINGPLANGUIDELINES.PDF](http://DARKSKYSOCIETY.ORG/HANDOUTS/LIGHTINGPLANGUIDELINES.PDF)

C. Parking Structures: The minimum illuminance level for parking structures is 1 foot-candle as measured on the floor with a uniformity ratio of 10:1. Sodium vapor lighting fixtures are prohibited.

D. Parking Sensors: If the leased space is 100 percent occupied by Government tenants, exterior parking area and parking structure lighting shall be sensor or BAS controlled in order that it may be programmed to produce reduced lighting levels during non use. This non-use time period will normally be from 11:00 pm to 6:00 am.

E. Exterior Power Backup: Exterior egress, walkway, parking lot, and parking structure lighting must have emergency power backup to provide for safe evacuation of the Building.

### 3.43 ACOUSTICAL REQUIREMENTS (JUN 2012)

A. Reverberation Control. Private office and conference rooms using suspended acoustical ceilings shall have a noise reduction coefficient (NRC) of not less than 0.65 in accordance with ASTM C-423. Open office using suspended acoustical ceilings shall have a NRC of not less than 0.75. Private offices, conference rooms, and open offices using acoustical cloud or acoustical wall panels with a minimum of 70% coverage shall have a NRC of not less than 0.85.

B. Ambient Noise Control. Ambient noise from mechanical equipment shall not exceed noise criteria curve (NC) 35 in accordance with the ASHRAE Handbook of Fundamentals in offices and conference rooms; NC 40 in corridors, cafeterias, lobbies, and toilets; NC 50 in other spaces.

C. Noise Isolation. Rooms separated from adjacent spaces by ceiling high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

Conference rooms: NIC 40  
Offices: NIC 35

D. Testing. The LCO may require, at Lessor's expense, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.

### 3.44 INTENTIONALLY DELETED

### 3.45 INTENTIONALLY DELETED

### 3.46 INTENTIONALLY DELETED

### 3.47 INTENTIONALLY DELETED

**3.48 INDOOR AIR QUALITY DURING CONSTRUCTION (SEP 2013)**

A. The Lessor shall provide to the Government material safety data sheets (MSDS) or other appropriate documents upon request, but prior to installation or use for the following products, including but not limited to, adhesives, caulking, sealants, insulating materials, fireproofing or fire stopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finishes for wood surfaces, janitorial cleaning products, and pest control products.

B. The LCO may eliminate from consideration products with significant quantities of toxic, flammable, corrosive, or carcinogenic material and products with potential for harmful chemical emissions. Materials used often or in large quantities will receive the greatest amount of review.

C. All MSDS shall comply with Occupational Safety and Health Administration (OSHA) requirements. The Lessor and its agents shall comply with all recommended measures in the MSDS to protect the health and safety of personnel.

D. To the greatest extent possible, the Lessor shall sequence the installation of finish materials so that materials that are high emitters of volatile organic compounds (VOCs) are installed and allowed to cure before installing interior finish materials, especially soft materials that are woven, fibrous, or porous in nature, that may adsorb contaminants and release them over time.

E. Where demolition or construction work occurs adjacent to occupied Space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.

F. HVAC during Construction: If air handlers are used during construction, the Lessor shall provide filtration media with a MERV of 8 at each return air grill, as determined by the latest edition of ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size. The permanent HVAC system may be used to move both supply and return air during the construction process only if the following conditions are met:

1. A complete air filtration system with 60 percent efficiency filters is installed and properly maintained;
2. No permanent diffusers are used;
3. No plenum type return air system is employed;
4. The HVAC duct system is adequately sealed to prevent the spread of airborne particulate and other contaminants; and
5. Following the Building "flush out," all duct systems are vacuumed with portable high-efficiency particulate arrestance (HEPA) vacuums and documented clean in accordance with National Air Duct Cleaners Association (NADCA) specifications.

G. Flush-Out Procedure:

1. A final flush-out period of 72 hours minimum is required after installation of all interior finishes and before occupancy of the Space. The Lessor shall ventilate 24 hours a day, with new filtration media at 100% outdoor air (or maximum outdoor air while achieving a relative humidity not greater than 60%).
2. After the 3-day period the Space may be occupied; however, the flush-out must continue for 30 days using the maximum percentage of outdoor air consistent with achieving thermal comfort and humidity control.
3. Any deviation from this ventilation plan must be approved by the LCO.
4. The Lessor is required to provide regularly occupied areas of the Space with new air filtration media before occupancy that provides a MERV of 13 or better.
5. During construction, meet or exceed the recommended design approaches of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guideline for Occupied Buildings Under Construction, 1995, Chapter 3.
6. Protect stored onsite and installed absorptive materials from moisture damage.

**3.49 SYSTEMS COMMISSIONING (APR 2011)**

The Lessor shall incorporate commissioning requirements to verify that the installation and performance of energy consuming systems meet the Government's project requirements. The commissioning shall cover only work associated with TIs or alterations or at a minimum: heating, ventilating, air conditioning and refrigeration (HVAC&R) systems and associated controls, lighting controls, and domestic hot water systems.

**3.50 LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)**

A. Lessor shall provide a minimum of 1 loading dock(s) for the exclusive use of the Government. The dock configuration shall be straight.

B. Lessor shall equip each dock with two molded rubber bumpers (at least 6 inches by 12 inches by 14 inches) and heavy-duty bump blocks (the dock must be fully protected with edge guards and dock bumpers). Lessor shall equip each dock with exterior dock seals to prevent the exchange of air from indoors to outdoors and vice versa when the trailer docked for loading or unloading. The entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.

C. Dock-high doors shall be a minimum of 8' wide by 10' high and shall be approximately 48" above finished exterior grade unless otherwise specified in the Agency Special Requirements. Doors shall be insulated (R8 or better) with 2" angled, metal track and manual push-up. Door shall be spring loaded to assist opening and to safe return to the closed position. Weather-tight seals shall be provided around all 4 sides of the doors.

D. Drive-in doors shall be a minimum of 12' wide by 16' high unless otherwise specified in the Agency Special Requirements. The slope of the ramp shall not exceed 8.3% or by local code, whichever is more stringent. Doors shall be insulated (R8 or better) with 2" angled, metal track with chain hoist for opening and closing. Weather-tight seals shall be provided around all 4 sides of the doors.

E. Lessor shall equip each dock if exterior to the building, the entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Any open loading docks must be covered at least 1,200 mm (4 feet) beyond the edge of the loading dock platform over the loading berth. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.

F. Lessor shall provide sufficient ventilation to remove carbon monoxide even when doors and windows are shut. Ventilation air intakes must be at least 25 feet away from loading docks, garage entries, and similar carbon monoxide contamination points. Docks shall be separated by at least 50 feet in any direction from utility rooms, utility mains, and service entrances, including electrical, telephone/data, fire detection/alarm systems, fire suppression water mains, cooling and heating mains, etc. All regular and emergency fuel storage locations shall be located away from loading docks.

G. All dock wells shall be level throughout. Each dock shall have a roll-up, industrial steel warehouse & dock door with lock. The loading dock area shall be nearly flat with a 1:50 slope for drainage. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). When a steeper slope is required in the apron area, the headroom must increase with a gradient allowance to permit trucks to traverse the grade change. If the approach to the loading dock is ramped, the design must permit easy snow removal.

H. Lessor shall equip each loading dock with adjustable lights capable of illuminating the truck or van interior. Each dock shall have either a trailer lock or wheel chocks chained to the platforms. Where specified by Government on Exhibit A (Floor Plans), the Lessor shall provide a ramp from the loading dock down to the vehicle parking area to facilitate deliveries from small trucks and vans. This ramp must have a maximum 8.3% slope. Public and loading dock access must not be from the same point of access (at least one personnel door shall be provided in addition to overhead doors).

I. All docks shall provide shelter to people and materials in inclement weather. Operating controls for individual dock doors, dock levelers and lights shall be located on the interior wall adjacent to each dock door.

J. Service dock access may be from an alley, from a below grade ramp, or from a site circulation drive. Lessor shall provide sufficient space for an 85 foot truck to maneuver and service the facility, and also to screen the service drive as much as possible. At a minimum, Lessor shall provide a truck turning radius of 100 feet for all loading docks. The service drive must always be separated from access to the parking area. One-way design for service traffic is preferred in order to avoid the need for large turning areas. The service area of the facility must not interfere with public access roadways.

K. Lessor shall provide at least one off-street berth for loading and unloading. Loading berths must be located adjacent to the loading dock areas. Unless otherwise specified by local zoning regulations, a single berth must be a minimum of 4,600 mm (15 feet) wide and sized for the longest vehicle servicing the building as determined by Lessee. Additional loading berths do not need to be wider than 3,600 mm (12 feet) if they are contiguous with another loading berth. Lessor shall provide an apron space in front of the loading berth for vehicle maneuvering equal to the length of the berth plus 600 mm (2 feet). The apron must be relatively flat and have positive drainage with a minimum slope of 2%. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). If programming forces a steeper slope in the apron area, the headroom should increase with a gradient allowance to allow trucks to traverse the grade change.

L. Loading dock areas must be separated and visually screened (wherever practical) from the main public building entrance(s). Lessor shall provide an internal staging area adjacent to the loading dock. The staging area must not interfere with emergency egress from the building. Loading docks must have a direct route to freight elevators (if any) and be sized to accommodate the transport of supplies, equipment replacement parts, and building goods. If provided for, a dock manager's room must have visual control of the entire dock area as well as the building entrance and exit. Service circulation must be separated from public areas such as lobbies, corridors, and elevators. Loading dock stairs must be on the driver's left when backing into the dock. The grade of the apron must slope away from the loading dock and shall not exceed an 8.3% slope.

M. Trash rooms must be located adjacent to loading docks or service entrances. Trash rooms must be sized to accommodate the trash handling equipment required and provide storage for trash and recycling generated during a three day occupancy of the building. Space must be allowed for sorting and recycling of paper, bottles and cans, metals, and other materials. Facilities that use trash containers that are picked up by vendors must have at least one loading berth for the trash container.

### **3.51 EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)**

Emergency power backup is required for all alarm systems, CCTV monitoring devices, fire alarm systems, entry control devices, lighting, etc., and special equipment, as identified elsewhere within this Lease. Costs for emergency power to critical systems that are security requirements should be allocated to the BSAC cost component.

### **3.52 MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)**

Roof access shall meet the applicable egress requirements in the National Fire Protection Association (NFPA) 101, Life Safety Code or IBC (current as of the Award Date of this Lease).

### **3.53 DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)**

#### **A. Environmental Due Diligence**

Lessor is responsible for performing all necessary "response" actions (as that term is defined at 42 U.S.C. § 9601(25) of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA)) with regard to all "recognized environmental conditions," as that term is defined in ASTM Standard E1527-13, as such standard may be revised from time to time. This obligation extends to any contamination of the Property where such contamination is not attributable to the Government. Lessor must provide the Government with a summary report demonstrating completion of



all required response actions prior to Substantial Completion. Any remediation performed by or on behalf of Lessor must be undertaken in strict compliance with all applicable federal, state and local laws and regulations.

**B. National Environmental Policy Act**

The National Environmental Policy Act regulations provide for analyzing proposed major federal actions to determine if there are ways to mitigate the impact of the proposed actions to avoid, minimize, rectify, reduce, or compensate for environmental impacts associated with such actions. Where the Government has determined that any or all of these mitigation measures should be or must be adopted to lessen the impact of these proposed actions, Lessor must incorporate all mitigation measures identified and adopted by the Government in the design and construction drawings and specifications. All costs and expenses for development of design alternatives, mitigation measures and review submittals for work to be performed under the Lease are the sole responsibility of Lessor.

**3.54 NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS - LEASE (SEP 2014)**

A. Where a Memorandum of Agreement or other pre-award agreement concluding the Section 106 consultation includes mitigation, design review or other continuing responsibilities of the Government, Lessor must allow the Government access to the Property to carry out compliance activities. Compliance may require excavation for artifact recovery, recordation and interpretation. For Tenant Improvements and other tenant-driven alterations within an existing historic building, new construction or exterior alterations that could affect historic properties, compliance also may require on-going design review. In these instances, Lessor will be required to retain, at its sole cost and expense, the services of a preservation architect who meets or exceeds the *Secretary of the Interior's Professional Qualifications Standards for Historic Architecture*, as amended and annotated and previously published in the Code of Federal Regulations, 36 C.F.R. part 61, and the *GSA Qualifications Standards for Preservation Architects*. These standards are available at: [HTTP://WWW.GSA.GOV/HISTORICPRESERVATION](http://www.gsa.gov/historicpreservation)>Project Management Tools> Qualification Requirements for Preservation Architects. The preservation architect will be responsible for developing preservation design solutions and project documentation required for review by the Government, the State Historic Preservation Officer (SHPO), the Tribal Historic Preservation Officer (THPO), if applicable, and other consulting parties in accordance with Section 106. For Tenant Improvements and other tenant-driven alterations within an existing historic building, the preservation architect must develop context-sensitive design options consistent with the *Secretary of the Interior's Standards for the Treatment of Historic Properties*. Where new construction or exterior alterations, or both, are located within a historic district, may be visible from historic properties or may affect archeological resources, compliance may require tailoring the design of the improvements to be compatible with the surrounding area. Design review may require multiple revised submissions, depending on the complexity of the project and potential for adverse effects to historic properties. VA is responsible for corresponding with the SHPO, the THPO, if applicable, and any other consulting party.

B. Compliance requirements under Section 106 apply to all historic property alterations and new construction, regardless of the magnitude, complexity or cost of the proposed scope of work.

C. The costs for development of design alternatives and review submittals for work required under the Lease are the sole responsibility of Lessor. In addition, building shell costs relating to such design alternatives are the sole responsibility of Lessor and must be included in the shell rent. Such costs may be offset by federal, state or local preservation tax benefits. Lessor is encouraged to seek independent financial and legal advice concerning the availability of these tax benefits.

## SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES

### 4.01 SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (MAY 2014)

Design and construction activities for the Space shall commence upon Lease award. The Lessor shall schedule the following activities to achieve timely completion of the work required by this Lease:

A. DIDs. For the purposes of this Lease, DIDs are defined as fully dimensioned drawings of the leased Space that reflect all Lease requirements provided by the Government sufficient for the preparation of construction documents (CDs), including, but not limited to:

1. Generic furniture layout, wall, door, and built-in millwork locations;
2. Telephone, electrical, and data outlet types and locations;
3. Information necessary for calculation of electrical and HVAC loads;
4. Work related to security requirements; and
5. All finish selections.
6. Racking System Plan
7. The exits and fire department access doors in place or any proposed exits, aisles, and fire department access doors.

B. Lessor-Provided DIDs: The Lessor must submit to VA, as part of the shell cost, complete DIDs conforming to the requirements of this Lease and other Government-supplied information related to the tenant agency's interior build-out requirements not later than 20 Working Days following the Lease Award Date, provided that the Government supplies such information and direction as reasonably required for Lessor to timely complete DIDs. The Government (VA and the tenant agency) shall attend two meetings at the Lessor's request for the purpose of providing information and direction in the development of DIDs. The Lessor should anticipate at least two submissions of DIDs before receiving approval. At the sole discretion of the Government, the Lessor may be required to submit a budget proposal based on the TIs and associated work as shown on the DIDs. This budget proposal shall be completed within 5 Working Days of the Government's request.

C. Government review and approval of Lessor-provided DIDs: The Government must notify the Lessor of DID approval not later than 10 Working Days following submission of DIDs conforming to the requirements of this Lease as supplied by the Government. Should the DIDs not conform to these requirements, the Government must notify the Lessor of such non-conformances within the same period; however, the Lessor shall be responsible for any delay to approval of DIDs occasioned by such non-conformance. The Government's review and approval of the DIDs is limited to conformance to the specific requirements of the Lease as they apply to the Space.

D. The Lessor's preparation and submission of construction documents (CDs): The Lessor as part of the TI must complete CDs conforming to the approved DIDs not later than 10 Working Days following the approval of DIDs. The pricing for this work is included under the A/E fees established under Section 1 of the Lease. If during the preparation of CDs the Lessor becomes aware that any material requirement indicated in the approved DIDs cannot be reasonably achieved, the Lessor shall promptly notify VA, and shall not proceed with completion of CDs until direction is received from the LCO. The LCO shall provide direction within 10 Working Days of such notice, but the Government shall not be responsible for delays to completion of CDs occasioned by such circumstances. For the purpose of this paragraph, a "material requirement" shall mean any requirement necessary for the Government's intended use of the Space as provided for in, or reasonably inferable from, the Lease and the approved DIDs (e.g., number of workstations and required adjacencies).

E. Government review of CDs: The Government shall have 10 Working Days to review CDs before Lessor proceeds to prepare a TI price proposal for the work described in the CDs. At any time during this period of review, the Government shall have the right to require the Lessor to modify the CDs to enforce conformance to Lease requirements and the approved DIDs.

F. Construction of TIs and completion of other required construction work: The Lessor shall complete all work required to prepare the Premises as required in this Lease ready for use not later than 90 Working Days following issuance of NTP.

### 4.02 CONSTRUCTION DOCUMENTS (SEP 2012)

The Lessor's CDs shall include all mechanical, electrical, plumbing, fire protection, life safety, lighting, structural, security, and architectural improvements scheduled for inclusion into the Space. CDs shall be annotated with all applicable specifications. CDs shall also clearly identify TIs already in place and the work to be done by the Lessor or others. Notwithstanding the Government's review of the CDs, the Lessor is solely responsible and liable for their technical accuracy and compliance with all applicable Lease requirements.

### 4.03 TENANT IMPROVEMENTS PRICE PROPOSAL (SEP 2013)

The Lessor's TI price proposal shall be supported by sufficient cost or pricing data to enable the Government to evaluate the reasonableness of the proposal, or documentation that the Proposal is based upon competitive proposals (as described in the "Tenant Improvements Pricing Requirements" paragraph) obtained from entities not affiliated with the Lessor. Any work shown on the CDs that is required to be included in the Building shell rent or already priced as BSAC shall be clearly identified and excluded from the TI price proposal. After negotiation and acceptance of the TI price, VA shall issue a NTP to the Lessor.

### 4.04 INTENTIONALLY DELETED

### 4.05 TENANT IMPROVEMENTS PRICING REQUIREMENTS (SEP 2013)

A. Under the provisions of FAR Subpart 15.4, the Lessor shall submit a TI price proposal with information that is adequate for the Government to evaluate the reasonableness of the price or determining cost realism for the TIs within the time frame specified in this section. The TI price proposal shall use the fee rates specified in the "Tenant Improvement Fee Schedule" paragraph of this Lease. The Lessor shall exclude from the TI price proposal all costs for fixtures and/or other TIs already in place, provided the Government has accepted same. However, the Lessor will be reimbursed for costs to repair or improve the fixture(s) and/or any other improvements already in place. The Lessor must provide certified cost or pricing data for TI proposals exceeding the threshold in FAR 15.403-4, to establish a fair and reasonable price. For TI proposals that do not exceed the threshold in FAR 15-403-4, the Lessor shall submit adequate documentation to support the reasonableness of the price proposal as determined by the LCO.

B. The TIs scope of work includes the Lease, the DIDs, the CDs, and written specifications. In cases of discrepancies, the Lessor shall immediately notify the LCO for resolution. All differences will be resolved by the LCO in accordance with the terms and conditions of the Lease.

C. In lieu of requiring the submission of detailed cost or pricing data as described above, the Government (in accordance with FAR 15.403) is willing to negotiate a price based upon the results of a competitive proposal process. A minimum of two qualified General Contractors (GCs) shall be invited by the Lessor to participate in the competitive proposal process. Each participant shall compete independently in the process. In the absence of sufficient competition from the GCs, a minimum of two qualified subcontractors from each trade of the Tenant Improvement Cost Summary (TICS) Table (described below) shall be invited to participate in the competitive proposal process.

D. Each TI proposal shall be (1) submitted by the proposed General Contractors (or subcontractors) using the TICS Table in CSI MasterFormat; (2) reviewed by the Lessor prior to submission to the Government to ensure compliance with the scope of work (specified above) and the proper allocation of shell and TI costs; and (3) reviewed by the Government. General Contractors shall submit the supporting bids from the major subcontractors along with additional backup to the TICS Table in a format acceptable to the Government. Backup will follow the TICS table MasterFormat cost elements and be to level 5 as described in P-120, Project Estimating Requirements for the Public Buildings Service.

E. Unless specifically designated in this Lease as a TI or BSAC cost, all construction costs shall be deemed to be included in the Shell Rent. Any costs in the GC's proposal for Building shell items shall be clearly identified on the TICS Table separately from the TI costs.

F. The Government reserves the right to determine if bids meet the scope of work, that the price is reasonable, and that the Lessor's proposed contractors are qualified to perform the work. The Government reserves the right to reject all bids at its sole discretion. The Government reserves the right to attend or be represented at all negotiation sessions between the Lessor and potential contractors.

G. The Lessor shall demonstrate to the Government that best efforts have been made to obtain the most competitive prices possible, and the Lessor shall accept responsibility for all prices through direct contracts with all contractors. The LCO shall issue to the Lessor a NTP with the TIs upon the Government's sole determination that the Lessor's proposal is acceptable. The Lessor shall complete the work within the time frame specified in this section of the Lease.

#### **4.06 GREEN LEASE SUBMITTALS (JUN 2012)**

The Lessor shall submit to the LCO:

A. Product data sheets for floor coverings, paints and wall coverings, ceiling materials, all adhesives, wood products, suite and interior doors, subdividing partitions, wall base, door hardware finishes, window coverings, millwork substrate and millwork finishes, lighting and lighting controls, and insulation to be used within the leased Space. This information must be submitted NO LATER THAN the submission of the DIDs.

B. MSDS or other appropriate documents upon request for products listed in the Lease.

C. Re-use plan required in accordance with the "Existing Fit-out, Salvaged, or Re-used Building Material" paragraph in the Lease.

D. Any waiver needed when not using materials from the CPG and RMAN lists of acceptable products in accordance with the "Recycled Content Products" paragraph in the Lease.

E. Radon test results as may be required by the "Radon in Air" and "Radon in Water" paragraphs in the Lease.

F. Construction waste management plan: Prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the LCO, may permit alternative means of disposal.

G. Building recycling service plan: A Building recycling service plan with floor plans annotating recycling area(s) as part of DIDs to be reflected on the CD submission.

H. A signed statement from the Lessor for the leased Space explaining how all HVAC systems serving the leased Space will achieve the desired ventilation of the Space during the flush-out period called for in the Lease.

I. A written commissioning plan submitted to the LCO prior to the completion of DIDs that includes:

1. A schedule of systems commissioning (revised as needed during all construction phases of the project, with such revisions provided to the LCO immediately); and
2. A description of how commissioning requirements will be met and confirmed.

J. At completion of LEED®, documentation and receipt of final certification, along with two electronic copies of all supporting documentation for certification on compact disk.

K. If renewable source power is purchased, documentation within 9 months of occupancy.

#### **4.07 CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)**

The Lessor shall furnish a detailed construction schedule (such as Critical Path Method) to the Government within 10 Working Days of issuance of the NTP. Such schedule shall also indicate the dates available for Government contractors to install telephone/data lines or equipment, if needed. Within 10 Working Days of NTP, the Lessor shall initiate a construction meeting. The Lessor will have contractor representatives including its architects, engineers, general contractor and sub-contractor representatives in attendance. The Lessor shall keep meeting minutes of discussion topics and attendance.

#### **4.08 PROGRESS REPORTS (JUN 2012)**

After start of construction, the Lessor shall submit to the LCO written progress reports at intervals of 10 Working Days. Each report shall include information as to the percentage of the work completed by phase and trade; a statement as to expected completion and occupancy dates; changes introduced into the work; and general remarks on such items as material shortages, strikes, weather, etc., that may affect timely completion. In addition, at the Government's discretion, the Lessor shall conduct meetings every two weeks to brief Government personnel and/or contractors regarding the progress of design and construction of the Space. The Lessor shall be responsible for taking and distributing minutes of these meetings.

#### **4.09 ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)**

The Government shall have the right to access any space within the Building during construction for the purposes of performing inspections or installing Government furnished equipment. The Government shall coordinate the activity of Government contractors with the Lessor to minimize conflicts with and disruption to other contractors on site. Access shall not be unreasonably denied to authorized Government officials including, but not limited to, Government contractors, subcontractors, or consultants acting on behalf of the Government on this project.

#### **4.10 CONSTRUCTION INSPECTIONS (APR 2011)**

A. The LCO or the LCO's designated technical representative may periodically inspect construction work to review compliance with Lease requirements and approved DIDs.

B. Periodic reviews, witnessing of tests, and inspections by the Government shall not constitute approval of the Lessor's apparent progress toward meeting the Government's objectives but are intended to discover any information which the LCO may be able to call to the Lessor's attention to prevent costly misdirection of effort. The Lessor shall remain responsible for designing, constructing, operating, and maintaining the Building in full accordance with the requirements of the Lease.

#### **4.11 ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (MAY 2015)**

A. Ten (10) Working Days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of Building shell and TIs conforming to this Lease and the approved DIDs is substantially complete, a Certificate of Occupancy (C of O) has been issued as set forth below, and the Building improvements necessary for acceptance as described in the paragraph "Building Improvements" are completed.

B. The Space shall be considered substantially complete only if the Space may be used for its intended purpose, and completion of remaining work will not interfere unreasonably with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punch list generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.

C. The Lessor shall provide a valid C of O, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue C of O's or if the C of O is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease.

D. The Government will not be required to accept space prior to the schedule outlined in this Lease.

#### **4.12 LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)**

At acceptance, the Space shall be measured in accordance with the standards set forth in this Lease to determine the total NUSF in the Space. The rent for the Space will be adjusted based upon the measured ABOA square footage as outlined under the Payment clause of the General Clauses. At acceptance, the Lease term shall commence. The Lease Term Commencement Date, final measurement of the Premises, reconciliation of the annual rent, and amount of Commission Credit, if any, shall be memorialized by Lease Amendment.

#### **4.13 AS-BUILT DRAWINGS (JUN 2012)**

Not later than 10 days after the acceptance of the Space, the Lessor, at Lessor's expense, shall furnish to the Government a complete set of Computer Aided Design (CAD) files of as-built floor plans showing the Space under Lease, as well as corridors, stairways, and core areas. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD. The required file extension is ".DWG." Clean and purged files shall be submitted on CD-ROM. They shall be labeled with Building name, address, list of drawing(s), date of the drawing(s), and Lessor's architect and architect's phone number. The Lessor's operator shall demonstrate the submission on VA equipment, if requested by the LCO.

**4.14 LIQUIDATED DAMAGES (JUN 2012)**

In case of failure on the part of the Lessor to complete the work within the time fixed in the Lease, the Lessor shall pay the Government liquidated damages for each and every calendar day that the delivery is delayed beyond the date specified for delivery of all the Space ready for occupancy by the Government. This remedy is not exclusive and is in addition to any other remedies which may be available under this Lease or at law. This liquidated sum is not meant as a penalty, but as an approximation of actual damages that would be suffered by the Government because of the Lessor's delay.

**4.15 INTENTIONALLY DELETED****4.16 LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)**

A. The Lessor's project management fee shall cover all of the Lessor's project management costs associated with the delivery of Tenant Improvements, including, but not limited to:

1. Legal fees
2. Travel costs
3. Insurance
4. Home office overhead and other indirect costs
5. Carrying costs, exclusive of the TI amortization rate. Carrying costs are those costs of capital incurred for the delivery of TI, for the period starting from Lessor's outlay of funds, until the Lease Term Commencement Date.
6. Municipal, county, or state fees (not related to sales tax)
7. TI proposal preparation costs
8. Lessor's labor costs related to the management of the TI build-out.

B. At a minimum, the Lessor shall be responsible for performing the following services in order to receive the project management fee:

1. Provide assistance and expertise to the Government project team in the form of coordination, management, and administration of the design and construction process;
2. Monitor performance of the general contractor and other contractors, control schedules, and oversee financial accounts;
3. Conduct and document design and construction project meetings;
4. Perform administrative tasks, including documentation, record keeping (issuing meeting minutes), and payment validation in addition to submittal and change order processing;
5. Maintain Request for Information (RFI), submittal, and change order logs; and
6. Provide technical expertise (e.g. testing, estimating, resolving claims, or responding to inquiries).

---

## SECTION 5 TENANT IMPROVEMENT COMPONENTS

---

### 5.01 TENANT IMPROVEMENT REQUIREMENTS (MAY 2014)

The TIs shall be designed, constructed, and maintained in accordance with the standards set forth in this Lease. For pricing, only those requirements designated as TIs within this section, or designated as TIs within the attached agency requirements, shall be deemed to be TI costs.

### 5.02 FINISH SELECTIONS (JUN 2012)

The Lessor must consult with the Government prior to developing a minimum of three (3) finish options to include coordinated samples of finishes for all interior elements such as paint, wall coverings, base coving, carpet, window treatments, laminates, and flooring. All samples provided must comply with specifications set forth elsewhere in this Lease. All required finish option samples must be provided at no additional cost to the Government within 10 Working Days after initial submission of DIDs. VA must deliver necessary finish selections to the Lessor within 10 Working Days after receipt of samples. The finish options must be approved by VA prior to installation. The Lessor may not make any substitutions after the finish option is selected.

### 5.03 WINDOW COVERINGS (WAREHOUSE) (JUN 2012)

A. Window Blinds. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the TIs. The blinds may be aluminum or plastic vertical blinds, horizontal blinds with aluminum slats of one-inch width or less, solar fabric roller shades, or an equivalent product pre-approved by the Government. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Government.

### 5.04 DOORS: SUITE ENTRY (SEP 2013)

Suite entry doors shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Government. Hollow core wood doors are not acceptable. They shall be operable by a single effort; and shall meet the requirement of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semigloss oil-based paint finish with no formaldehyde.

### 5.05 DOORS: INTERIOR (SEP 2013)

Doors within the Space shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 80" high. Doors shall be flush, solid core, wood with a natural wood veneer face or an equivalent door pre-approved by the LCO. Hollow core wood doors are not acceptable. They shall be operable with a single effort, and shall meet the requirements of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint with no formaldehyde.

### 5.06 DOORS: HARDWARE (SEP 2013)

Doors shall have door handles or door pulls with heavyweight hinges. The Lessor is encouraged to avoid the use of chrome-plated hardware. All doors shall have corresponding doorstops (wall- or floor-mounted) and silencers. All door entrances leading into the Space from public corridors and exterior doors shall have automatic door closers. Doors designated by the Government shall be equipped with 5-pin, tumbler cylinder locks and strike plates. All locks shall be master keyed. Furnish at least two master keys for each lock to the Government. Any exterior entrance shall have a high security lock, with appropriate key control procedures, as determined by Government specifications. Hinge pins and hasps shall be secured against unauthorized removal by using spot welds or pinned mounting bolts. The exterior side of the door shall have a lock guard or astragal to prevent tampering of the latch hardware. Doors used for egress only shall not have any operable exterior hardware. All security-locking arrangements on doors used for egress shall comply with requirements of NFPA 101 or the International Building Code current as of the Lease Award Date.

### 5.07 DOORS: IDENTIFICATION (JUN 2012)

Door identification shall be installed in approved locations adjacent to office entrances as part of the TIs. The form of door identification shall be approved by the Government.

### 5.08 PARTITIONS: SUBDIVIDING (SEP 2015)

A. Office subdividing partitions shall comply with applicable building codes and local requirements and ordinances and shall be provided as part of the TIs. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a minimum sound transmission class (STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the DIDs. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84).

B. HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.

C. If installed in accordance with the "Automatic Fire Sprinkler System" and "Fire Alarm System" paragraphs, sprinklers and fire alarm notification appliances shall be repositioned as appropriate after installation of partitions to maintain the level of fire protection and life safety.

D. Partitioning requirements may be satisfied with existing partitions if they meet the Government's standards and layout requirements.

- E. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

#### 5.09 CEILINGS—TI (WAREHOUSE) (APR 2015)

Government designated office and related areas shall contain a complete acoustical ceiling system (such a ceiling system include grid and lay-in tiles or other Building standard ceiling system as approved by the LCO).

A. Ceilings in office and related areas shall be at a minimum 9 feet and 0 inches and no more than 12 feet and 0 inches measured from floor to the lowest obstruction. Areas with raised flooring shall maintain these ceiling-height limitations above the finished raised flooring. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the Space, with no obvious damage to tiles or grid.

B. Prior to closing the ceiling, Lessor shall coordinate with the Government for the installation of any items above the ceiling.

C. Should the ceiling be installed in the Space prior to construction of the TI, then Lessor shall be responsible for all costs for the disassembly, storage during construction, and subsequent re-assembly of ceiling components which may be required to complete the TI. Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the construction of the TI.

D. Ceilings shall be a flat plane in each room and shall be suspended and finished as follows unless an alternate equivalent is pre-approved by the LCO:

1. Restrooms. Plastered or spackled and taped gypsum board.
2. Offices and conference rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the LCO. Tiles or panels shall contain recycled content.
3. Corridors and eating/galley areas. Plastered or spackled and taped gypsum board or mineral acoustical tile.

E. For ceiling installations in new lease construction projects, tiles or panels (for restrooms, offices, conference rooms, corridors, and eating/gallery areas) must comply with the following environmental standards: a) California Section 01350 standard for low-VOC materials; b) recyclable in a closed loop process; c) USDA Certified Biopreferred; and d) Environmental Product Declaration (EPD) available.

#### 5.10 WALL FINISHES (JUN 2012)

If the Government chooses to install a wall covering, the minimum standard is vinyl-free, chlorine-free, plasticizer-free wall covering with recycled content or bio-based commercial wall covering weighing not less than 13 ounces per square yard or equivalent. If the Government chooses to install a high-performance paint coating, it shall comply with the VOC limits of the Green Seal Standard GS-11.

Op

#### 5.11 PAINTING—TI (WAREHOUSE) (MAY 2014)

A. Prior to acceptance, all surfaces within the Space which are designated by VA for painting shall be newly finished in colors acceptable to the Government.

B. The Lessor shall provide interior paints and coatings that meet or are equivalent to the following standards for VOC off gassing:

1. Topcoat paints: Green Seal Standard GS-11, Paints, First Edition, May 20, 1993.
2. All other architectural coatings, primers, and undercoats: South Coast Air Quality Management District (SCAQMD) Rule 1113, Architectural Coatings, effective January 1, 2004.
3. Architectural paints, coatings, and primers applied to interior walls and ceilings:
  - a. Flats: 50 grams per liter (g/L).
  - b. Non-flats: 150 g/L.
4. Anti-corrosive and anti-rust paints applied to interior ferrous metal substrates: 250 g/L.
5. Clear wood finishes:
  - a. Varnish: 350 g/L.
  - b. Lacquer: 550 g/L.
6. Floor coatings: 100 g/L.
7. Sealers:
  - a. Waterproofing sealers: 250 g/L.
  - b. Sanding sealers: 275 g/L.
  - c. All other sealers: 200 g/L.
8. Shellacs:
  - a. Clear: 730 g/L.
  - b. Pigmented: 550 g/L.
9. Stains: 250 g/L.

C. Use reprocessed latex paint in accordance with EPA's CPG (Comprehensive Procurement Guidelines) on all painted surfaces where feasible. The type of paint shall be acceptable to the Government.

**5.12 FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (APR 2015)**

A. Broadloom carpet or carpet tiles meeting the requirements set forth in the specifications below shall be installed in all office areas. Office area floor perimeters at partitions shall have wood, rubber, vinyl, or carpet base. Floor covering shall be installed in accordance with manufacturing instructions to lay smoothly and evenly.

B. The use of existing carpet may be approved by the Government; however, existing carpet shall be repaired, stretched, and cleaned before occupancy and shall meet the static buildup requirement as stated in the specifications below.

C. Any alternate flooring shall be pre-approved by the Government.

**D. SPECIFICATIONS FOR CARPET TO BE NEWLY INSTALLED OR REPLACED**

1. Product sustainability and environmental requirements. In order to achieve superior performance in multiple environmental attribute areas, carpet must have third party certification in accordance with ANSI/NSF 140 2007e Sustainable Carpet Assessment Standard at a "Gold" level minimum. Carpet manufacturer must supply certificate as part of the procurement documentation.
2. Recycled content: Recycled content is measured by total product weight of pre-consumer and/or post-consumer materials. Recycled content must be at least 10% post-consumer recovered content.
3. Low emitting materials. The carpet and floor adhesive (for glue-down installations) must meet the Green Label Plus (GLP) and floor adhesive (for direct glue down) requirements of the Carpet and Rug Institute (CRI). GLP number must be provided. Adhesives must meet VOC content standards per South Coast Air Quality Management District Rule #1168.
4. Face fiber content. Face yarn must be 100 percent nylon fiber. Loop Pile shall be 100 percent Bulk Continuous Filament (BCF); cut and loop shall be 100 percent BCF for the loop portion and may be BCF or staple for the cut portion; cut pile carpet shall be staple or BCF.
5. Performance requirements for broadloom and modular tile:
  - a. Static: Less than or equal to 3.5 kV when tested by AATCC Test Method 134 (Step Test Option).
  - b. Flammability: Meets CPSC-FF-1-70, DOC-FF-1-70 Methenamine Tablet Test criteria.
  - c. Flooring Radiant Panel Test: Meets NFPA 253 Class I or II depending upon occupancy and fire code when tested under ASTM E-648 for glue down installation.
  - d. Smoke Density: NBS Smoke Chamber—Less than 450 Flaming Mode when tested under ASTM E-662.

**NOTE:** Testing must be performed in a NVLAP accredited laboratory.

6. Texture Appearance Retention Rating (TARR). Carpet must meet TARR ratings specified below:

Space Definition	Traffic Classification	TARR Classification
Private Offices	Moderate	≥ 3.0 TARR
Training, conference, courtrooms, etc.	Heavy	≥ 3.0 TARR
Open Office, cafeteria, corridors, lobbies	Severe	≥ 3.5 TARR

The carpet must be evaluated using ASTM D-5252 Hexapod Drum Test as per the commercial carpet test procedure and the TARR classification determined using ASTM D-7330.

7. Carpet reclamation. Reclamation of existing carpet to be determined with potential vendor. When carpet is replaced, submit certification documentation from the reclamation facility to the LCO.
8. Warranty. Submit a copy of the manufacturer's standard warranty to the LCO within the first 60 days of Government occupancy. The Government is to be a beneficiary of the terms of this warranty.

**5.13 HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)**

Zone Control. Provide individual thermostat control for office Space with control areas not to exceed 1,500 NUSF. Interior spaces must be separately zoned. Specialty occupancies (conference rooms, kitchens, etc.) must have active controls capable of sensing Space use and modulating HVAC system in response to Space demand. Areas that routinely have extended hours of operation shall be environmentally controlled through dedicated heating and air conditioning equipment. Special purpose areas (such as photocopy centers, large conference rooms, computer rooms, etc.) with an internal cooling load in excess of 5 tons shall be independently controlled. Provide concealed package air conditioning equipment to meet localized spot cooling of tenant special equipment. Portable space heaters are prohibited.

**5.14 ELECTRICAL: DISTRIBUTION—TI (WAREHOUSE) (MAY 2014)**

A. All electrical, telephone, and data outlets within the Space shall be installed by the Lessor in accordance with the DIDs. All electrical outlets shall be installed in accordance with NFPA Standard 70.



B. All outlets within the Space shall be marked and coded for ease of wire tracing; outlets shall be circuited separately from lighting. All floor outlets shall be flush with the plane of the finished floor. Outlet cover colors shall be coordinated with partition finish selections.

C. The Lessor shall in all cases safely conceal outlets and associated wiring (for electricity, voice, and data) to the workstation(s) in partitions, ceiling plenums, in recessed floor ducts, under raised flooring, or by use of a method acceptable to the Government.

#### **5.15 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)**

Telecommunications floor or wall outlets shall be provided as part of the TIs. At a minimum, each outlet shall house one 4-pair wire jack for voice and one 4-pair wire jack for data. The Lessor shall ensure that all outlets and associated wiring, copper, coaxial cable, optical fiber, or other transmission medium used to transmit telecommunications (voice, data, video, Internet, or other emerging technologies) service to the workstation shall be safely concealed under raised floors, in floor ducts, walls, columns, or molding. All outlets/junction boxes shall be provided with rings and pull strings to facilitate the installation of cable. Some transmission medium may require special conduit, inner duct, or shielding as specified by the Government.

#### **5.16 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)**

Provide sealed conduit to house the agency telecommunications system when required.

#### **5.17 DATA DISTRIBUTION (JUN 2012)**

The Government shall be responsible for the cost of purchasing and installing data cable. The Lessor shall safely conceal data outlets and the associated wiring used to transmit data to workstations in floor ducts, walls, columns, or below access flooring. The Lessor shall provide as part of the TI, outlets with rings and pull strings to facilitate the installation of the data cable. When cable consists of multiple runs, the Lessor shall provide ladder type or other acceptable cable trays to prevent Government-provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Space such that they are within a 30-foot horizontal distance of any single drop.

#### **5.18 ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)**

A. The Lessor shall provide as part of the TIs separate data, telephone, and electric junction boxes for the base feed connections to Government provided modular or systems furniture, when such feeds are supplied via wall outlets or floor penetrations. When overhead feeds are used, junction boxes shall be installed for electrical connections. Raceways shall be provided throughout the furniture panels to distribute the electrical, telephone, and data cable. The Lessor shall provide all electrical service wiring and connections to the furniture at designated junction points. Each electrical junction shall contain an 8-wire feed consisting of 3 general purpose 120-V circuits with 1 neutral and 1 ground wire, and a 120-V isolated ground circuit with 1 neutral and 1 isolated ground wire. A 20-ampere circuit shall have no more than 8 general purpose receptacles or 4 isolated ground "computer" receptacles.

B. The Government shall be responsible for the cost of purchasing data and telecommunications cable. Said cable shall be installed and connected to systems furniture by the Lessor/contractor with the assistance and/or advice of the Government or computer vendor. The Lessor shall provide wall mounted data and telephone junction boxes, which shall include rings and pull strings to facilitate the installation of the data and telecommunications cable. When cable consists of multiple runs, the Lessor shall provide ladder-type or other acceptable cable trays to prevent Government provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Space such that they are within a 30-foot horizontal distance of any single drop. Said cable trays shall provide access to both telecommunications data closets and telephone closets.

C. The Lessor shall furnish and install suitably sized junction boxes near the "feeding points" of the furniture panels. All "feeding points" shall be shown on Government approved design intent drawings. The Lessor shall temporarily cap off the wiring in the junction boxes until the furniture is installed. The Lessor shall make all connections in the power panel and shall keep the circuit breakers off. The Lessor shall identify each circuit with the breaker number and shall identify the computer hardware to be connected to it. The Lessor shall identify each breaker at the panel and identify the devices that it serves.

D. The Lessor's electrical contractor must connect power poles or base feeds in the junction boxes to the furniture electrical system and test all pre-wired receptacles in the systems furniture. Other Government contractors will be installing the data cable in the furniture panels for the terminal and printer locations, installing the connectors on the terminal/printer ends of the cable, and continuity testing each cable. Work shall be coordinated and performed in conjunction with the furniture, telephone, and data cable installers. Much of this work may occur over a weekend on a schedule that requires flexibility and on-call visits. The Lessor must coordinate the application of Certification of Occupancy with furniture installation.

#### **5.19 LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)**

##### WAREHOUSE AREAS:

A. **FIXTURES:** Once the design intent drawings are approved, the Lessor shall design and provide interior lighting to comply with requirements under the paragraph, "Lighting: Interior and Parking—Shell." Any additional lighting fixtures and/or components required beyond what would have been provided for an open warehouse 10 foot candle plan plus shipping & receiving areas of 30 foot candles (Shell) are part of the TIs.

B. Lighting for the warehouse, shipping, and receiving portions of the Space is detailed in Section 3 and is part of Shell.

C. **BUILDING PERIMETER:** There may be additional requirements for lighting in exterior parking areas, vehicle driveways, pedestrian walkways, and Building perimeter in the Security Requirements attached to this Lease. Such additional lighting required to meet Security Requirements shall be BSAC.

OFFICE AREAS:

NOTE: FOR PRICING ESTIMATING PURPOSES, FIXTURES IN OFFICE AREAS WILL BE INSTALLED AT THE AVERAGE RATIO OF 1 FIXTURE PER 80 NUSF.

A. FIXTURES: High efficiency T-8, T-5, or LED light fixtures (and associated ballasts or drivers) shall be installed as either ceiling grid or pendant mounted for an open-office plan. Ceiling grid fixtures shall be either 2' wide by 4' long or 2' wide by 2' long. Lessor shall provide a minimum overall lighting fixture efficiency of 85 percent. Lamps shall maintain a uniform color level throughout the lease term.

B. LIGHTING LEVELS: Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1.

C. POWER DENSITY:

Existing Buildings: The maximum fixture power density shall not exceed 1.4 watts per NUSF.

New Construction: The maximum fixture power density shall not exceed 1.1 watts per NUSF.

D. DAYLIGHTING CONTROLS: If the office portion of the Space is more than 10,000 NUSF, the Lessor shall provide daylight dimming controls in atriums or within 15 feet of windows and skylights where daylight can contribute to energy savings. Daylight harvesting sensing and controls shall be either integral to the fixtures or ceiling mounted and shall maintain required lighting levels in office work areas.

E. OCCUPANCY/VACANCY SENSORS: The Lessor shall provide ceiling mount occupancy sensors, or vacancy sensors (preferred), or scheduling controls through a building automation system (BAS) throughout the office portion of the Space in order to reduce the hours that the lights are on when a particular space is unoccupied. Occupancy sensors only shall be installed in the non-office areas of the Space as part of Shell Rent. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

**5.20 LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)**

The Government will require hydraulic dock levelers or loading ramps for any warehouse dock (other than drive thrus) not already having dock high loading docks.

---

## SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM

---

### 6.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)

A. The Government's normal hours of operations are established as 6 AM to 6 PM, Monday through Friday, with the exception of Federal holidays. Services, maintenance, and utilities shall be provided during these hours. The Government shall have access to the Premises and its Appurtenant Areas at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, restrooms, lights, and electric power.

B. The Lessor and the Lessor's representatives, employees and contractors shall demonstrate a cooperative, positive, welcoming, respectful, professional and business-like demeanor and shall present a neat, clean, job-appropriate (professional) appearance.

### 6.02 UTILITIES (APR 2011)

The Lessor is responsible for providing all utilities necessary for base Building and tenant operations as part of the rental consideration.

### 6.03 UTILITY CONSUMPTION REPORTING (SEP 2015)

Upon the effective date of the Lease, only for leases over 10,000 RSF, the Lessor shall provide regular quarterly reports for the amount of utilities (including water) consumed at the Building broken down by utility type per month for the duration of the Lease. Lessors shall report this utility consumption data within 45 calendar days of the end of each calendar quarter. Data reported includes, but is not limited to, the number of actual units consumed, by utility type per month, and associated start and end date(s) for that consumption.

(Refer to the following link for reporting guidance: [www.gsa.gov/ucf](http://www.gsa.gov/ucf))

### 6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (SEP 2014)

A. In all office areas, temperatures shall conform to local commercial equivalent temperature levels and operating practices in order to maximize tenant satisfaction. These temperatures shall be maintained throughout the leased Premises and service areas, regardless of outside temperatures, during the hours of operation specified in the Lease. The Lessor shall perform any necessary systems start-up required to meet the commercially equivalent temperature levels prior to the first hour of each day's operation. At all times, humidity shall be maintained below 60% relative humidity.

B. In all office areas, during non working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not be provided except as necessary to return Space temperatures to a suitable level for the beginning of working hours. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative.

C. In all office areas, thermal comfort. During all working hours, comply with the latest edition of ASHRAE Standard 55, Thermal Comfort Conditions for Human Occupancy.

D. Warehouse or garage areas require heating and ventilation only. Cooling of this Space is not required. Temperature of warehouse or garage areas shall be maintained at a minimum of 50° Fahrenheit.

E. The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the Lease and shall make a reasonable attempt to schedule major construction outside of office hours.

F. Normal HVAC systems' maintenance shall not disrupt tenant operations.

G. 14,000 NUSF of the Premises shall receive cooling at all times (24 hrs a day, 365 days a year) for purposes of cooling the designated server room. The peak BTU output of this room is established as 238,000 BTU per hour. The temperature of this room shall be maintained at 67-78 degrees F, with humidity control not to exceed 60% relative humidity, regardless of outside temperature or seasonal changes. Notwithstanding the foregoing, Lessor shall provide this service at no additional cost to the Government if the Lessor provides this service to other tenants in the Building at no additional charge.

### 6.05 OVERTIME HVAC USAGE (JUN 2012)

A. If there is to be a charge for heating or cooling outside of the Building's normal hours, such services shall be provided at the hourly rates set forth elsewhere in the Lease. Overtime usage services may be ordered by the Government's authorized representative only.

B. When the cost of service is \$3,000 or less, the service may be ordered orally. An invoice shall be submitted to the official placing the order for certification and payment. Orders for services costing more than \$3,000 shall be placed using GSA Form 300, Order for Supplies or Services, or other approved service requisition procurement document. An invoice conforming to the requirements of this Lease shall be submitted to the official placing the order for certification and payment.

C. Failure to submit a proper invoice within 120 days of providing overtime utilities shall constitute a waiver of the Lessor's right to receive any payment for such overtime utilities pursuant to this Lease.

**6.06 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)**

The Lessor shall maintain the office area and common area of the Premises in a clean condition and shall provide supplies and equipment for these areas for the term of the Lease. The following schedule describes the level of services intended. Performance will be based on the LCO's evaluation of results, not the frequency or method of performance.

- A. Daily. Empty trash receptacles. Sweep entrances, lobbies, and corridors. Spot sweep floors, and spot vacuum carpets. Clean drinking fountains. Sweep and damp mop or scrub restrooms. Clean all restroom fixtures, and replenish restroom supplies. Dispose of all trash and garbage generated in or about the Building. Wash inside and out or steam clean cans used for collection of food remnants from snack bars and vending machines. Dust horizontal surfaces that are readily available and visibly require dusting. Spray buff resilient floors in main corridors, entrances, and lobbies. Clean elevators and escalators. Remove carpet stains. Police sidewalks, parking areas, and driveways. Sweep loading dock areas and platforms. Clean glass entry doors to the Space.
- B. Three times a week. Sweep or vacuum stairs.
- C. Weekly. Damp mop and spray buff all resilient floors in restrooms and health units. Sweep sidewalks, parking areas, and driveways (weather permitting).
- D. Every two weeks. Spray buff resilient floors in secondary corridors, entrance, and lobbies. Damp mop and spray buff hard and resilient floors in office Space.
- E. Monthly. Thoroughly dust furniture. Completely sweep and/or vacuum carpets. Sweep storage Space. Spot clean all wall surfaces within 70 inches of the floor.
- F. Every two months. Damp wipe restroom wastepaper receptacles, stall partitions, doors, window sills, and frames. Shampoo entrance and elevator carpets.
- G. Three times a year. Dust wall surfaces within 70 inches of the floor, vertical surfaces and under surfaces. Clean metal and marble surfaces in lobbies. Wet mop or scrub garages.
- H. Twice a year. Wash all interior and exterior windows and other glass surfaces. Strip and apply four coats of finish to resilient floors in restrooms. Strip and refinish main corridors and other heavy traffic areas.
- I. Annually. Wash all venetian blinds, and dust 6 months from washing. Vacuum or dust all surfaces in the Building more than 70 inches from the floor, including light fixtures. Vacuum all draperies in place. Strip and refinish floors in offices and secondary lobbies and corridors. Shampoo carpets in corridors and lobbies. Clean balconies, ledges, courts, areaways, and flat roofs.
- J. Every two years. Shampoo carpets in all offices and other non-public areas.
- K. Every five years. Dry clean or wash (as appropriate) all draperies.
- L. As required. Properly maintain plants and lawns. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Provide and empty exterior ash cans and clean area of any discarded cigarette butts.
- M. Pest control. Control pests as appropriate, using Integrated Pest Management techniques, as specified in the VA Environmental Management Integrated Pest Management Technique Guide (E402-1001).

**6.06 SELECTION OF CLEANING PRODUCTS (APR 2015)**

The Lessor shall use cleaning products (including general purpose cleaners, floor cleaners, hand soap, etc.) that comply with either the Green Seal standard, the UL/EcoLogo standard, EPA's Design for the Environment (DfE) designation, or a substitute acceptable to the LCO. Hand soap products shall also be USDA Certified BioPreferred.

**6.07 SELECTION OF PAPER PRODUCTS (APR 2015)**

The Lessor shall select paper and paper products (e.g., restroom tissue and paper towels) conforming to the Green Seal Standard (GS-1), or a substitute acceptable to the LCO.

**6.08 SNOW REMOVAL (WAREHOUSE) (MAY 2014)**

Lessor shall provide snow removal services for the Government on all days for which this Lease has designated normal hours. Lessor shall clear parking lots if the accumulation of snow exceeds two inches. Lessor shall clear sidewalks, walkways, loading docks, dock ramps, and entrances before accumulation exceeds 1.5 inches. The snow removal shall take place no later than 5:00 AM, without exception. Should accumulation continue throughout the day, the Lessor shall provide such additional snow removal services to prevent accumulation greater than the maximums specified in this paragraph. In addition to snow removal, the Lessor shall keep sidewalks, walkways, loading docks, dock ramps, and entrances free of ice during the normal hours. The Lessor shall remove excess buildup of sand and/or ice melt to minimize slipping hazards. If the Building entrance(s) has a northern exposure, then Lessor shall take additional measures to protect the safety of pedestrians.

**6.09 MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)**

A. The Lessor is responsible for the total maintenance, repair and replacement of the leased Premises, the Building, and the Property. Such maintenance, repairs and replacements include the site and private access roads, and all necessary repairs and replacements to the loading docks, ramps, levelers and all other associated equipment and features. All equipment and systems shall be maintained, repaired, and replaced to provide reliable, energy efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance responsibility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with current applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the Government's designated representative.

B. At the Lessor's expense, the Government reserves the right to require documentation of proper operations or testing inspection, testing, and maintenance of fire protection systems, such as fire alarm, fire sprinkler, standpipes, fire pump, emergency lighting, illuminated exit signs, emergency generator, prior to occupancy to ensure proper operation. These tests shall be witnessed by the Government's designated representative.

#### **6.10 MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (MAY 2014)**

A. Paint, wall coverings. Lessor shall maintain all wall coverings and high performance paint coatings in "like new" condition for the life of the Lease. All painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if the paint is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this Lease. In addition to the foregoing requirement,

1. Lessor shall repaint common areas at least every three years.
2. Lessor shall perform cyclical repainting of the Space every **X** years of occupancy. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.
3. If the warehouse portion of the Space was painted originally, Lessor shall perform cyclical repainting of the warehouse portion at the same cycle as the office and related space. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.

B. Carpet and flooring.

1. Except when damaged by the Government, the Lessor shall repair or replace flooring at any time during the Lease term when:
  - a. Backing or underlayment is exposed;
  - b. There are noticeable variations in surface color or texture;
  - c. It has curls, upturned edges, or other noticeable variations in texture;
  - d. Tiles are loose; or,
  - e. Tears or tripping hazards are present.
2. Notwithstanding the foregoing, as part of the rental consideration, the Lessor shall replace all carpet in the Space every **X** years, with a product which meets the requirements in the "Floor Coverings and Perimeters" paragraph in this Lease.
3. Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture per manufacturer's warranty, if necessary. Work shall be performed after the normal hours established elsewhere in this Lease.
4. Except when damaged by the Government, Lessor shall reseal flooring in warehouse areas whenever there are noticeable variations in surface color or texture.

#### **6.11 ASBESTOS ABATEMENT (APR 2011)**

If asbestos abatement work is to be performed in the Space after occupancy, the Lessor shall submit to the Government the occupant safety plan and a description of the methods of abatement and re-occupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

#### **6.12 ONSITE LESSOR MANAGEMENT (APR 2011)**

The Lessor shall provide an onsite Building superintendent or a locally designated representative available to promptly respond to deficiencies, and immediately address all emergency situations.

#### **6.13 IDENTITY VERIFICATION OF PERSONNEL (MAY 2014)**

A. The Government reserves the right to verify identities of personnel with routine pre-occupancy and/or unaccompanied access to Government space. The Lessor shall comply with the agency personal identity verification procedures below that implement [Homeland Security Presidential Directive-12](#) (HSPD-12), Office of Management and Budget (OMB) guidance [M-05-24](#), and Federal Information Processing Standards Publication (FIPS PUB) Number 201, as amended.

B. The Government reserves the right to conduct background checks on Lessor personnel and contractors with routine access to Government leased space.

C. Upon request, the Lessor will notify the Government whether they will use either the manual process and submit completed fingerprint charts and background investigation forms, or use the electronic process of ID verification, completed through the e-QIP system. This would be done for each employee of the Lessor, as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased space for a period greater than 6 months. The Government may also require this information for the Lessor's employees, contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's space.

1. **MANUAL PROCESS:** The Lessor shall provide Form FD 258, Fingerprint Chart (available from the Government Printing Office at <http://bookstore.gpo.gov>), and Standard Form 85P, Questionnaire for Public Trust Positions, completed by each person and returned to the Lease Contracting Officer (or the contracting officer's designated representative) within 30 days from receipt of the forms.
2. **ELECTRONIC PROCESS:** The electronic process will be done through the e-QIP system. The Lessor's contractor/personnel will receive an email along with instructions for completing the Office of Personnel Electronic Questionnaire (e-QIP). The contractor/personnel will have up to (7) seven business days to login and complete the e-QIP for the background investigation. The contractor/personnel will be instructed to access the website, and receive on screen instructions which include but it is not limited to:
  - a) How to Log In
  - b) How to Answer and Create New Golden Questions
  - c) What Additional Documents to Send
  - d) To Print and Sign two Signature Forms (Certification That My Answers Are True)
  - e) To complete the submission process, press the "Release /Request Transmit to the Agency" and exit the process
  - f) Where to Send.

The Lessor must ensure prompt input, and timely receipt of the following, from their contractor/personnel:

- a) Two FBI Fingerprint Cards (Form FD-258) or one card produced by a livescan device,
- b) Certification That My Answers Are True
- c) Authorization for Release of Information.

D. The Lessor must ensure the contracting officer (or the contracting officer's designated representative) has all of the requested documentation to ensure the completion of the investigation.

E. Based on the information furnished, the Government will conduct background investigations of the employees. The contracting officer will advise the Lessor in writing if an employee fails the investigation, and, effective immediately, the employee will no longer be allowed to work or be assigned to work in the Government's space.

F. Throughout the life of the lease, the Lessor shall provide the same data for any new employees, contractors, or subcontractors who will be assigned to the Government's space. In the event the Lessor's contractor or subcontractor is subsequently replaced, the new contractor or subcontractor is not required to submit another set of these forms for employees who were cleared through this process while employed by the former contractor or subcontractor. The Lessor shall resubmit Form FD 258 and Standard Form 85P for every employee covered by this paragraph on a 5 year basis.

G. The Lessor shall insert this paragraph in all subcontracts when the subcontractor is required to have physical access to a federally controlled facility or access to a federal information system.

#### **6.14 SCHEDULE OF PERIODIC SERVICES (JUN 2012)**

Within 60 days after occupancy by the Government, the Lessor shall provide the LCO with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly.

#### **6.15 LANDSCAPING (JUN 2012)**

A. Landscape management practices shall prevent pollution by:

1. Employing practices which avoid or minimize the need for fertilizers and pesticides;
2. Prohibiting the use of the 2,4-Dichlorophenoxyacetic Acid (2,4-D) herbicide and organophosphates; and
3. Composting/recycling all yard waste.

B. The Lessor shall use landscaping products with recycled content as required by EPA's CPG for landscaping products. Refer to EPA's CPG web site, [www.epa.gov/cpg](http://www.epa.gov/cpg).

C. If the Lessor satisfies performance of this Lease by new construction, and where conditions permit, the site shall be landscaped for low maintenance and water conservation with plants that are either native or well-adapted to local growing conditions.

#### **6.16 LANDSCAPE MAINTENANCE (APR 2011)**

Landscape maintenance shall be performed during the growing season at not less than a weekly cycle and shall consist of watering, weeding, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an as-needed basis. In addition, dead, dying, or damaged plants shall be replaced.

#### **6.17 RECYCLING—WAREHOUSE (JUN 2012)**

- A. Where state or local law, code, or ordinance requires recycling programs for the Premises, Lessor shall comply with such state and/or local law, code, or ordinance.
- B. When implementing any recycling program, the Lessor shall provide an easily accessible, appropriately sized area (2 SF per 1,000 SF of Building gross floor area) that serves the Space for the collection and storage of materials for recycling. Telecom rooms are not acceptable as recycling space. During the Lease term, the Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the Building and in the Space.
- C. For Leases greater than 10,000 rentable SF, with a Lease term greater than six months, the Lessor shall establish a recycling program for (at a minimum) paper, corrugated cardboard, glass, plastics, and metals where local markets for recovered materials exist.

#### **6.18 RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)**

During the term of the Lease, the Lessor may not establish vending facilities within the leased Space that will compete with any Randolph-Sheppard vending facilities.

#### **6.19 INTENTIONALLY DELETED**

#### **6.20 INDOOR AIR QUALITY (MAY 2014)**

- A. The Lessor shall control contaminants at the source and/or operate the Space, as well as in space serving the Space (e.g., common use areas, janitorial closets, mechanical rooms, HVAC systems, etc.), in such a manner that the VA indicator levels for carbon monoxide (CO), carbon dioxide (CO<sub>2</sub>), and formaldehyde (HCHO) are not exceeded. The indicator levels for office areas shall be: CO 9 ppm time weighted average (TWA 8 hour sample); CO<sub>2</sub> 1,000 ppm (TWA); HCHO 0.1 ppm (TWA).
- B. The Lessor shall make a reasonable attempt to apply insecticides, paints, glues, adhesives, and HVAC system cleaning compounds with highly volatile or irritating organic compounds, outside of working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying noxious chemicals in occupied Spaces and shall adequately ventilate those Spaces during and after application.
- C. The Lessor shall promptly investigate indoor air quality (IAQ) complaints and shall implement the necessary controls to address the complaint.
- D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in Space that it occupies, as well as in space serving the Space (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by:
1. Making available information on Building operations and Lessor activities;
  2. Providing access to Space for assessment and testing, if required; and
  3. Implementing corrective measures required by the LCO.
- E. The Lessor shall provide to the Government material safety data sheets (MSDS) upon request for the following products prior to their use during the term of the Lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within:
1. The Space;
  2. Common Building areas;
  3. Ventilation systems and zones serving the Space; and
  4. The area above suspended ceilings and engineering space in the same ventilation zone as the Space.
- F. Where hazardous gasses or chemicals (any products with data in the Health and Safety section of the MSDS sheets) may be present or used, including large-scale copying and printing rooms, segregate areas with deck-to-deck partitions with separate outside exhausting at a rate of at least 0.5 cubic feet per minute per SF, no air recirculation. The mechanical system must operate at a negative pressure compared with the surrounding spaces of at least an average of 5 Pa (pascal) (0.02 inches of water gauge) and with a minimum of 1 Pa (0.004 inches of water gauge) when the doors to the rooms are closed.

#### **6.21 RADON IN AIR (SEP 2013)**

If Space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased Space for 2 days to 3 days using charcoal canisters. The Lessor is responsible to provide Space in which radon levels in air are below the VA action levels of 4 picoCuries per liter (pCi/L) for childcare and 25 pCi/L for all other space. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors shall be completed. For further information on radon, go to: <http://www.epa.gov/radon/zonemap.html>.

#### **6.22 INTENTIONALLY DELETED**

#### **6.23 HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)**

- A. The leased Space shall be free of hazardous materials, hazardous substances, and hazardous wastes, as defined by and according to applicable Federal, state, and local environmental regulations. Should there be reason to suspect otherwise, the Government reserves the right, at Lessor's expense, to require documentation or testing to confirm that the Space is free of all hazardous materials.
- B. Lessor shall, to the extent of its knowledge, notify Government of the introduction of any hazardous materials onto the Property by Lessor or others, including but not limited to, co-tenants occupying Space in the Building

C. All hazardous materials stored in the Space must be kept and maintained according to applicable Federal, State, and local environmental regulations. The Government will notify Lessor of any hazardous materials it will store in the Space.

#### **6.24 MOLD (SEP 2013)**

A. Actionable mold is mold of types and concentrations in excess of that found in the local outdoor air.

B. The Lessor shall provide Space to the Government that is free from actionable mold and free from any conditions that reasonably can be anticipated to permit the growth of actionable mold or are indicative of the possibility that actionable mold will be present (indicators).

C. At such times as the Government may direct, including but not limited to: after a flood, water damage not caused by the Government, or repairs caused by the Lessor, the Lessor, at its sole cost, expense and risk shall: (i) cause an industrial hygienist certified by the American Board of Industrial Hygienists or a qualified consultant (the Inspector) who, in either instance, is reasonably acceptable to the Government, to inspect and evaluate the Space for the presence of actionable mold or mold indicators; and (ii) cause the Inspector to deliver the results of its inspection and evaluation (the Report) to the Government within 30 days after it conducts same and, in all events, at the same time that it delivers the Report to Lessor. With the delivery of the Report to the Government, the Inspector shall notify the Government, in writing via cover letter to the report, if the Inspector discovers or suspects the existence of actionable mold or indicators in the leased Space.

D. The presence of actionable mold in the Premises may be treated as a Casualty, as determined by the Government, in accordance with the Fire and Other Casualty clause contained in the General Clauses of this Lease. In addition to the provisions of the Fire and Other Casualty clause of this Lease, should a portion of the Premises be determined by the Government to be un-tenantable due to an act of negligence by the Lessor or his agents, the Lessor shall provide reasonably acceptable alternative Space at the Lessor's expense, including the cost of moving, and any required alterations.

E. If the Report indicates that actionable mold or indicators are present in the leased Space, the Lessor, at its sole cost, expense, and risk, shall within 30 days after its receipt of the Report: (1) retain an experienced mold remediation contractor reasonably acceptable to the Government to prepare and submit to the Government and Lessor a remediation plan (the Plan) and within 90 days after the Government's approval of the Plan, remediate the actionable mold or the indicators in the leased Space, but prior to commencing such remediation, Lessor shall send the Government a notice stating: (i) the date on which the actionable mold remediation shall start and how long it is projected to continue; (ii) which portion of the leased Space shall be subject to the remediation; and (iii) the remediation procedures and standards to be used to implement the Plan and the clearance criteria to be employed at the conclusion of the remediation; and (2) notify, in accordance with any applicable Federal, state, and local health and safety requirements, the Government employees as well as all other occupants of and visitors to the leased Space of the nature, location and schedule for the planned remediation and reasons therefore.

F. The Lessor shall be responsible for conducting the remediation in accordance with the relevant provisions of the document entitled "Mold Remediation in Schools and Commercial Buildings" (EPA 402-K-01-001, March 2001), published by the U.S. Environmental Protection Agency, as same may be amended or revised from time to time, and any other applicable Federal, state, or local laws, regulatory standards and guidelines.

G. The Lessor acknowledges and agrees that the Government shall have a reasonable opportunity to inspect the leased Space after conclusion of the remediation. If the results of the Government's inspection indicate that the remediation does not comply with the Plan or any other applicable Federal, state, or local laws, regulatory standards or guidelines, the Lessor, at its sole cost, expense, and risk, shall immediately take all further actions necessary to bring the remediation into compliance.

H. If the Lessor fails to exercise due diligence, or is otherwise unable to remediate the actionable mold, the Government may implement a corrective action program and deduct its costs from the rent.

#### **6.25 OCCUPANT EMERGENCY PLANS (SEP 2013)**

The Lessor is required to cooperate, participate and comply with the development and implementation of the Government's Occupant Emergency Plan (OEP) and if necessary, a supplemental Shelter-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising its OEP and SIP. The Plan, among other things, must include an annual emergency evacuation drill, emergency notification procedures for the Lessor's Building engineer or manager, Building security, local emergency personnel, and Government agency personnel.

#### **6.26 FLAG DISPLAY (SEP 2013)**

The Lessor must supply a flagpole on the property as a requirement of this lease. The Lessor shall be responsible for the flag display on all workdays and Federal holidays. The Lessor shall illuminate the flag in lieu of raising and lowering the flag daily. The Government will provide instructions when flags shall be flown at half-staff.

#### **6.27 PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)**

Lessor shall provide, inspect, and maintain portable fire extinguishers in accordance with NFPA No. 10.

#### **6.28 TRASH DUMPSTER SERVICE (WAREHOUSE) (MAY 2014)**

Lessor must provide trash dumpster service for the Space on a basis. Lessor must provide an outdoor area for dumpsters, each measuring 72"L x 56"W x 84"H, conveniently located to the Government's loading area for the trash dumpsters at no additional charge to the Government.

#### **6.29 ACCESS TO BUILDING INFORMATION (MAY 2014)**



Building Information—including mechanical, electrical, vertical transport, fire protection and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, preferably by the development of an access list and controlled copy numbering. The LCO may direct that the names and locations of Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the Building directory.

---

## SECTION 7     ADDITIONAL TERMS AND CONDITIONS

---

### 7.01   SECURITY REQUIREMENTS (MAY 2014)

The Lessor agrees to the requirements of Security Level II attached to this Lease.

### 7.02 CLAUSES INCORPORATED BY REFERENCE

As prescribed by FAR 52.102(a) the following clauses are incorporated by reference:

52.222-4 Contract Work Hours and Safety Standards – Overtime Compensation (May 2014)  
52.222-6 Construction Wage Requirements (May 2014)  
52.222-7 Withholding of Funds (May 2014)  
52.222-8 Payrolls and Basic Records (May 2014)  
52.222-9 Apprentices and Trainees (July 2005)  
52.222-10 Compliance with Copeland Act Requirements (Feb 1988)  
52.222-11 Subcontracts (Labor Standards) (May 2014)  
52.222-12 Contract Termination – Debarment (May 2014)  
52.222-13 Compliance with Construction Wage Rate Requirements and Related Regulations (May 2014)  
52.222-14 Disputes Concerning Labor Standards (Feb 1988)  
52.222-15 Certification of Eligibility (May 2014)

### 7.03 PROVISION INCORPORATED IN FULL

52.222-5 Construction Wage Rate Requirements – Secondary Site of the Work (May 2014)

(a)(1) The offeror shall notify the Government if the offeror intends to perform work at any secondary site of the work, as defined in paragraph (a)(1)(ii) of the FAR clause at 52.222-6, Construction Wage Rate Requirements, of this solicitation.

(2) If the offeror is unsure if a planned work site satisfies the criteria for a secondary site of the work, the offeror shall request a determination from the Contracting Officer.

(b)(1) If the wage determination provided by the Government for work at the primary site of the work is not applicable to the secondary site of the work, the offeror shall request a wage determination from the Contracting Officer.

(2) The due date for receipt of offers will not be extended as a result of an offeror's request for a wage determination for a secondary site of the work.  
(End of Provision)