

**Project No. :** 549-CSI-325

**Title:** Angio Medical Equipment Site Prep

**COR:** George Johnson

**STATEMENT OF WORK:**

Provide all labor, material, and equipment to accomplish the following work:

- Build temporary walls and door unit as per attached plans labeled 549-CSI-325 Angio Elevation Plan and 549-CSI-325 Holding Room Casework. Demolition existing double door unit, temporary walls, and after job is completed. Provide metal stud framing using 3-5/8 MS 18 Gage, 16" o.c.
- Furnish and Install 2 Corian Rain Cloud Counter Top with 4" Backsplash, Cabinets with SSI Brushed Steel Laminate and 1 stainless steel top with cabinets underneath.
- Furnish and Install 2 Corian Rain Cloud Counter Top with 4" Backsplash, Cabinets with SSI Brushed Steel Laminate and 1 Stainless Steel Top with Cabinets Underneath.
- 1108" X 52" Record 5100 Slide Series Automatic Single Sliding Door Unit (SX-P) Furnished In bronze Anodized. Finish Narrow Stile, Muntins, Standard Bottom Rail and Standard Locking 2 Motion and Presence Sensors ¼" Frosted.
- ADA Sink with Hand Free Faucet
- Install four (4) SSL Fixture Furnished by the VA. Provide and install whip connections between VA furnished fixtures and one (1) dimmer switch for lights.

**General Note:** The contractor will be responsible for safety and infection control requirements such as negative air machines (as needed), Tacky Mats, general cleaning, fire extinguishers, etc.

**Period of Performance:** 30 Calendar Days