

**GCC ENTERPRISE INC.,
1601 Valley View Lane
Dallas, TX 75234**

	GCC Enterprises, Inc.								
PROJECT:	Radiology Holding Room		Radiology Holding Room						
BID DATE:	9/18/2015		at the Dallas VA						
Project	549-CSI-1325/VIR								
BID TIME:	1300 hrs								
<u>SEC.</u>	<u>DIVISION 1 - GENERAL</u>	<u>QUANTITY</u>	<u>U/M</u>	<u>COST</u>	<u>TOTAL</u>		<u>TOTAL</u>	<u>SUBS</u>	
	SUPERVISION	3	Weeks	1845	\$5,535		5,535	GCC	
	SMALL TRUCK	3	Weeks	150	\$450		450	GCC	
	Negative Air and Sticky Mats/Final Cleaning	1	Material	600	\$600		600	GCC	
	<u>DIVISION 6 - WOOD/PLASTICS</u>								
	Build temp walls and Install temp door units as per plans. Demo double door unit, temp walls and temp door after job is complete. Metal stud framing using 3-5/8 MS 18 Ga., 16" o.c. as per plans. Install 5/8" FC sheetrock on metal stud framing as per plans. Install R-11 unfaced insulation in drywall partitions as per plans. Install 2x6 noncomb wood blocking as per plans.	1	Lump Sum	2730	\$2,730		2,730	RS Drywall	
	<u>DIVISION 9 - FINISHES</u>								
	Furnish and Install 2 Corian Rain Cloud Counter Top with 4" Backsplash, Cabinets with SSI Brushed Steel Laminate and 1 Stainless Steel Top with Cabinets Underneath	1	Lump Sum	34500	\$34,500		34,500	CFS	
	Patch Sheet Vinyl as needed at door change; repair VCT as needed at door change out	1	Lump Sum	1050	\$1,050		1,050	CFS	
	<u>DIVISION 10 - SPECIALITIES</u>								

**GCC ENTERPRISE INC.,
1601 Valley View Lane
Dallas, TX 75234**

	1 108" X 52" RECORD 5100 Slide Series Automatic Single Sliding Door Unit (SX-P) Furnished In bronze Anodized Finish Narrow Stile, Muntins, Standard Bottom Rail And Standard Locking 2 Motion And Presence Sensors 1/4" FROSTED Tempered Glass One Year WarrantyTo Furnish and Install-1 Automatic simultaneous swing door operator in clear anodized finish, 75" header, 2 Wireless remote push plate actuators, 4 Supercan safety sensors door mounted, 1 Overhead Presence safety sensor. Room 3B-444 Angio will demo and remove automatic Operator and Install 1 automatic Operator(VA supplied)	1	Lump Sum	8642	\$8,642		8,642.00	DCS
	Tape and Bed/Paint both sides of room 3B-442 Corridor 3B-40M touch up if needed at corridor about 80 sqft of wall at corridor	1	Lump Sum	2577	\$2,577		2,577.00	Carrco
	<u>DIVISION 15 - MECHANICAL</u>							
	ADA Sink with Hand Free Faucet	1	Lump Sum	950	\$950		950	Innovations
	<u>DIVISION 16 - ELECTRICAL</u>							
	Install (4) SSL Fixtures Furnished by others, Provide whip connections between fixtures(VA will provide) Provide (1) Dimmer switch for lights.	1	Lump Sum	1695	\$1,695		1,695	McKenna
Note:	Department of Veterans Affairs will supply power and cut in boxes for new keypads for sliding doors.				SUB-TOTAL		58,729.00	
					OVERHEAD	10.00%	5,872.90	
					SUB-TOTAL		64,601.90	
Lead Time:	2 or 3 weeks for material after award				PROFIT	10.00%	6,460.19	
					SUB-TOTAL		71,062.09	
					GRAND TOTAL		71,062.09	