

1.8 EVALUATION FACTOR D – INTEGRATED MASTER SCHEDULE

- a. The Government will evaluate the project schedule in the form of a Critical Path Method (CPM) using the technical approach (Evaluation Factor E) identified.
- b. The Offeror's Integrated Master Schedule shall, at a minimum, comply with the requirements of:
 - i. Contract clause FAR 52.211-10 Commencement, Prosecution and Completion of Work;
 - ii. Construction Specification 01 00 00 General Requirements at 1.6 Operations and Storages Areas I. Phasing; and
 - iii. Construction Specification 01 00 00 General Requirements at 1.22 VA TRIRIGA CPMS
- c. The Offeror's schedule shall be for the entire period of performance of FAR 52.211-10. Schedule float will belong to the project and not to either the Contractor or the Government.
- d. The Offeror shall provide a project schedule to the appropriate level of detail to visibly illustrate and evaluate the sequence of work to ensure that performance will be completed on time in accordance with the contract period of performance. The integrated master schedule should clearly demonstrate a thorough understanding of all project activities related to the project scope, including but not limited to submittals, government reviews not less than 20 days, inspections, test and balance, commissioning operations, etc. The Integrated Master Schedule should not only show the activities/events for actual construction work for each trade/commodities, but also trade relationships along with Government activities that can impact progress.
- e. The schedule at a minimum should include:
 - i. Activity/Phase
 - ii. Duration
 - iii. Early Start
 - iv. Early Finish
 - v. Late Finish, if applicable
 - vi. Predecessor Activity
 - vii. Float per Activity
 - viii. Total Float
 - ix. Relevant Milestones
 - x. Identified Critical Path