



# **Fort Scott National Cemetery**

**Project Number 893CM3014B**

## **SCOPE OF WORK**

---

## SCOPE OF WORK

Fort Scott National Cemetery

893CM3014B

Renovation of Historic Rostrum

This project will renovate the historic rostrum at Fort Scott National Cemetery in Fort Scott, Kansas. The Contractor shall completely prepare site for construction operations, furnish labor and materials and perform work as required by the Drawings and Specifications. The contractor will have one hundred and eighty (180) calendar days to complete the work from the Notice to Proceed (NTP).

### CLIN1:

The horizontal construction work includes clear and grubbing, fine grading, demolition, salvage of the existing rostrum; Horizontal work will be complete by concrete and electrical and plumbing contractors. Both heavy equipment operator and general laborers will be required. Vertical construction work includes the demolition and salvage of the existing historic rostrum and will require the services of building trades to include the following; carpenter for the construction of the pergola, brick layers for the demolition, salvage and construction of the rostrum base and columns of the rostrums. Contractors include electricians for installation of the power. Other building trades include; painters railing and pergola finishes; pipe fitter for the railings. Additional site contractor will include; an irrigation contractor and landscape contractor for the finished grading, turf and plant material installation.



---

Stephen E. Davis  
PM/COR