



Profit from the Eagle Advantage[®]

Specification Sheet

Short Form Specifications

Eagle Spec-Master[®] Three-Compartment Sinks, model _____. Unit constructed of 14/304, 18-8 stainless steel throughout. Sink bowls coved with a full $\frac{5}{8}$ " radius, and shall have a 14" water level. Drainboards, when required, shall be "V" creased for positive drainage. 9 $\frac{1}{2}$ " high backsplash with 1" upturn and tile edge. Legs to be 1 $\frac{1}{2}$ " O.D., stainless steel, with stainless steel gussets, stainless steel crossbracing and adjustable stainless steel bullet feet.



3-compartment sink
(faucets not included)

Options / Accessories

- | | |
|--|--|
| <input type="checkbox"/> Lever drain | <input type="checkbox"/> Faucets |
| <input type="checkbox"/> Lever drain with overflow | <input type="checkbox"/> Polyboard sink covers |
| <input type="checkbox"/> Twist handle drains | <input type="checkbox"/> Stainless steel sink covers |
| <input type="checkbox"/> Overflow hole | <input type="checkbox"/> Skirted front panel |
| <input type="checkbox"/> Sink kits | |

Assembly:

- Entire assembly is fuse-welded and planished, providing a one-piece seamless sink unit.
- Welded areas are high-speed belt blended to match adjacent surfaces with continuity of satin finish.
- All outside corners of assembly are bullnosed to provide safe, clean edges.
- Water supply is $\frac{1}{2}$ " (13mm) IPS for hot and cold lines.

EAGLE GROUP

100 Industrial Boulevard, Clayton, DE 19938-8903 USA

Phone: 302-653-3000 • Fax: 302-653-2065

www.eaglegrp.com

Foodservice Division: Phone 800-441-8440

MHC/Retail Display Divisions: Phone 800-637-5100

For custom configuration or fabrication needs, contact our **SpecFAB[®]** Division.

Phone: 302-653-3000 • Fax: 302-653-3091 • e-mail: specfab@eaglegrp.com

Item No.: _____
Project No.: _____
S.I.S. No.: _____

Spec-Master[®] FN Series Coved Corner Three-Compartment Sinks

MODELS:

- | | |
|--|--|
| <input type="checkbox"/> FN2048-3-* | <input type="checkbox"/> FN2472-3-* |
| <input type="checkbox"/> FN2054-3-* | <input type="checkbox"/> FN2860-3-* |
| <input type="checkbox"/> FN2060-3-* | |

* See table on back for complete model numbers.

Top:

- Drainboards, backsplash and rolled rims are 14 gauge type 304 stainless steel.
- Drainboards, when provided, are integrally welded.
- All rolled edges are highlighted for enhanced appearance.
- 9 $\frac{1}{2}$ " high backsplash with 1" upturn and tile edge.
- 1 $\frac{1}{2}$ " (29mm) faucet holes** punched on 8" (203mm) centers.

Base:

- Legs: 1 $\frac{1}{2}$ " (41mm)-diameter stainless steel tubing with stainless steel gussets and fully adjustable stainless steel bullet feet.
- Crossbracing: Adjustable, 1 $\frac{1}{4}$ " (32mm)-diameter stainless steel; running left-to-right and front-to-back.
- Leg locations fall directly under sink bowls, providing increased stability and maximum weight support.
- Leg gussets welded to a die-cut heavy-gauge stainless steel reinforcing corner plate.
- Legs are crossbraced on all sides for increased stability.

Sink Bowls:

- 14 gauge type 304 stainless steel.
- 14" (356mm) water level, 17" (432mm) flood level.
- Sink compartments are coved on a full $\frac{5}{8}$ " (41mm) radius and constructed using state-of-the-art seamless welding techniques.
- Basket-type waste drain fits sink bowls' 3 $\frac{1}{2}$ " (89mm) opening and features 1 $\frac{1}{2}$ " (38mm) outlet.

** Three-compartment sinks with 20" x 16" (508 x 406mm) bowls have one set of faucet holes. All others feature two sets of faucet holes.

Certifications / Approvals



Spec sheets available for viewing, printing or downloading from our online literature library at www.eaglegrp.com

Eagle Foodservice Equipment, Eagle MHC, SpecFAB[®], and Retail Display are divisions of Eagle Group. ©2010 by the Eagle Group

Although every attempt has been made to ensure the accuracy of the information provided, we cannot be held responsible for typographical or printing errors. Information and specifications are subject to change without notice. Please confirm at time of order.