

Computer Filename:

NOTE: FIELD VERIFY EXISTING FINISHES

[illegible]

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
	CC BUILDING									
V101	ED – NURSE STATION	F4	B2	W1	W1	W1	W1	C3/C2/C1	10	PROVIDE NEW WALL
127	ED FAST TRACK	F4	B2	–	–	W1	W4	C2	11	
131	PHLEBOTOMY (BLOOD DRAW)	F4	B2	–	W1	–	–	C1	8	WALLPAPER BOARDER
P140	INPATIENT RX	F4	B2	–	W1	–	–	C3	6	
U105	OUTPATIENT RX	F4	B2	–	W1	–	–	C2	7	
T106	BLOOD BANK	F4	B2	W1	W1	W1	W1	C2	9	PROVIDE NEW WALL
T107.2	BLOOD LAB–WORKSTATION	F4	B2	–	–	W1	–	C2	5	MILLWORK
X115	ED (FUTURE EXPANSION)	–	–	–	–	–	–	–	35	NEW FINISHES T.B.D.
	CLC BUILDING									
2A143	CLC – NURSE STATION	F1	B2	W1/W2	W1/W2	W1/W2	W1/W2	C1	12	COLUMN/CORNER GUARDS

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
	CC BUILDING									
251	FLOW LAB (BONE MARROW)	F4	B2	—	—	W1	W1	C2	13	
U202	MOLECULAR LAB RPI	F4	B2	—	—	W1	W1	C2	14	
N200	RECEPTION — OR SURGERY	F4	B2	W1/W3	—	—	W1/W3	C2	16	CERAMIC TILE/PAINT
F205	OUTPATIENT SURGERY	F4	B2	W1	—	—	—	C2	21	WALL GUARD PROTECTION
N239	PACU	F4	B2	—	—	W1	—	C3	17	SYSTEMS FURNITURE
Z201	RECOVERY 2A	F4	B2	—	—	—	W1	C2	18	WALL GUARD PROTECTION
Z211	RECOVERY 2B	F4	B2	—	—	W1	—	C2	19	WALL GUARD PROTECTION
D205	SICU	F5	B2	W1	W1	W1	W1	C2	15	PROVIDE NEW WALL
A201	NURSING STATION	F4	B2	W1	W1	W1	W1	C2	36	PROVIDE NEW WALL
A227	NURSING STATION	F4	B2	W1	W1	W1	W1	C2	37	PROVIDE NEW WALL
	PRC BUILDING									
225	POLYTRAUMA	F6	B2	W1	—	—	W1	C1	20	ROD/SHELF

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
C315	CC BUILDING CYTOGENETICS	F4	B2	W1	-	-	W1	C2	22	

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
	CC BUILDING									
A433	MEDSURG –NURSE STATION	F2	B2	–	W1	–	–	C2	23	WALL GUARD PROTECTION
B406	MEDSURG –NURSE STATION	F4	B2	–	–	–	W1	C2	24	
C406	HEMODIALYSIS	F5	B5	–	–	W1	–	C2	25	

NOTE: FIELD VERIFY EXISTING FINISHES

[illegible]

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
	CC BUILDING									
A606	CCU - NURSE STATION	F4	B2	—	—	—	W1	C2	29	SYSTEMS FURNITURE
B609	IMC - NURSE STATION	F4	B2	—	—	—	W1	C2	30	WALL GUARD PROTECTION
C606	CATH LAB 2	F4	B2	—	—	W1	—	C2	31	

NOTE: FIELD VERIFY EXISTING FINISHES

RN#	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CLG	STATION NUMBER	REMARKS
	CC BUILDING									
7A	BCRU 7A NURSE STATION	F4	B2	—	W1/W2	—	—	C1	34	PAINT/VINYL WALLCOVERING
B701	BONE MARROW TRANSPLANT UNIT—NURSE STATION	F5	B5	—	—	—	W1	C3	32	EXISTING LOCATION
D707	CHEMOTHERAPY ONCOLOGY LAB / PHARMACY	F5	B5	—	W1	—	—	C2	33	

NOTE: FIELD VERIFY EXISTING FINISHES

NO.	DESCRIPTION	MFR & MODEL No.
F1	CARPET BROADLOOM	MATCH EXISTING ADJACENT CARPET FLOORING
F2	LVT	MATCH EXISTING ADJACENT LVT FLOORING
F3	PORCELAIN TILE	MATCH EXISTING ADJACENT PORCELAIN TILE FLOORING
F4	VCT	MATCH EXISTING ADJACENT VCT FLOORING
F5	SHEET VINYL	MATCH EXISTING SHEET VINYL FLOORING
F6	SHEET VINYL WOOD	MATCH EXISTING SHEET VINYL FLOORING
B1	CARPET BASE	MATCH EXISTING CARPET BASE AND HEIGHT
B2	RUBBER BASE	MATCH EXISTING RUBBER BASE/HEIGHT/STYLE
B3	PORCELAIN TILE BASE	MATCH EXISTING PORCELAIN TILE BASE
B4	WOOD STAINED BASE	MATCH EXISTING WOOD STAINED BASE
B5	SHEET VINYL SHELF COVE BASE	MATCH EXISTING SELF-COVE SHEET VINYL
W1	FIELD WALL PAINT	MATCH EXISTING ADJACENT WALL PAINT
W2	VINYL WALLCOVERING	MATCH EXISTING ADJACENT WALL COVERING
W3	CERAMIC TILE	MATCH EXISTING CERAMIC TILE
W4	ACCENT PAINT	MATCH EXISTING ADJACENT ACCENT WALL PAINT
C1	2X2 ACOUSTICAL TILE	MATCH BUILDING STANDARD
C2	2X4 ACOUSTICAL TILE	MATCH BUILDING STANDARD
C3	GYPSPUM BOARD/PAINT	PROVIDE ACCESS PANEL AND PATCH/REPAIR AND PAINT TO MATCH AS REQUIRED

SPECIAL MATERIALS

P1	PLASTIC LAMINATE -- COUNTER	MATCH EXISTING MILLWORK LAMINATE
P2	PLASTIC LAMINATE -- BASE CABINET	MATCH EXISTING MILLWORK LAMINATE
P3	PLASTIC LAMINATE -- UPPER CABINET	MATCH EXISTING MILLWORK LAMINATE
EXISTING LOCATION		REMOVE OLD PNEUMATIC TUBE EQUIPMENT AND REPLACE WITH NEW SYSTEM
WALL GUARD/CORNER GUARDS		PROVIDE NEW WALL/CORNER GUARDS TO MATCH ADJACENT WALL/CORNER PROTECTION GUARDS
SYSTEMS FURNITURE		REMOVE WALL HUNG SYSTEMS FURNITURE AND STORE/RELOCATE PER DIRECTION OF DEPARTMENT/OWNER

PNEUMATIC TUBE SYSTEM (PTS) – DEPARTMENT STATION SCHEDULE

NO.	DEPARTMENT	BUILDING	FLOOR	ROOM	PTS DROP	ACM IDENTIFIED	NOTES
1	SPD (SUPPLY, PROCESSING & DISTRIBUTION)	CC	GROUND	F832A	SINGLE	NO	
2	SCI (SPINAL CORD INJURY) PHARMACY	SCI	GROUND	C015	DUAL	NO	
3	SCI (SPINAL CORD INJURY) NURSING STATION	SCI	GROUND	D035.1	SINGLE	NO	
4	CLC (COMMUNITY LIVING CENTER) NURSING STATION	CLC	GROUND (LEVEL 1)	1A144	SINGLE	NO	
5	LAB 2 – (BLOOD LAB)	CC	FIRST	T107.2	DUAL	NO	
6	PHARMACY – INPATIENT – ULTRA STATIONS	CC	FIRST	P140	DUAL	NO	
7	PHARMACY – OUTPATIENT	CC	FIRST	U105	DUAL	NO	
8	PHLEBOTOMY (BLOOD DRAW)	CC	FIRST	131	DUAL	NO	
9	BLOOD BANK	CC	FIRST	T106	DUAL	NO	
10	ED (EMERGENCY DEPARTMENT) NURSING STATION	CC	FIRST	V101	DUAL	NO	
11	ED (EMERGENCY DEPARTMENT) FAST TRACK	CC	FIRST	127	DUAL	NO	
12	CLC (COMMUNITY LIVING CENTER) NURSING STATION	CLC	FIRST (LEVEL 2)	2A143	SINGLE	NO	B
13	FLOW LAB (BONE MARROW LAB)	CC	SECOND	251	SINGLE	YES	
14	MOLECULAR LAB RPI	CC	SECOND	U202	SINGLE	YES	
15	SICU (SURGICAL INTENSIVE CARE UNIT)	CC	SECOND	D205	SINGLE	NO	
16	OR SURGERY / SAT SUG PHARM / ANESTHESIA	CC	SECOND	N200	SINGLE	NO	
17	PACU (POST ANESTHESIA CARE UNIT)	CC	SECOND	N239	SINGLE	NO	
18	RECOVERY 2A	CC	SECOND	Z201	SINGLE	NO	
19	RECOVERY 2B	CC	SECOND	Z211	SINGLE	NO	
20	POLYTRAUMA	PRC	SECOND (LEVEL 3)	225	SINGLE	NO	
21	OUTPATIENT SURGERY	CC	SECOND	F205	SINGLE	YES	
22	CYTODIAGNOSTICS LAB	CC	THIRD	C315	SINGLE	YES	
23	MEDSURG – NURSING STATION A	CC – TOWER	FOURTH	A433	SINGLE	NO	
24	MEDSURG – NURSING STATION B	CC – TOWER	FOURTH	B406	SINGLE	YES	
25	HEMODIALYSIS	CC – TOWER	FOURTH	C406	SINGLE	YES	
26	MEDSURG – NURSING STATION A	CC – TOWER	FIFTH	A507	SINGLE	NO	
27	PCU (PROGRESSIVE CARE UNIT) MEDSURG – NURSING STATION B	CC – TOWER	FIFTH	B515	SINGLE	NO	
28	MICU (MEDICAL INTENSIVE CARE UNIT) – NURSING STATION	CC – TOWER	FIFTH	C508	SINGLE	NO	
29	CCU (CRITICAL CARE UNIT) – NURSING STATION 6A	CC – TOWER	SIXTH	A606	SINGLE	NO	
30	IMC (INTERNAL MEDICINE CLINIC) NURSING STATION – 6B	CC – TOWER	SIXTH	B609	SINGLE	NO	
31	CATH (LAB 2) – 6C	CC – TOWER	SIXTH	C606	SINGLE	YES	
32	BONE MARROW TRANSPLANT UNIT	CC – TOWER	SEVENTH	7C / B701	SINGLE	YES	
33	CHEMOTHERAPY	CC – TOWER	SEVENTH	D707	SINGLE	YES	
34	BARRETT CANCER CENTER – NURSING STATION 7A	CC – TOWER	SEVENTH	7A	SINGLE	YES	
35	ED (EMERGENCY DEPARTMENT – FUTURE EXPANSION) (ADDED TO SCOPE 4/2014)	CC	FIRST	X115	DUAL	–	A
36	2 SURGERY INPATIENT UNIT NURSING STATION (ADDED TO SCOPE 7/2014)	CC – WEST	SECOND	A201	SINGLE	–	
37	2 SURGERY INPATIENT UNIT NURSING STATION (ADDED TO SCOPE 7/2014)	CC – WEST	SECOND	A227	SINGLE	–	

PTS – NOTES

A	ROUGH-IN UTILITY SERVICE LINES (POWER / PNEUMATIC TUBES / DATA) AND CAP ABOVE CEILING; DELIVER PTS DROP STATION TO VA FOR STORAGE. VA TO INSTALL UPON COMPLETION OF AREA REMODEL TO E.D. USE.
B	CONFIRM PTS CONFIGURATION WITH USER.

PTS - BLOWER EQUIPMENT

NO.	EQUIPMENT	BUILDING	FLOOR	ROOM/AREA	NOTES
A	BLOWERS	CC	PIPE SPACE LEVEL	PS-PBX009	EXISTING STORAGE ITEMS TO BE REMOVED BY VA. STORAGE AREA INFORMATION AS FOLLOWS: SERVICE - FISCAL / MAS P.O.C. - MARK DIXON EXTENSION - 15861

100% CONSTRUCTION ISSUE

[illegible]