

STATEMENT OF WORK

PROJECT 657-15-101, FCA-UPGRADE AIR HANLDING UNITS/SYSTEMS

This project will replace air handling units currently located in the 5th floor Interstitial Space mechanical room in Building 1. Work includes mold abatement of some insulation and removal of the AHU and demolition of some ductwork. New AHUs will be installed and will also include new direct digital control systems, new chilled water piping and steam piping. New ductwork will be installed as needed and tie-in to existing where possible. New electric service to the units will be provided and new floor drains and condensate drains. The sprinkler system in the mechanical room will be adjusted to fit the new units.