

Statement of Work

Flowmeters and Regulators

Southeast Louisiana Veterans Health Care System
New Orleans, LA
April 29, 2016

1, PURPOSE

1.1 The purpose is to provide flowmeters and regulators at Southeast Louisiana Veterans Health Care System (SLVHCS) 2400 Canal St, New Orleans, LA 70119.

2. SCOPE

2.1 The Contractor shall provide all listed equipment. All products must meet all salient characteristics defined in this section and be compliant with the National Fire Protection Association's (NFPA) codes and standards.

2.2 SALIENT CHARACTERISTICS

2.2.1 Oxygen Select Flowmeter

Specifications/Salient Characteristics:

- 1-15 lpm/50PSI take off
- Increments 0.5lpm from 0.5lpm – 5lpm; 1lpm from 5-15lpm
- Flush flow – 60-80lpm
- Back flow compensated
- Wall connection DISS

2.2.2 MRI Compatible Oxygen Flowmeter

Specifications/Salient Characteristics:

- Oxygen flowmeter – composed of non-magnetic material
- 1-15 lpm/50PSI takeoff
- Increments 0.5lpm from 0.5lpm – 5lpm; 1lpm from 5-15lpm
- Flush flow – 60-80lpm
- Back flow compensated
- Wall connection DISS

2.2.3 Air Flowmeter

Specifications/Salient Characteristics:

- 1-15 lpm/50 PSI power take off
- 1-15 lpm increments 1lpm from 1-15
- Wall connection DISS

2.2.4 MRI Compatible Air Flowmeter

Specifications/Salient Characteristics:

- Air Flowmeter – composed of non-magnetic material –
- 1-15 lpm/50PSI takeoff

- Increments 0.5lpm from 0.5lpm – 5lpm; 1lpm from 5-15lp
- Flush flow – 60-80lpm
- Back flow compensated
- Wall connection DISS

2.2.5 Neb Drive Oxygen

Specifications/Salient Characteristics:

- Calibrated to deliver 8-9 LPM for nebulizer therapy
- Non-flow selecting device
- DISS
- Non-detachable nipple connection
- Female Hand Tight

2.2.6 Suction Regulator

Specifications/Salient Characteristics:

- Modes: Off/ Intermit/Continuous
- 0-200 mmHg regulated suction
- Color coded scale easily visible
- Manufacturer's warranty
- Overflow safety trap
- Fine resolution control knob
- High-flow bubble barb

3. DELIVERY

- 3.1 Contractor shall deliver all equipment to the Southeast Louisiana Veterans Health Care System (SLVHCS) Warehouse 2400 Canal St, New Orleans, LA 70119 on June 6, 2016.
- 3.2 Deliver materials to job in manufacturer's original sealed containers with brand name marked thereon.
- 3.3 Package to prevent damage or deterioration during shipment, handling, and storage.
- 3.4 Maintain protective covering in place and in good repair until delivery is necessary.
- 3.5 Any government requested delayed delivery up to 90 days after initial negotiated delivery date, shall be at no additional cost to the Government.
- 3.6 A pre-delivery meeting will be conducted 60 days prior to initial negotiated delivery date for verification of delivery and installation dates.

4. WARRANTY:

- 4.1 The contractor shall provide all manufacturers' warranty with products upon delivery.

5. INSPECTION AND ACCEPTANCE:

- 5.1 The Contractor shall conduct a joint inspection with the COR upon delivery of tools.
- 5.2 Contractor shall provide dates of completion of punch list items and replacement parts and/or short ship items from the manufacturer(s).

6. GENERAL

- 6.1 Contractors, contractor personnel, subcontractors, and subcontractor personnel shall be subject to the same Federal laws, regulations, standards, and VA Directives and Handbooks as VA and VA personnel regarding information and information system security.

7. SECURITY CLAUSE

7.1 A&A requirements do not apply--Security Accreditation Package is not required.

8. REFERENCE (S):

VA Affairs Handbook 6500, Risk Management Framework for VA Information Systems – Tier 3: VA Information Security Program, 10 Mar 2015.

Memo: VA Maintenance/Installation (Warranty) Contracts (VAIQ 7058822), 24 Mar 2011.

Veterans Affairs Handbook 6500.6 Contract Security, 12 Mar 2010.

HIPPA Privacy Rule (See 45 CFR 164, 502(a)(1))

Memo: Contractors Excepted from Background Investigations and Screenings, 8 Feb 2007