










## EXISTING CONDITIONS KEYED NOTES


KEY	NOTE
①	EXISTING TREE, TYP. PROTECT IN PLACE. TREE PROTECTION FENCING, TYP. SEE TREE PROTECTION NOTES BELOW.
②	REMOVE TREE
③	EXISTING DRAIN INLET, TYP. PROTECT IN PLACE.
④	EXISTING 15-18" STORM DRAIN, PROTECT IN PLACE.
⑤	EXISTING IRRIGATION MAINLINE, TYP. PROTECT.
⑥	EXISTING IRRIGATION LATERAL LINES, TYP. PROTECT.
⑦	EXISTING IRRIGATION CONTROL VALVE, TYP. PROTECT
⑧	EXISTING HEADSTONES (SIDE LINE), TYP. PROTECT.
⑨	TRENCH ASPHALT ROAD FOR NEW MANHOLE AND STORM DRAIN LINE TIE-IN

## LEGEND

	WORK LIMIT BOUNDARY		HEADSTONE SIDE LINE
	IRRIGATION MAINLINE		STORM DRAIN LINE
	IRRIGATION LATERAL		STORM DRAIN INLET
	IRRIGATION CONTROL VALVE		TREE, SHADE (LARGE)
	TREE, SMALL		

## TREE PRESERVATION NOTES

1. REFER TO THIS SHEET (DEMOLITION) FOR EXACT LOCATIONS OF TREES TO BE PROTECTED ON SITE.
2. INSTALL A MINIMUM OF 4" HIGH PLASTIC MESH FENCE AROUND THE CRITICAL ROOT ZONE (DRIP LINE OF TREE) OF PROTECTED TREES. SEE PLAN FOR TREES WITHIN PROJECT LIMITS REQUIRING TREE PROTECTION FENCING.
3. PARKING OF VEHICLES, EQUIPMENT, OR STORAGE OF MATERIAL UNDER THE DRIP LINE OF THE TREE SHALL NOT OCCUR AT ANY TIME.
4. NO TRENCING SHALL BE ALLOWED WITHIN THE DRIP LINES OF THE PROTECTED TREES.
5. IT IS NECESSARY TO INSTALL UNDERDRAIN WITHIN THE DRIP LINE OF TREES AS INDICATED ON THIS DRAWING. THE UTILITY LINE TRENCH SHALL BE HAND DUG UNDER THE DIRECT SUPERVISION OF A CERTIFIED ARBORIST.
6. ROOTS WHICH ARE APPROVED TO BE SEVERED OR WHICH FALL WITHIN THE TRENCH SHALL BE CUT CLEANLY AND TREATED WITH A ROOT SEALER COMPOUND AND COVERED WITH EARTH AS SOON AS POSSIBLE. SUPPORT ROOTS THAT ARE INSIDE THE DRIP LINE OF THE TREE SHALL BE PROTECTED. THE CONTRACTOR IS REQUIRED TO HAND-DIG IN THE VICINITY OF MAJOR TREES TO PREVENT ROOT CUTTING AND MANGLING WHICH MAY BE CAUSED BY HEAVY EQUIPMENT.
7. DURING CONSTRUCTION, IF ANY TREE DESIGNATED TO BE PRESERVED IS DAMAGED, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE REMOVAL AND REPLACEMENT.



Revisions		Date		