

**NOTES BY SYMBOL 'O':**

- ① EXISTING FIRE ALARM DEVICE. FIRE ALARM CONTRACTOR SHALL FIELD VERIFY INTEGRITY OF EXISTING SYSTEM AND COMPLIANCE WITH CURRENT LOCAL CODES. EXISTING FIRE ALARM SHALL BE MAINTAINED AND OPERATIONAL. REFER TO DETAIL ON THIS SHEET FOR ASME-A17.1 COMPLIANCE.
- ② CONTRACTOR SHALL PROVIDE NEW CORRIDOR LIGHTING AND SUPPLY AIR GRILLES TO MATCH BUILDING STANDARD IN AREA TO BE RE-COMPAIRED.

1/8" = 1'-0" BLDG. #29, 1ST FLOOR PLAN-MEP

TAG NO.	DESCRIPTION	UNIT
SRV-2	BLDG 29 ELEVATOR EQUIPMENT	AHU-2
SUPPLY FAN:		
ESTIMATED T.O.P. (L.W.G.)	5	
ESTIMATED T.O.P. (W.G.)	1.0	
FAN TYPE		
FAN RPM		
MOTOR HP	5	
ELECTRICAL DATA		
COOLING COIL SECTION:		
COOLING COIL CFM	412	
MAX. FACE VELOCITY (FPM)	500	
ENT. AIR DB/AB (°F)	80.0 / 67.0	
LVG. AIR DB/AB (°F)	51.3/50.90	
ROWS / FINS PER INCH	4 / 12	
AIR PRESS. DROP (L.W.G.)	5.42	
GM	45 / 52	
EMV/LMT (°F)	12.0	
WATER PRESS. DROP (°F W.G.)	18,000	
TOTAL CAPACITY (GPH)	16,000	
RESPONSIBLE CAPACITY (GPH)		
UNIT CONFIGURATION	DRAM-THRU	
FILTERS	30% FILTERS	
MODEL - TRADE	FPC06	

NOTES:  
1. PROVIDE VIBRATION ISOLATION PER 23 05 41.

Revisions	Date

**CONSULTANTS:**

TELLOS  
MECHANICAL-ELECTRICAL-PLUMBING  
MECHANICAL-ELECTRICAL-PLUMBING

**ARCHITECT/ENGINEERS:**

SBL Architecture + Planning  
1001 North Avenue Way #105, Tucson, Arizona 85711  
e: sbl@sbl.biz

**Project Title**  
FIRST-FLOOR-PLAN-MEP

**Approved Project Director**

**Project Title**  
ELEVATOR REPAIRS AND UPGRADES, BUILDINGS 29


**Location**  
VAMC - THOMAS E CREEK

**Project Number**  
VA 504-1-105

**Building Number**  
29

**Drawing Number**  
29-MEP2

**Office of Construction and Facilities Management**



100% CD'S

VA FORM 08-0231