

	A	B
1	Renovation, Madison, Wisconsin	
2	SELECTIVE DEMOLITION	
4	ARCHITECTURAL	REMOVE AND LEGALLY DISPOSE OF THE FOLLOWING:
5		Carpet and pad in the hallway, living room, dining room and bedroom
6		Base and wall cabinets in the kitchen
7		Flooring in kitchen
8		Remove and save for re-use kitchen appliances as instructed by Home Owner. Temporarily cap existing utilities as required.
9		Exterior door from kitchen to back yard
10		Widen doorway from kitchen to dining area per design by T. Hirsch, FAIA
11		Concrete driveway and apron
12		
13		
14	NEW INSTALLATION	
15	ARCHITECTURAL	PROVIDE AND INSTALL THE FOLLOWING:
16		Engineered wood flooring product in all areas where carpet was removed.
17		Seal and patch wall where exterior door was demolished to match existing surrounding finish.
18		New base and wall cabinets per design by T. Hirsch, FAIA
19		Install kitchen fixtures and appliances and connect utilities as required per design by T. Hirsch, FAIA
20		New finish floor per design by T. Hirsch, FAIA
21		Provide a new pass-thru window from kitchen to living room per design by T. Hirsch, FAIA.
22		Provide a new pass-thru window from kitchen to dining room per design by T. Hirsch, FAIA.
23		Install and connect a new power operated door opener from the adaptive bedroom to the accessible ramp behind the house. Consultwith Home Owner re: access control options (keypad, fob, wall mounted switch, etc.) Provide power as required.
24		Removed from Scope of Work.
25		Install and connect a new power operated door opener at the front door. Consultwith Home Owner re: access control options (keypad, fob, wall mounted switch, etc.) Provide power as required.
26		Provide a new camera/intercom at the front door.

	A	B
27		Provide a new concrete driveway and apron.
28		