

→ SOUTH ELEVATORS

Remove bottom two rows of wall tile and replace with bullnose tile to match existing, creating drip edge over new epoxy flooring. Repair any damaged wall tile thru-out.

New epoxy flooring
with integral covebase.

Paint all walls above tile to ceiling grid

1173

Ceiling and lights existing to remain.

Existing lavatorys to remain

P-408

Provide/Install new wall hung lavatory in office 1174 and all associated piping. Install **Government furnished** Chicago faucet. See specifications for lavatory type and size. Patch wall in 1173 to match existing.

Remove and replace toilet partition with new **stainless steel partition** to match existing configuration. Field verify dimensions.

Remove existing toilet and replace with **government furnished** stainless steel toilet. Rework plumbing for new toilet. Seal water tight around floor penetration. Install new flush valve.

P-202

P-201

Remove floor mounted urinals and replace with new **wall mounted** urinals (P-201/P-202). Mount new urinals on 20 gauge metal stud partition, 16"OC from floor to deck, covered with water repellant gypsum board and ceramic tile to match existing. Rework plumbing for new urinals. Install new flush valves.