



James A. Lovell FHCC  
3001 Green Bay Road  
North Chicago, IL. 60064

- 1 REMOVE AREA OF DAMAGED PAVING IN PREPARATION FOR NEW PAVING - INCLUDING ALL UNSOUND SUBGRADE MATERIAL.
- 2 DEMOLISH EXISTING DAMAGED CONCRETE CURB & GUTTER (WHEN PRESENT) IN PREPARATION FOR NEW. REMOVE ADJACENT PAVING AS REQUIRED.
- 3 MILL TO REMOVE 3" OF EXISTING ASPHALT. SEE NEW WORK PLANS. WHERE BASE IS EXPOSED VERIFY BASE IS SOLID AND COMPACTED TO EXCEPT NEW ASPHALT. IF ADDITIONAL BASE IS REQUIRED PROVIDE AND COMPACT AAS PER SPECIFICATIONS.
- 4 DEMOLISH DAMAGED CONCRETE STORM SEWER INLET COVER & ADJACENT DAMAGED CURBS / SIDEWALK IF REQUIRED
- 5 DEMOLISH DAMAGED CAST IRON STORM DRAIN & DAMAGED PAVING. DEMOLISH ADJACENT CURB & PAVING AS REQUIRED FOR INSTALLATION OF NEW CAST IRON DRAIN

AREAS TO BE MILLED TO REMOVE EXISTING ASPHALT

three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
three eighths inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot

Revisions:		ARCHITECT/ENGINEERS:		Approved: Assistant Director	Approved: Chief of Staff	Approved: Chief, Engineering	Drawing Title	Project Name	Project Number	Office of Construction and Facilities Management
				Approved: Service Chief	Approved: Service Chief	Approved: Service Chief	ASPHALT REPAIR REPLACEMENT LOCATIONS	NRM 556-16-002 REPAIR ROADS and CURBS	556-16-002	
				Approved: Chief, Bio-Med	Approved: Chief, EMS	Approved: Chief, Infection Control	Location		Date	
				Approved: Chief, IT	Approved: Chief, M&O	Approved: Chief, Police	CAPTAIN JAMES A. LOVELL F.H.C.C. NORTH CHICAGO, ILLINOIS	Building Number	3/30/16	
				Approved: Chief, Safety	Approved: Chief	Approved: Chief		Checked	Dwg. of	