







EQUIPMENT LEGEND					
ITEM	ELEC. SYM.	ITEM DESCRIPTION SUPPLIED AND INSTALLED BY TOSHIBA	BTU/HR	WEIGHT	REF.
1	GANT	AQUILION GANTRY (TYPE D)	6,063	1	A2
2	PCH	AQUILION HIGH CAPACITY PATIENT COUCH (EXTENDED)	*	1,544	1 A2
3	NAVI	NAVI BOX	683	27	2 A2
4	MON	CONTROL MONITOR	192	18	3 A2
5	SPK1	SPEAKER (DESKTOP)	0	5	4 A2
6	SPK2	SPEAKER (WALL MOUNT)	0	5	4 A2
7	SKBD	KEYBOARD (SCAN)	0	6	-
8	DESK	DESK FOR MONITORS & KEYBOARDS	0	221	5 A2
9	CHR	CHAIR	0	55	-
10	INV	INNERVISION WORKSTATION	444	17	6 A2
11	CONB	AQUILION CONSOLE BOX	10,246	915	7 A2
12	PR	PHANTOM RACK (MOBILE CART TO TRANSPORT PHANTOMS)	0	287	9 A2
ITEM	ELEC. SYM.	ITEM DESCRIPTION - SUPPLIED BY TOSHIBA & INSTALLED BY CUSTOMER / CONTRACTOR	BTU/HR	WEIGHT	REF.
13	PD	POWER DISTRIBUTOR	4,777	1,654	8 A2
ITEM	ELEC. SYM.	OPTIONAL ITEM DESCRIPTION - SUPPLIED & INSTALLED BY TOSHIBA	BTU/HR	WEIGHT	REF.
14	DKBD	KEYBOARD (DISPLAY)	0	6	-
15	FPMC	CT FLUOROSCOPY FLAT PANEL MONITOR (CEILING MOUNTED)	137	56	-
16	EOP	CT FLUOROSCOPY EXTENSION OPERATING PANEL (PEDESTAL MOUNTED)	0	T.B.D.	-
17	RWT	ECG MONITOR, R-WAVE TRIGGER (MODEL 7800) ON ROLL STAND	-	29	-
* AQUILION GANTRY & COUCH BTU / HOUR:					
EXAM ROOM SCANNING 2 PATIENTS: 20,712 BTU/HR					
EXAM ROOM SCANNING 3 PATIENTS: 21,991 BTU/HR					
EXAM ROOM SCANNING 4 PATIENTS: 23,271 BTU/HR					
EXAM ROOM SCANNING 5 PATIENTS: 24,550 BTU/HR					
EXAM ROOM SCANNING MAXIMUM: 25,830 BTU/HR					
FUTURE GROWTH OF FACILITY MUST BE CONSIDERED WHEN FORECASTING PATIENT NUMBERS FOR A/C REQUIREMENTS.					
REVISED: 07-17-14					

SITE PLAN APPROVAL	
IN ORDER TO USE THIS SET OF FINAL SITE PLANS, A CUSTOMER SIGNATURE IS REQUIRED BELOW. THE CUSTOMER'S SIGNATURE DEMONSTRATES ACCEPTANCE OF THE LAYOUT SHOWN AND ALL STATED SPECIFICATIONS.	
CUSTOMER:	DATE:
SALES:	DATE:
I.P.M.:	DATE:

**TOSHIBA**  
Leading Innovation >>>

VA  
**WILKES BARRE**  
(AQUILION - ONE 320)  
111 E. END BLVD.  
WILKES BARRE, PA 18711

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 03-02-16

SCALE: 1/4" = 1'-0"

PLANNER: V. H.

SID: 30031364

PROJECT NO.  
**150015930CTF**

**A1**

FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.