


HATCH INDICATIONS SHOWN AS GUIDE ONLY; HATCHING SCALES MAY NEED TO BE MODIFIED DEPENDING UPON SCALE USED



REFER TO THE MATERIAL LEGEND FOR ABBREVIATIONS RELATED TO FINISHES NOT HERE LISTED

[illegible]

GENERAL CONTRACTOR IS RESPONSIBLE FOR ENSURING ALL SUBCONTRACTORS ARE AWARE OF THESE NOTES

- THAT WILL OCCUR IN PHASE 2B AND PHASE 3 ABOVE TO BE COMPLETED BEFORE PHASE 3 BEGINS.
61. THERE IS NO CONTRACTOR PARKING ON VA PROPERTY BOUNDED BY GRAND, ENRIGHT, SPRING AND WALL. CONTRACTOR PARKING IS ALLOWED IN HARGES SPACES IN THE VA LOT OPPOSITE THE HOSPITAL AT THE CORNER OF GRAND BLVD. AND DELMAR AVE. CONTRACTOR MAY LOAD AND UNLOAD MATERIALS IN UNRESTRICTED AREAS ONLY, AND CANNOT LEAVE A VEHICLE UNATTENDED.
62. FOR DOORS BEING REPLACED AND WALLS WITHIN A CONSTRUCTION AREA: CAREFULLY REMOVE SIGNAGE, ROOM NUMBERS, ARTWORK, ETC., AND STORE IN A PROTECTIVE BOX FOR REINSTALLATION AT COMPLETION OF AREA. ANY DAMAGED SIGNAGE, ARTWORK, ETC., SHALL BE REPLACED WITH NEW. VA INTERIOR DESIGNER AND COR SHALL IDENTIFY LOCATIONS FOR REINSTALLATION.
63. THERE IS SPACE FOR ONLY ONE CONSTRUCTION DEMOLITION DEBRIS DUMPSTER ON SITE AT THE DOCK. THE VA DOES NOT PROVIDE A DUMPSTER FOR THIS MATERIAL. CONTRACTORS WORKING AT THE MEDICAL CENTER SHALL COOPERATE AND PROPORTIONALLY SHARE THE COST OF THE DUMPSTERS.
64. WHEN WORKING IN OCCUPIED AREAS OF THE MEDICAL CENTER THE CONTRACTOR CANNOT HAVE TOOLS, EQUIPMENT, LADDERS, ETC., UNATTENDED WHERE THEY ARE ACCESSIBLE TO PATIENTS, STAFF, VISITORS, ETC. CEILING TILES AND CEILING ACCESS PANELS MUST ALSO BE REPLACED WHEN UNATTENDED, FOR SAFETY AND INFECTION PREVENTION REASONS.

## ARCHITECTURAL CONSTRUCTION PHASING

1-2A-3-PH1-100	PARTIAL 4TH FLOOR CONSTRUCTION PHASING FOR PHASE 2A & 3
1-2A-3-PH1-101	CONSTRUCTION PHASING DETAILS FOR PHASE 2A & 3

## ARCHITECTURAL

1-3A-100-100	4TH FLOOR DEMOLITION COMPOSITE - PHASE 3
1-3A-101-101	PARTIAL 4TH FLOOR DEMOLITION PLAN - PHASE 3
1-3A-101-101	PARTIAL 4TH FLOOR COMPOSITE PLAN - PHASE 3
1-3A-102-102	PARTIAL 4TH FLOOR DIMENSION PLAN - PHASE 3
1-3A-103-103	ENLARGED PLAN - PHASE 3
1-3A-104-104	PARTIAL 4TH FLOOR REFLECTED CEILING PLAN - PHASE 3
1-3A-105-105	PENTHOUSE ROOF PLAN - PHASE 3
1-3A-200-200	INTERIOR ELEVATIONS
1-3A-500-500	ARCHITECTURAL WALL PARTITIONS SECTIONS AND DETAILS
1-3A-501-501	LEAD LINING DETAILS
1-3A-502-502	CASEWORK DETAILS
1-3A-600-600	OPENING SCHEDULE - PHASE 3
1-3A-601-601	PARTIAL 4TH FLOOR EQUIPMENT PLAN - PHASE 3
1-3A-602-602	OVERHEAD 4TH FLOOR OR SUITE EQUIPMENT PLAN
1-3A-603-603	EQUIPMENT SCHEDULE ALL PHASES FOR INFORMATION ONLY
1-3A-604-604	PARTIAL 4TH FLOOR FINISH PLAN & SCHEDULES - PHASE 3

1. THE WORK FOR PHASE 3 CANNOT COMMENCE UNTIL THE PHASE 2B IS COMPLETE AND ACCEPTED BY THE VA AND UNTIL THE VA HAS EVACUATED EQUIPMENT AND SUPPLIES AND HAS TURNED OVER THE PROJECT AREA TO THE CONTRACTOR.

**SPECIAL WORKING HOURS:**  
TO MINIMIZE INTERFERENCE WITH ADJECENT SURGERY AREA WORKING HOURS ARE RESTRICTED TO 8:00PM - 5:00PM, MONDAY THROUGH FRIDAY. WEEKEND WORK IS ACCEPTABLE. THE CONTRACTOR SHALL EXPECT 2 EMERGENCY SURGERIES PER MONTH THAT WILL CAUSE AN APPROXIMATE WORK STOPPAGE OF 4 HRS. PER SURGERY.

---

CONSULTANTS:

---

One Memorial Drive  
Suite 1800  
Saint Louis, MO 63102

15X014.021.0201

MEP & Structural Engineer  
18207 Edison Avenue  
Chesterfield, MO 63005

Tel 636.530.7770  
Fax 636.530.7877

TABLE 1

Approved: Associate Director	Approved: Chief Engineer
------------------------------	--------------------------

Approved: Chief of Staff

Approved: Infection Control

Approved: Infection Control	Approved: Child, Family & Community
-----------------------------	-------------------------------------

Location	V.A.M.C. ST. LOUIS, MO
----------	------------------------

Date	Checked	Drawn
------	---------	-------

06/01/16	IB	MP
----------	----	----

01	
----	--

Drawing Number

1-3-GI-00

100

Department of

 Department of  
Psychology 0221