PROVIDE THE FOLLOWING SERVICES FOR ROOM 2J-128:
1. TWO (2) INCH, TYPE "C", FLOOR DRAINS LOCATED 11'-6" NORTH OF SOUTH WALL AND APPROXIMATELY 6" FROM WEST WALL.
2. 3/4" HOT AND COLD WATER SERVICES AT SAME LOCATION AS ABOVE. STUB OUT WATER SERVICE 12" ABOVE FINISHED FLOOR AND PROVIDE SHUT-OFF VALVE AND CAP.
3. 1/2" MEDICAL AIR WALL OUTLET ON SOUTH WALL, APPROXIMATELY 4'-0" WEST OF GRID "DD" AND ABOVE BASE CASEWORK.

SEE SHEET 70-165 AREA "M"

FOR CONT. SEE SHT. 70-P85

SEE SHEET 70-165 AREA "M"

233 EYE CLINIC

262 AMBULATORY SURGERY

402 EDUCATION

286 SURGICAL SERVICE

O.R.-1 O.R.-2 O.R.-3 O.R.-4 O.R.-5 O.R.-6 O.R.-7 O.R.-8 O.R.-9 O.R.-10 O.R.-11 O.R.-12 O.R.-14 O.R.-15 O.R.-16 O.R.-17 O.R.-18 O.R.-19

OP SURGERY

SP3

FOR CONT. SEE SHT. 70-P63

SEE SHEET 70-143 AREA "A"

SEE SHEET 70-145 AREA "B"

FOR CONT. SEE SHT. 70-P65

SHEET SHEET 70-145 AREA "B"

SEE SHEET 70-161 AREA "K"

FOR CONT. SEE SHT. 70-P81

NOTES:
1. MED GAS PIPING SERVING CEILING OUTLETS SHALL BE SIZED AS FOLLOWD 1 1/4" MV, 1/2" MA, 1/2" OXY, N & NO.
2. SEE NOTE #39 & #40 ON SYMBOL & ABBREVIATION SHT.
3. CAP 1 1/2" WASTE & 1/2" H & CW IN WALL FOR SINKS IN CASEWORK FOR ROOMS 2J123, 2J106, 2K136A & 2L169.
4. NITROGEN CEILING OUTLETS TO BE SUPPLIED THRU NITROGEN CONTROL CABINET.
5. FOR FLOOR DRAINS SEE NOTE #34 AND #35, SHT. 70X9 AND 70X11.

This area is protected by an automatic fire extinguishing system.

AS-BUILT EYE/AMBULATORY CLINIC RENOVATION J.L.WILLE 6-10-1997

REVISIONS | DATE

GENERAL NOTES:

GENERAL CONTRACTOR AND/OR ALL SUBCONTRACTORS SHALL FIELD VERIFY ALL DIMENSIONS SHOWN ON THESE PLANS AND SHALL BE RESPONSIBLE FOR VARIATIONS BETWEEN PLAN DIMENSIONS AND ACTUAL FIELD DIMENSIONS. WHERE VARIATIONS ARE FOUND TO OCCUR, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING PRIOR TO PROCEEDING WITH CONSTRUCTION; NO ADJUSTMENT TO THE WORK WILL BE MADE WITHOUT THE PRIOR APPROVAL OF THE PROJECT ENGINEER.

GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR GENERAL DEMOLITION INCLUDING REMOVAL OF WALLS, PARTITIONS, DOORS & CEILING & FLOORS, ANY AND ALL CUTTING OF CONCRETE FLOORS, WALLS OR STRUCTURE SHALL BE THE GENERAL CONTRACTOR'S RESPONSIBILITY. CORE DRILLING THROUGH CONCRETE WALLS, FLOORS OR STRUCTURE FOR PIPING OR CONDUIT SHALL BE THE RESPONSIBILITY OF THE SUBCONTRACTOR BY TRADE; FIRESTOPPING OF THESE OPENING SHALL BE DONE BY THE RESPECTIVE SUBCONTRACTOR. REMOVAL OF DEBRIS RESULTING FROM DEMOLITION, CUTTING, AND/OR DRILLING IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. PATCHING AND REPAIR OF CONCRETE WALLS, FLOOR, OR STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR; THIS WILL BE ACCOMPLISHED UPON COMPLETION OF THE INSTALLATION OF ANY AND ALL UTILITIES INSTALLED BY THE VARIOUS SUBCONTRACTORS.

TRUE NORTH
PLAN NORTH

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED UNDER THE LAWS OF THE STATE OF MINNESOTA
REGISTRATION NUMBER:

Drawing Title: SECOND FLOOR AREA "L" PLUMBING
Drawing Scale: 1/8" = 1'-0"
Plot Scale: 12" = 1'-0"
Approved: Division Chief
Approved: Service Director

Project Title: REPLACEMENT MEDICAL CENTER
Location: V.A. MEDICAL CENTER ONE VETERANS DRIVE MINNEAPOLIS, MN 55417
Date: 04/15/1998 | Checked | Drawn

Project No.
Building Number: 70
DRAWING NO.: 70-P83
Dwg. - Of 87

Office of Facilities Management
Department of Veterans Affairs