



DOOR SCHEDULE							
DOOR NUMBER	DOOR		FRAME		HARDWARE SET	REMARKS	
	TYPE	RATING	MATERIAL	TYPE			RATING
01/1	A	X	H.M.	A	X	HM2	INSULATED, ALUM. SILLS, WEATHER STRIPING, KICK PLATES, PRIME AND PAINT
01/2	B	X	STEEL	N/A	X	HM2	INSULATED, WEATHER STRIPING, PRIME AND PAINT

DOOR SCHEDULE GENERAL NOTES:

1. FIELD VERIFY ALL DIMENSIONS AND CONDITIONS PRIOR TO ANY FABRICATION
2. COORDINATE OPENINGS WITH FLOOR PLANS AND WALL SECTIONS
3. USE A PAINTABLE, TWO-PART POLYURETHANE SEALANT @ ALL LOCATIONS
4. ALL DOORS ARE 1 3/4" THICK, UNLESS OTHERWISE NOTED
5. ALL NEW DOORS TO RECEIVE NEW HARDWARE. IF NO HARDWARE SET IS LISTED, CONSULT ARCHITECT FOR HARDWARE SET.
6. REFER TO JAMB DETAILS FOR APPROPRIATE DOOR FRAME INSTALLATION REQUIREMENTS.
7. ANCHOR STEEL JAMBS INTO MASONRY AS REQUIRED.

AS-BUILT SET

[illegible]