ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS				CEILING		REMARKS
				N	E	S	W	MATL	HEIGHT	
2S-01	CANTEEN STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-02	ELEC CLST	CONC.	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXP STRUC	--	NOTE 7
2S-03	ELEC CLST	CONC.	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXP STRUC	--	NOTE 7
2S-04	DIRTY UTILITY	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-10	SP COORD	CPT-1	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-12	SP CASE MGR	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-14	SP CASE MGR	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-15	PTSD WAITING	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-4	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-16	PTSD CASE MGR	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-17	CHECK-IN	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-4	GYP BDPT-1	ACT-1	9'-0"	NOTE 3
2S-18	PTSD CASE MGR	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-19	PTSD PHYS ROOM	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-20	OEF/OIF COUNSELOR	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-21	PTSD SMALL GROUP	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-22	SOC WRK	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-23	MECHANICAL	CONC.	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXP STRUC	--	NOTE 7
2S-24	PSYCH OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-25	PTSD LARGE GROUP	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-26	NEURO PSYCH	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-28	PSYCH OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-30	TELM PSYCH	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-32	BREAKROOM	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-33	VISN PRG SUP	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-34	STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-35	TELM CONF.	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-36	STAIR #10	RT	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-2	ACT-1	VARIES	--
2S-37	JANITOR	CONC.	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	NOTE 7
2S-38	MH CHIEF	CPT-1	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-40	ASSIST CHIEF	CPT-1	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-41	WOMEN'S TOILET	CT-1	B-3	CT-1/2	GYP BD/PT-1	GYP BD/PT-2	GYP BD/PT-1	ACT-1	9'-0"	NOTE 5, 6
2S-42	ADMIN OFFICER	CPT-1	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-43	MH PSA	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-44	ADMIN SEC	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-45	MEN'S TOILET	CT-1	B-3	GYP BD/PT-2	GYP BD/PT-1	CT-1/2	GYP BD/PT-1	ACT-1	9'-0"	NOTE 5, 6
2S-46	OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-47	GROUP ROOM	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-48	COPIER	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-49	CLEAN STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP	9'-0"	--
2S-50	OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-52	CRC SOC WRK	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-54	CRC SOC WRK	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-56	CRC PRG COORD	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-58	CRC PSA	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-66	SP PSA	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
2S-67	WOMEN'S TOILET	CT-1	B-3	GYP BD/PT-1	CT-1/2	CT-1/2	GYP BD/PT-2	ACT-1	9'-0"	NOTE 5, 6
2S-68	MEN'S TOILET	CT-1	B-3	GYP BD/PT-1	GYP BD/PT-2	CT-1/2	CT-1/2	ACT-1	9'-0"	NOTE 5, 6
2S-69	CORRIDOR	LVT-1/2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	8'-6"	NOTE 4
2S-70	CORRIDOR	LVT-1/2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	8'-6"	NOTE 4
2S-71	ELEVATOR LOBBY	LVT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
2S-72	CORRIDOR	LVT-1/2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	VARIES	NOTE 4
2S-73	IT CLST	CONC.	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXP STRUC	--	NOTE 7
2W-44	OFFICE	EXIST'G	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXIST'G	--	--
2W-45	CORRIDOR	LVT-1/2	B-2	--	GYP BD/PT-1	--	GYP BD/PT-1	ACT-1	VARIES	NOTE 4

REMARKS:

1. PLASTER WALLS TO BE PAINTED PT-3.
2. CT ON WALLS WHERE INDICATED. SEE SHEET A303 AND A402
3. TRANSACTION COUNTER & SILL @ PASS WINDOW TO BE SSM-1.
4. FOR CORRIDOR FLOORING DESIGN, SEE SHEET A604.
5. LAVATORY COUNTER TO BE SSM-1. MILLWORK TO BE PL-2.
6. FOR TILE PATTERN, SEE SHEET A402.
7. SEAL ALL EXPOSED CONCRETE FLOORS.

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS				CEILING		REMARKS
				N	E	S	W	MATL	HEIGHT	
3RD FLOOR										
3S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
3W-20	OFFICE	EXIST'G	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXIST'G	--	--
3W-21	CORRIDOR	LCT-1/2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	VARIES	NOTE 4
3W-22	OFFICE	EXIST'G	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXIST'G	--	--
4TH FLOOR										
4S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
4W-17A	SEC OFFICE	LVT-2	B-2	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
4W-17B	OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
4W-18	CORRIDOR	LCT-1/2	B-2	--	GYP BD/PT-1	--	GYP BD/PT-1	ACT-1	VARIES	NOTE 4
4W-19A	OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
4W-19B	OFFICE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
5TH FLOOR										
5S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
5W-17	OFFICE	EXIST'G	--	GYP BD/PT-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXIST'G	--	--
5W-18	CORRIDOR	LVT-1/2	B-2	--	GYP BD/PT-1	--	GYP BD/PT-1	ACT-1	VARIES	NOTE 4
5W-19	OFFICE	EXIST'G	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	EXIST'G	--	--
6TH FLOOR										
6S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
6W-11	LOBBY	LVT-1/2	B-2	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
6W-12	STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
7TH FLOOR										
7S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
7W-11	LOBBY	LVT-1/2	B-2	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
7W-12	STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
8TH FLOOR										
8S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
8W-11	LOBBY	LVT-1/2	B-2	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
8W-12	STORAGE	LVT-2	B-2	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT-1	9'-0"	--
9TH FLOOR										
9S-71	ELEVATOR LOBBY	LCT-1/2	B-1	--	GYP BD/PT-1	GYP BD/PT-1	GYP BD/PT-1	ACT/GYP. BD.	VARIES	NOTE 1, 2
9W-31	CORRIDOR	LVT-1/2	B-2	--	GYP BD/PT-1	--	GYP BD/PT-1	ACT-1	VARIES	NOTE 4
10TH FLOOR										
10S-71	EQUIPMENT ROOM	CONC	B-2	PT-1	PT-1	PT-1	PT-1	EXP STRUC	--	NOTE 7

FINISH NOTES:

NOTE: THE FOLLOWING PRODUCTS WERE USED IN ORIGINAL CONSTRUCTION AND ARE BASIS OF DESIGN.

1. WOOD DOORS TO BE STAINED DS-1.
2. LUXURY VINYL TILE BUTT JOINTED. SEE "FINISHES". PRODUCT TO COMPLY WITH ASTM F1700 MICRO BEVEL EDGE, 0.020" WEAR LAYER.
3. HOLLOW METAL DOOR & WINDOW FRAMES TO BE PAINTED PT-1 SEMI-GLOSS.
4. HANDRAILS AND CORNER GUARDS TO BE ACROVYN 100 "EGGSHELL".
5. WINDOW SILLS TO BE SSM-1.
6. WINDOW TREATMENT COLOR TO BE DETERMINED AT SUBMITTAL.
7. CABINETS ARE TO BE PL-1 AND COUNTERTOPS, WHERE INDICATED, TO BE PLAM ARE TO BE PL-2.
8. FIRE EXTINGUISHER CABINET TO BE PAINTED TO MATCH ADJACENT WALL.
9. STAIR RUBBER TREAD COLOR TO BE DETERMINED AT SUBMITTAL. PRODUCT TO COMPLY WITH ASTM F1344 CLASS, HOMOGENOUS, TYPE B.
10. STAIR RISER AND RAILING TO BE PAINTED PT-3.
11. ELEVATOR CAB FLOORING TO BE LVT-2 AND WALLS TO BE DETERMINED AT SUBMITTAL.
12. TOILET PARTITIONS TO BE BAKED ENAMEL-COLOR TBD.
13. DRY ERASE PRESENTATION WALL COVERING COLOR TO BE DETERMINED AT SUBMITTAL. PROVIDE ON NORTH WALL OF ALL GROUP ROOMS.
14. EXTERIOR BRICK TO BE ACME BRICK "BURNT PUMPKIN" BASIS OF DESIGN.
15. EXTERIOR GLAZING TO BE 1" "GREYLITE" LOW-E INSULATED – ASSUMED TO BE MANUFACTURED BY AMERICAN GLASS (VITRO AMERICA LOCAL SUPPLIER).
16. EXTERIOR ALUMINUM TO BE DARK BRONZE ANODIZED.
17. SUPPLY MINI-BLINDS AT ALL EXTERIOR WINDOWS.
18. ELEVATOR CAB FLOOR TO BE LVT-2. WALLS & CEILING TO BE BRUSHED STAINLESS STEEL.
19. NEW STAIR TOWER FLOORS TO BE LVT-2 W/B-2 BASE. PAINT EAST WALL PT-2. ALL OTHER WALLS PT-1.

GENERAL FINISH NOTES:

1. ALL NEW FINISHES ARE INTENDED TO MATCH EXISTING INSTALLED IN SOUTH WING CONSTRUCTION.
2. PAINT/STAIN ALL UNFINISHED MATERIALS AS INDICATED BY SCHEDULES AND NOTES.
3. REFER TO FLOOR FINISH LAYOUT SHEET A604 AND INTERIOR ELEVATION SHEETS A303 AND A402 FOR ADDITIONAL INFORMATION AND LOCATION OF VARIOUS MATERIALS.
4. REVISE LVT TO STANDARD VCT ALL SCHEDULED LOCATIONS IF DEDUCT BID OPTION PER SPECIFICATIONS 01 00 00 PARAGRAPH 1.2.4, SUB PARAGRAPH 7 IS ACCEPTED.
5. SIGNAGE COLORS TO MATCH EXISTING.
6. PAINT END OF WALLS AT WINDOWS BLACK.
7. WALL SURFACE TEXTURES IN PAINTED AREAS TO BE "ORANGE-PEEL".
8. METAL PANELS INDICATED FOR ROOF ENCLOSURES AND REAR OF PARAPETS TO BE 26 GA EXPOSED FASTENER MATERIAL. FINISH IN DARK BRONZE TO MATCH STOREFRONT WITH FACTORY POLYVINYL FLUORIDINE (PVF2) FINISH.

FINISHES

FINISH NO.	DESCRIPTION
	PAINT
PT-1	TO MATCH SHERWIN WILLIAMS, SW6107 NOMADIC DESSERT
PT-2	TO MATCH SHERWIN WILLIAMS, SW6194 BASIL
PT-3	TO MATCH SHERWIN WILLIAMS, SW7618 DEEP SEA DIVE
PT-4	TO MATCH SHERWIN WILLIAMS, SW007 DECOROUS AMBER
	DOOR STAIN
DS-1	MARSHFIELD, #26-95 HONEY
	CARPET TILE
CPT-1	MANNINGTON, R&D 11, CHALLENGE
	LUXURY VINYL TILE
LVT-1	ARMSTRONG, NATURAL CREATIONS, TP512 KASHMIR SAND
	12"x24" OR EQUAL
LVT-2	ARMSTRONG NATURAL CREATIONS, ARBOR ART TP020 WALNUT MEDIUM
	4"x36" OR EQUAL
	PORCELAIN AND CERAMIC TILE
CT-1	DAL-TILE VERANDA, GRAVEL, 13"x13" OR EQUAL (FIELD TILE)
CT-2	DAL-TILE GLASS REFLECTIONS, URBAN CAMOUFLAGE OR EQUAL
	GROUT
G-1	CUSTOM BUILDING PRODUCTS #145 LIGHT SMOKE
	BASE
B-1	ROPPE, 193 BLACK BROWN, 6" COVED RUBBER BASE OR EQUAL
B-2	ROPPE, 193 BLACK BROWN, 4" COVED RUBBER BASE OR EQUAL
B-3	DAL-TILE VERANDA, GRAVEL, COVE BASE OR EQUAL
	PLASTIC LAMINATE
PL-1	FORMICA, 3696-58 SHOJI SCREEN
PL-2	FORMICA, 3688-58 MADRAS INDIAN SLATE
	SOLID SURFACE MATERIAL
SSM-1	CORIAN FOSSIL OR EQUAL
SSM-2	CORIAN COCOA BROWN OR EQUAL
	CEILING
ACT-1	ACT TO MATCH EXISTING HOSPITAL STANDARD
GYP	GYP. BD. FURR DOWN / CEILING PT-1
	RUBBER TREAD
RT	TO BE DETERMINED

SUBJECT TO COMPLIANCE WITH SPECIFICATIONS PRODUCTS OF OTHER MANUFACTURERS THAT MATCH INDICATED FINISH ARE ACCEPTABLE FOR USE.

NORTH

100% REVIEW SUBMITTAL

	Revisions	Date

Toland◆Mizell◆Molnar, LLC
590 MEANS STREET NW,
SUITE 200
ATLANTA, GA, 30318
404-214-9774

ALAN J. TOLAND REG. NO. 6788 STATE OF LOUISIANA REGISTERED ARCHITECT

Drawing Title: FINISH SCHEDULES

Approved Project Engineer:

Project Title: 2ND FLOOR OUTPATIENT MENTAL HEALTH

Building Number: BLDG 1 SOUTH WING
Checked: AJT
Drawn: EO
Location: VA MEDICAL CENTER SHREVEPORT, LOUISIANA

Date: 05-25-2011
Project No.: VA256-C-1047
DRAWING NO.: A601
Dwg. – Of –

Veterans Administration

VA FORM 08-6231A, MAR 1984

U.S. GOVERNMENT PRINTING OFFICE:1984-440-467

one-eighth inch = one foot
one-quarter inch = one foot
three-eighths inch = one foot
one-half inch = one foot
three-quarters inch = one foot
one inch = one foot