



GENERAL NOTE:
(DEMOLITION SHEET ONLY)

THIS PLAN SHOWS GENERALLY THE EXTENT OF DEMOLITION TO BE PERFORMED. CONTRACTOR SHALL DISCONNECT, REMOVE, AND HAUL OFF ALL ACCESSIBLE ELECTRICAL, LIGHTING, DEVICES, DATA OUTLETS, NURSE CALL, CABLE TELEVISION, ETC. IN THE RENOVATED SPACES UNLESS NOTED OTHERWISE BACK TO CLOSEST JUNCTION BOX OR TERMINATION POINT, AND LEAVE ALL NON-DEMOLISHED CIRCUITS, DEVICES, EQUIPMENT, ETC. IN PROPER WORKING ORDER. EXISTING ELECTRICAL CIRCUITS, DATA, CABLE TELEVISION, ETC. MAY BE REROUTED AND REINSTALLED IN NEW LOCATIONS IN RENOVATED AREAS, COORDINATE WITH NEW WORK PLANS FOR NEW LOCATIONS. CONTRACTOR SHALL COORDINATE SO THAT ALL EXISTING TO REMAIN CIRCUITS IN NON-RENOVATED SPACES REMAIN ACTIVE AND IN PROPER WORKING ORDER, DURING AND AFTER WORK IS TO BE PERFORMED. ANY DOWNTIME FOR RENOVATION OF SPACES THAT WILL AFFECT NON-RENOVATED SPACES SHALL BE COORDINATED WITH VA AT LEAST 2 WEEKS PRIOR TO BEGINNING WORK. DOWNTIME SHALL BE LIMITED TO WEEKENDS AND AFTER 7:00 P.M. ON WEEKDAYS UNLESS APPROVED BY THE VA.

- DEMOLITION NOTES:**
(THIS SHEET ONLY)
- 1 NO ELECTRICAL DEMOLITION REQUIRED THIS SPACE.
 - 2 CONTRACTOR SHALL DISCONNECT AND RELOCATE ELECTRICAL POWER CONNECTIONS TO HVAC, FAN COIL UNIT. SEE NEW WORK PLAN E405 FOR EXACT LOCATION.
 - 3 DISCONNECT AND REMOVE POWER CONNECTION TO PATIENT LIFT AND TURN OVER TO VA.
 - 4 DISCONNECT AND REMOVE NURSE CALL DEVICE AND TURN OVER TO VA.
 - 5 DISCONNECT AND REMOVE ALL POWER REQUIREMENTS TO HVAC FAN COIL UNIT.
 - 6 EXISTING ELECTRICAL CONDUIT FOR LIGHTING AT ROOF. CONTRACTOR SHALL REMOVE AND REROUTE CONDUIT FOR A COMPLETE AND WORKING INSTALLATION OF LIGHTING TO AVOID NEW CORRIDOR LOCATION TO BE IN SAME LOCATION. ALL WORK TO RELOCATE LIGHTING CIRCUIT SHALL BE DONE DURING DAYTIME HOURS SO THAT THERE IS NO LOSS OF TIME THAT LIGHT FIXTURES ARE WORKING.
 - 7 CONTRACTOR SHALL REMOVE EXISTING SECTION OF LIGHTNING PROTECTION SYSTEM AND PROVIDE NEW AT TOP OF NEW CORRIDOR ADDITION, TO MATCH EXISTING INSTALLATION. SEE SHEET E104 FOR LIGHTING RENOVATION AT ROOF OF STAIR TOWER ADDITION.
 - 8 POWER CONNECTION TO FAN COIL UNIT IN THIS LOCATION TO REMAIN "AS-IS".
 - 9 CONTRACTOR SHALL RELOCATE EXISTING ELECTRICAL CONDUIT AND CONDUCTORS IN THIS WALL. ROUTE 3#2,#6G;1-1/2" C TO AVOID WALL BEING REMOVED AT EACH END. JUNCTION BOXES HAVE BEEN PROVIDED AT CEILING OF FIRST FLOOR AREA TO HELP WITH RELOCATION.
 - 10 EXISTING LIGHTING IN THIS SPACE TO BE TEMPORARILY REMOVED, AND REPLACED AT THE COMPLETION OF NEW CEILING DURING CONSTRUCTION.

Revisions	Date

Toland♦Mizell♦Molnar, LLC

590 MEANS STREET NW,
SUITE 200
ATLANTA, GA, 30318
404-214-9774

Drawing Title	DEMOLITION STAIRWELL PLANS ELECTRICAL	
Approved Project Engineer		

Project Title	2ND FLOOR OUTPATIENT MENTAL HEALTH	
Building Number	BLDG 1 SOUTH WING	Checked
Location	VA MEDICAL CENTER SHREVEPORT, LOUISIANA	

Date	05-25-2011
Project No.	VA256-C-1047
DRAWING NO.	ED101
Dwg. Of	

100% REVIEW
SUBMITTAL

Veterans
Administration