



GENERAL NOTE:

(NEW WORK STAIRWELL DRAWINGS ONLY)

CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF NEW DEVICES WITH USER PRIOR TO INSTALLATION. WHERE POSSIBLE CONTRACTOR MAY REUSE CONCEALED CONDUIT AND JUNCTION BOXES IN EXISTING WALLS FOR NEW DEVICES SHOWN TO BE INSTALLED IN SAME LOCATION. IN ROOMS WHERE PATIENT LIFTS ARE TO BE REMOVED, ELECTRICAL CONTRACTOR SHALL DISCONNECT AND REMOVE ELECTRICAL CONNECTIONS TO LIFT AND TURN OVER ANY LIFT ELECTRICAL COMPONENTS TO THE VA. IN ALL ROOMS WHERE THE EXISTING HILROM NURSE CALL DEVICES ARE BEING REMOVED, CONTRACTOR SHALL DISCONNECT, REMOVE, AND TURN OVER TO THE VA FOR THEIR USE. COORDINATE AND REPROGRAM SYSTEM AS REQUIRED. WHERE ELECTRICAL DEVICES HAVE BEEN REMOVED ON EXISTING TO REMAIN WALLS, WALLS SHALL BE REPAIRED AND PATCHED TO MATCH EXISTING NEW WALL FINISHES.

NOTES:

(THIS SHEET ONLY)

- 1 MAKE ALL CONNECTIONS TO EXISTING NORMAL POWER RECEPTACLE CIRCUIT LEFT ABANDONED IN THIS SPACE.
- 2 PROVIDE NEW DUKANE PA SPEAKER TO MATCH EXISTING PA SYSTEM AT HOSPITAL. MAKE ALL CONNECTIONS TO EXISTING PA SYSTEM AS REQUIRED.
- 3 NEW FIRE ALARM DEVICE. MAKE ALL CONNECTIONS TO EXISTING HOSPITAL ADDRESSABLE SYSTEM.
- 4 PROVIDE NEW DATA OUTLET IN THIS APPROXIMATE LOCATION. DATA DROPS SHALL BE REROUTED/CONFIGURED FROM EXISTING DATA OUTLETS BEING REMOVED IN RENOVATED SPACES.
- 5 PROVIDE NEW CABLE TELEVISION OUTLET IN THIS APPROXIMATE LOCATION. CABLE TELEVISION CABLING SHALL BE REROUTED/RECONFIGURED FROM EXISTING CABLE TELEVISION OUTLETS BEING REMOVED IN RENOVATED SPACES. PROVIDE AT 18" ABOVE FINISHED FLOOR.
- 6 NO NEW WORK IS REQUIRED IN THIS SPACE.
- 7 PROVIDE MOTOR-RATED SWITCH FOR POWER CONNECTION TO FAN COIL UNIT ABOVE CEILING. COORDINATE EXACT LOCATION AND MAKE ALL CONNECTIONS AS REQUIRED.
- 8 FLOW AND TAMPER SWITCHES IN STAIRWELLS OF ALL FLOORS.
- 9 FLOW AND TAMPER SWITCHES IN STAIRWELL OF NINTH FLOOR FOR SHAFT SPRINKLERS.
- 10 DEDICATED FIREFIGHTER TWO WAY COMMUNICATIONS PHONE OUTLET. CONTRACTOR SHALL COORDINATE EXACT LOCATION PRIOR TO INSTALLATION AND ROUTE NECESSARY CABLING BACK TO FACP AS REQUIRED FOR A COMPLETE SYSTEM.
- 11 CEILING MOUNTED SMOKE DETECTOR FOR DOOR HOLD OPEN HARDWARE. COMBINATION HOLD OPEN/CLOSER PROVIDED WITH DOOR HARDWARE.

ENLARGED FLOOR PLAN
8TH FLOOR STAIRS - ELECTRICAL POWER & MISCELLANEOUS
SCALE: 1/4" = 1'-0"

ENLARGED FLOOR PLAN
9TH FLOOR STAIRS - ELECTRICAL POWER & MISCELLANEOUS
SCALE: 1/4" = 1'-0"

1. PEER REVIEW CHANGES.	9/19/2011
Revisions	Date

Toland♦Mizell♦Molnar, LLC
590 MEANS STREET NW,
SUITE 200
ATLANTA, GA, 30318
404-214-9774



Drawing Title
EIGHT AND NINTH STAIRS ENLARGED FLOOR PLANS ELECTRICAL POWER & MISC.
Approved Project Engineer

Project Title
2ND FLOOR OUTPATIENT MENTAL HEALTH
Building Number
BLDG 1 SOUTH WING
Location
VA MEDICAL CENTER SHREVEPORT, LOUISIANA

100% REVIEW SUBMITTAL
Date
05-25-2011
Project No.
VA256-C-1047
DRAWING NO.
E407
Dwg. Of

Veterans
Administration