

SECTION 01 00 00  
GENERAL REQUIREMENTS

TABLE OF CONTENTS

1.1 GENERAL INTENTION ..... 1

1.2 STATEMENT OF BID ITEM(S)..... 2

1.3 SPECIFICATIONS AND DRAWINGS FOR CONTRACTOR ..... 2

1.4 construction security requiremenets ..... 2

1.5 FIRE SAFETY..... 2

1.6 OPERATIONS AND STORAGE AREAS ..... 5

1.7 ALTERATIONS..... 11

1.8 INFECTION PREVENTION MEASURES..... 13

1.9 DISPOSAL AND RETENTION ..... 13

1.10 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND  
IMPROVEMENTS..... 13

1.11 RESTORATION ..... 14

1.12 PHYSICAL DATA ..... 15

1.13 PROFESSIONAL SURVEYING SERVICES ..... 15

1.14 LAYOUT OF WORK..... 15

1.15 As-Built Drawings..... 15

1.16 USE OF ROADWAYS..... 15

1.17 PRECONSTRUCTION RISK ASSESSMENT ..... 16

1.18 TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT ..... 16

1.19 TEMPORARY USE OF EXISTING ELEVATORS..... 16

1.20 TEMPORARY USE OF NEW ELEVATORS..... 17

1.21 TEMPORARY TOILETS..... 17

1.22 AVAILABILITY AND USE OF UTILITY SERVICES..... 17

1.23 NEW TELEPHONE EQUIPMENT..... 19

1.24 TESTS..... 19

1.25 INSTRUCTIONS.....19

1.26 GOVERNMENT-FURNISHED PROPERTY.....20

1.27 RELOCATED EQUIPMENT OR ITEMS.....20

1.28 STORAGE SPACE FOR DEPARTMENT OF VETERANS AFFAIRS EQUIPMENT.....21

1.31 CONSTRUCTION DIGITAL IMAGES.....21

1.32 FINAL ELEVATION Digital Images.....21

1.33 HISTORIC PRESERVATION.....21

1.34 Parking.....21

1.35 I.D. Badges.....21

1.36 RADIOLOGY and bio safety.....21

1.37 construction schedule.....21

1.38 Daily Logs.....23

1.39 TB Testing Requirements.....23

1.40 Construction and Demolition Debris Management.....24

1.41 SEASONAL INFLUENZA VACCINATION.....24

**SECTION 01 00 00**  
**GENERAL REQUIREMENTS**

**1.1 GENERAL INTENTION**

- A. Contractor shall completely prepare site for building operations, including demolition and removal of existing structures, and furnish labor and materials and perform work as required by drawings and specifications.
- B. Visits to the site by Bidders may be made only by appointment with the Medical Center Engineering Officer.
- C. N/A
- D. N/A
- E. All employees of general contractor and subcontractors shall comply with VA's security program and obtain a VA ID badge from VA police. See paragraph 1.35 below for ID badge process. Along with ID Badges all workers must be able to speak and understand English during construction. Construction areas as defined by the contract documents will be keyed to a construction core when Notice to Proceed is issued. Access to non-construction areas is limited to public areas only. Access needed outside of construction area (i.e., mechanical rooms) will be provided by COTR or his/her representative upon written or verbal request.
- F. Prior to commencing work, general contractor shall provide proof that a OSHA certified "competent person" (CP) (29 CFR 1926.20(b)(2)) will maintain a presence at the work site whenever the general or subcontractors are present.
- G. Training:
  - 1. Beginning July 31, 2005, all employees of general contractor or subcontractors shall have the 10-hour OSHA certified Construction Safety course and /or other relevant competency training, as determined by VA CP with input from the ICRA team.
  - 2. In addition to the 10-hours OSHA training, VA will provide site-specific training as determined by VA Competent Person with input from the VA's Infection Control Risk Assessment team. Coordination of this required training will be accomplished through the COTR or Project Engineer. This briefing shall include information on the

construction limits, VAMC safety guidelines, means of egress, break areas, work hours, locations of restrooms, use of VAMC equipment, etc. All contractors, subcontractors, and vendors must receive this training in order to work at our facility. Failure to receive this training may cause debarment of contractor's staff until such training is accomplished.

3. Submit training records of all such employees for approval before the start of work.

H. Pre-Construction handout Dated August 2012

1. The contractor shall utilize this pre-construction packet as an orientation package to the SF VAMC facilities procedures and requirements for construction. This packet shall be reviewed by the contractor and utilized as tool to inform and educate their employees and their sub-contractors to the required procedures to be followed at the facility.

## 1.2 STATEMENT OF BID ITEM(S)

- A. ITEM I, See Scope of Work.

## 1.3 SPECIFICATIONS AND DRAWINGS FOR CONTRACTOR

01 00 00	General Requirements	11-15
02 41 00	Demolition	02-15
22 05 11	Common Work Results for Plumbing	09-15
22 05 23	General-Duty Valves for Plumbing Piping	09-15
26 05 11	Requirements for Electrical Installations	07-15
32 05 23	Cement and Concrete for Exterior Improvements	05-13

## 1.4 CONSTRUCTION SECURITY REQUIREMENTS

## 1.5 FIRE SAFETY

- A. Applicable Publications: Publications listed below form part of this Article to extent referenced. Publications are referenced in text by basic designations only.

1. American Society for Testing and Materials (ASTM):

E84-2008.....Surface Burning Characteristics of Building  
Materials

2. National Fire Protection Association (NFPA):

10-2006.....Standard for Portable Fire Extinguishers

30-2007.....Flammable and Combustible Liquids Code

51B-2003.....Standard for Fire Prevention During Welding,  
Cutting and Other Hot Work

70-2007.....National Electrical Code

241-2004.....Standard for Safeguarding Construction,  
Alteration, and Demolition Operations

3. Occupational Safety and Health Administration (OSHA):

29 CFR 1926.....Safety and Health Regulations for Construction

B. Fire Safety Plan: Establish and maintain a fire protection program in accordance with 29 CFR 1926. Prior to start of work, prepare a plan detailing project-specific fire safety measures, including periodic status reports, and submit to COTR for review for compliance with contract requirements in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES Prior to any worker for the contractor or subcontractors beginning work, they shall undergo a safety briefing provided by the general contractor's competent person per OSHA requirements. This briefing shall include information on the construction limits, VAMC safety guidelines, means of egress, break areas, work hours, locations of restrooms, use of VAMC equipment, etc. Documentation shall be provided to the COTR that individuals have undergone contractor's safety briefing.

C. Site and Building Access: Maintain free and unobstructed access to facility emergency services and for fire, police and other emergency response forces in accordance with NFPA 241.

D. Separate temporary facilities, such as trailers, storage sheds, and dumpsters, from existing buildings and new construction by distances in

accordance with NFPA 241. For small facilities with less than 6 m (20 feet) exposing overall length, separate by 3m (10 feet).

E. N/A

F. Temporary Heating and Electrical: Install, use and maintain installations in accordance with 29 CFR 1926, NFPA 241 and NFPA 70.

G. Means of Egress: Do not block exiting for occupied buildings, including paths from exits to roads. Minimize disruptions and coordinate with COTR.

H. Egress Routes for Construction Workers: Maintain free and unobstructed egress. Inspect daily. Report findings and corrective actions weekly to COTR.

I. Fire Extinguishers: Provide and maintain extinguishers in construction areas and temporary storage areas in accordance with 29 CFR 1926, NFPA 241 and NFPA 10.

J. Flammable and Combustible Liquids: Store, dispense and use liquids in accordance with 29 CFR 1926, NFPA 241 and NFPA 30.

K. Standpipes: Install and extend standpipes up with each floor in accordance with 29 CFR 1926 and NFPA 241.

L. Sprinklers: Install, test and activate new automatic sprinklers prior to removing existing sprinklers.

M. Existing Fire Protection: Do not impair automatic sprinklers, smoke and heat detection, and fire alarm systems, except for portions immediately under construction, and temporarily for connections. Provide fire watch for impairments more than 4 hours in a 24-hour period. All existing or temporary fire protection systems (fire alarms, sprinklers) located in construction areas shall be tested as coordinated with the medical center. Parameters for the testing and results of any tests performed shall be recorded by the medical center and copies provided to the COTR Engineer.

N. Smoke Detectors: Prevent accidental operation. Remove temporary covers at end of work operations each day. Coordinate with COTR.

O. Hot Work: Perform and safeguard hot work operations in accordance with NFPA 241 and NFPA 51B. Coordinate with COTR. Obtain permits from facility Safety through COTR at least 48 hours in advance. Designate

contractor's responsible project-site fire prevention program manager to permit hot work.

- P. Fire Hazard Prevention and Safety Inspections: Inspect entire construction areas weekly. Coordinate with, and report findings and corrective actions weekly to COTR.
- Q. Smoking: Smoking is prohibited in and adjacent to construction areas inside existing buildings and additions under construction. In separate and detached buildings under construction, smoking is prohibited except in designated smoking rest areas.
- R. Dispose of waste and debris in accordance with NFPA 241. Remove from buildings daily.
- S. Perform other construction, alteration and demolition operations in accordance with 29 CFR 1926.
- T. If required, submit documentation to the COTR that personnel have been trained in the fire safety aspects of working in areas with impaired structural or compartmentalization features.
- U. Above Ceiling Permit: Contractors are restricted from working above ceiling without the required Above Ceiling Permit. This required when working above any ceilings in the Medical Center outside of contained construction areas.
- V. Temporary Electrical: Contractors are not allowed to use power supplied VA unless approved by COTR. If approved, use and installations shall be in accordance with 29 CFR 1926, NFPA 241 and NFPA 70. At no time will VA approve temporary power connection from a critical electrical circuit.

#### **1.6 OPERATIONS AND STORAGE AREAS**

- A. The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the COTR. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.
- B. Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the COTR and shall be built with labor and materials furnished by the Contractor

without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

- C. The Contractor shall, under regulations prescribed by the COTR, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.
- D. Working space and space available for storing materials shall be as shown on the drawings or as determined by the COTR.
- E. Workmen are subject to rules of Medical Center applicable to their conduct. Execute work in such a manner as to interfere as little as possible with work being done by others. Keep roads clear of construction materials, debris, standing construction equipment and vehicles at all times.
- F. Execute work so as to interfere as little as possible with normal functioning of Medical Center as a whole, including operations of utility services, fire protection systems and any existing equipment, and with work being done by others. Use of equipment and tools that transmit vibrations and noises through the building structure, are not permitted in buildings that are occupied, during construction, jointly by patients or medical personnel, and Contractor's personnel, except as permitted by COTR where required by limited working space.
  - 1. Do not store materials and equipment in other than assigned areas.
  - 2. Schedule delivery of materials and equipment to immediate construction working areas within buildings in use by Department of Veterans Affairs in quantities sufficient for not more than four work days. Provide unobstructed access to Medical Center areas required to remain in operation.



3. Where access by Medical Center personnel to vacated portions of buildings is not required, storage of Contractor's materials and equipment will be permitted subject to fire and safety requirements.
- G. Construction Safety Rounds: VA will perform Construction Safety Rounds weekly. Contractor superintendent or Contractor's Competent Person will be present during these safety inspections. COTR will identify the date and time of these weekly inspections.
- H. Phasing: To insure such executions, Contractor shall furnish the COTR with a schedule of approximate phasing dates on which the Contractor intends to accomplish work in each specific area of site, building or portion thereof. In addition, Contractor shall notify the COTR two weeks in advance of the proposed date of starting work in each specific area of site, building or portion thereof. Arrange such phasing dates to insure accomplishment of this work in successive phases mutually agreeable to Medical Center Director, COTR and Contractor, as follows:
- I. N/A
- J. Construction Fence: Before construction operations begin, Contractor shall provide a chain link construction fence, 2.1m (seven feet) minimum height, around the construction area indicated on the drawings. Provide gates as required for access with necessary hardware, including hasps and padlocks. Fasten fence fabric to terminal posts with tension bands and to line posts and top and bottom rails with tie wires spaced at maximum 375mm (15 inches). Bottom of fences shall extend to 25mm (one inch) above grade. Remove the fence when directed by COTR Engineer.
- K. When a building is turned over to Contractor, Contractor shall accept entire responsibility therefore.
1. Contractor shall maintain a minimum temperature of 4 degrees C (40 degrees F) at all times, except as otherwise specified.
  2. Contractor shall maintain in operating condition existing fire protection and alarm equipment. In connection with fire alarm equipment, Contractor shall make arrangements for pre-inspection of site with Fire Department or Company (Department of Veterans Affairs or municipal) whichever will be required to respond to an alarm from Contractor's employee or watchman.
- L. Utilities Services: Maintain existing utility services for Medical Center at all times. Provide temporary facilities, labor, materials,

equipment, connections, and utilities to assure uninterrupted services. Where necessary to cut existing water, steam, gases, sewer or air pipes, or conduits, wires, cables, etc. of utility services or of fire protection systems and communications systems (including telephone), they shall be cut and capped at suitable places where shown; or, in absence of such indication, where directed by COTR.

1. No utility service such as water, gas, steam, sewers or electricity, or fire protection systems and communications systems may be interrupted without prior approval of COTR. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished, work on any energized circuits or equipment shall not commence without the Medical Center Director's prior knowledge and written approval. Refer to specification Sections 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, 27 05 11 REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS and 28 05 11, REQUIREMENTS FOR ELECTRONIC SAFETY AND SECURITY INSTALLATIONS for additional requirements.
2. Contractor shall submit a request to interrupt any such services to COTR, in writing, 7 DAYS in advance of proposed interruption. Request shall state reason, date, exact time of, and approximate duration of such interruption.
3. Contractor will be advised (in writing) of approval of request, or of which other date and/or time such interruption will cause least inconvenience to operations of Medical Center. Interruption time approved by Medical Center may occur at other than Contractor's normal working hours.
4. Major interruptions of any system must be requested, in writing, at least 15 calendar days prior to the desired time and shall be performed as directed by the COTR.
5. In case of a contract construction emergency, service will be interrupted on approval of COTR. Such approval will be confirmed in writing as soon as practical.
6. Whenever it is required that a connection fee be paid to a public utility provider for new permanent service to the construction project, for such items as water, sewer, electricity, gas or steam, payment of such fee shall

- M. Abandoned Lines: All service lines such as wires, cables, conduits, ducts, pipes and the like, and their hangers or supports, which are to be abandoned but are not required to be entirely removed, shall be sealed, capped or plugged. The lines shall not be capped in finished areas, but shall be removed and sealed, capped or plugged in ceilings, within furred spaces, in unfinished areas, or within walls or partitions; so that they are completely behind the finished surfaces.
- N. To minimize interference of construction activities with flow of Medical Center traffic, comply with the following:
1. Keep roads, walks and entrances to grounds, to parking and to occupied areas of buildings clear of construction materials, debris and standing construction equipment and vehicles. Wherever excavation for new utility lines cross existing roads, at least one lane must be open to traffic at all times.
  2. Method and scheduling of required cutting, altering and removal of existing roads, walks and entrances must be approved by the COTR.
- O. Coordinate the work for this contract with other construction operations as directed by Resident Engineer. This includes the scheduling of traffic and the use of roadways, as specified in Article, USE OF ROADWAYS.
- P. CONTRACT WORK HOURS and FEDERAL HOLIDAYS:
- (a). Standard daily contract work hours at the San Francisco VA Medical Center (SFVAMC) are from 7:30 AM to 7:00 PM, Pacific Standard Time (PST), Monday through Friday, with the exception of Federal Holidays. The contractor shall submit to the Contracting Officer (CO) for approval, in writing, a notice of its desire to work during any period/hours other than the standard. Notice shall include a detailed description of the type of work to be performed and its location. These "non-standard" hours are referred to as "WHEN Hours" (Weekend-Holiday-Evening-Night). The notice requesting work during WHEN hours shall be submitted not less than three (3) working days prior to each period of work scheduled at times other than normal duty hours to include Federal holidays. Contractors are reminded that patients are generally asleep after 10:00 PM EST. Therefore, approval is subject to the availability of the project manager/COTR, the type of work to be performed, the specific hours requested, and the anticipated noise level that will be generated by contractor activity. Under no circumstance will the contractor proceed without express written approval

of the Contracting Officer. When weekend work is approved by the COTR, work shall be limited to 8 am to 6 pm construction period weekends, any time outside of that window will be considered evening or night work and will require its own approval.

1. Work Phasing/Scheduling: Contractor shall work closely with the COTR in developing a work schedule for contract performance. Simultaneous or transitional work on/between multiple facilities may be required. Advance coordination by the contractor is critical and required. **Note**, Concurrent work performance is anticipated on all line items for this project.
2. The work to be performed on this project will include occupied areas, however arrangements may be made so that the particular area may be blocked off during performance of work if feasible. The contractor shall notify the COTR of intent to start work in any specific assigned area. The contractor shall coordinate the work of all activities whereby both the Government and the contractor can continue operations with the least possible interference and inconvenience.
3. The contractor is required to have a minimum of crews for work covered by this contract, and provide additional crew(s) as the work justifies. Each crew shall be capable of operating simultaneously and independently of the other crew(s).
4. The following is a list of Federal Holidays observed by all Federal Installations:

New Year's Day, January 1  
Martin Luther King, Jr, 3rd Monday in January  
Washington's Birthday, 3rd Monday in February  
Memorial Day, Last Monday in May  
Independence Day, July 4  
Labor Day, 1st Monday in September  
Columbus Day, 2nd Monday in September  
Veterans Day, November 11  
Thanksgiving Day, 4th Thursday in November  
Christmas Day, December 25

NOTE: Any of the above holidays falling on a Saturday will be observed on the preceding Friday; holidays falling on a Sunday will be observed on the following Monday. Also included is any date

specifically declared by the President of the United States of America as a National Holiday.

5. No deliveries of construction equipment, materials, HVAC equipment, dumpsters (or pick up of dumpsters), cranes, concrete trucks, etc. before 7:30 am on the weekdays and 8 am on the weekends. Exception will be for oversize loads that require delivery before a certain time due to permitting conditions, and shall require a minimum of 3 days notice to the COTR prior to arrival at SF VAMC. No contractor vehicles, delivery vehicle, cranes, concrete trucks, hauling trucks, etc will be staged within 500 yards of the SF VAMC prior to driving onto SF VAMC grounds.

#### **1.7 ALTERATIONS**

- A. Survey: Before any work is started, the Contractor shall make a thorough survey with the COTR, of areas of buildings in which alterations occur and areas which are anticipated routes of access, and furnish a report, signed by both, to the Contracting Officer. This report shall list by rooms and spaces.
- B. Any items required by drawings to be either reused or relocated or both, found during this survey to be nonexistent, or in opinion of COTR and/or Supply Representative to be in such condition that their use is impossible or impractical, shall be furnished and/or replaced by Contractor with new items in accordance with specifications which will be furnished by Government. Provided the contract work is changed by reason of this subparagraph B, the contract will be modified accordingly, of Section 00 72 00, GENERAL CONDITIONS.
- C. Re-Survey: Thirty days before expected partial or final inspection date, the Contractor and COTR together shall make a thorough re-survey of the areas of buildings involved. They shall furnish a report on conditions then existing, of resilient flooring, doors, windows, walls and other surfaces as compared with conditions of same as noted in first condition survey report:
  - 1. Re-survey report shall also list any damage caused by Contractor to such flooring and other surfaces, despite protection measures; and, will form basis for determining extent of repair work required of Contractor to restore damage caused by Contractor's workmen in executing work of this contract.

D. Protection: Provide the following protective measures:

1. Wherever existing roof surfaces are disturbed they shall be protected against water infiltration. In case of leaks, they shall be repaired immediately upon discovery.
2. Temporary protection against damage for portions of existing structures and grounds where work is to be done, materials handled and equipment moved and/or relocated.
3. Protection of interior of existing structures at all times, from damage, dust and weather inclemency. Wherever work is performed, floor surfaces that are to remain in place shall be adequately protected prior to starting work, and this protection shall be maintained intact until all work in the area is completed.

E. Construction Barriers:

F. Final Cleanup:

1. Upon completion of project, or as work progresses, remove all construction debris from above ceiling, vertical shafts and utility chases that have been part of the construction.

G. Disposal and Retention: Materials and equipment accruing from work removed and from demolition of buildings or structures, or parts thereof, shall be disposed of as follows:

1. Reserved items which are to remain property of the Government are identified by attached tags or noted on drawings or in specifications as items to be stored. Items which remain property of the Government shall be removed or dislodged from present locations in such a manner as to prevent damage which would be detrimental to re-installation and reuse. Store such items where directed by Resident Engineer.
2. Items not reserved shall become property of the Contractor and be removed by Contractor from Medical Center.
3. Items of portable equipment and furnishings located in rooms and spaces in which work is to be done under this contract shall remain the property of the Government. When rooms and spaces are vacated by the Department of Veterans Affairs during the alteration period, such items which are NOT required by drawings and specifications to be

either relocated or reused will be removed by the Government in advance of work to avoid interfering with Contractor's operation.

#### **1.8 INFECTION PREVENTION MEASURES**

#### **1.9 DISPOSAL AND RETENTION**

A. Materials and equipment accruing from work removed and from demolition of buildings or structures, or parts thereof, shall be disposed of as follows:

1. Reserved items which are to remain property of the Government are identified by attached tags or noted on drawings or in specifications as items to be stored. Items that remain property of the Government shall be removed or dislodged from present locations in such a manner as to prevent damage which would be detrimental to re-installation and reuse. Store such items where directed by COTR.
2. Items not reserved shall become property of the Contractor and be removed by Contractor from Medical Center.
3. Items of portable equipment and furnishings located in rooms and spaces in which work is to be done under this contract shall remain the property of the Government. When rooms and spaces are vacated by the Department of Veterans Affairs during the alteration period, such items which are NOT required by drawings and specifications to be either relocated or reused will be removed by the Government in advance of work to avoid interfering with Contractor's operation.

#### **1.10 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS**

A. The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the COTR.

- B. The Contractor shall protect from damage all existing improvements and utilities at or near the work site and on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the COTR may have the necessary work performed and charge the cost to the Contractor.
- C. For additional requirements on protecting vegetation, soils and the environment. Refer to Articles, "Alterations", "Restoration", and "Operations and Storage Areas" for additional instructions concerning repair of damage to structures and site improvements.

#### **1.11 RESTORATION**

- A. Remove, cut, alter, replace, patch and repair existing work as necessary to install new work. Except as otherwise shown or specified, do not cut, alter or remove any structural work, and do not disturb any ducts, plumbing, steam, gas, or electric work without approval of the Resident Engineer. Existing work to be altered or extended and that is found to be defective in any way, shall be reported to the COTR before it is disturbed. Materials and workmanship used in restoring work, shall conform in type and quality to that of original existing construction, except as otherwise shown or specified.
- B. Upon completion of contract, deliver work complete and undamaged. Existing work (walls, ceilings, partitions, floors, mechanical and electrical work, lawns, paving, roads, walks, etc.) disturbed or removed as a result of performing required new work, shall be patched, repaired, reinstalled, or replaced with new work, and refinished and left in as good condition as existed before commencing work.
- C. At Contractor's own expense, Contractor shall immediately restore to service and repair any damage caused by Contractor's workmen to existing piping and conduits, wires, cables, etc., of utility services or of fire protection systems and communications systems (including telephone) which are indicated on drawings and which are not scheduled for discontinuance or abandonment.



- D. Expense of repairs to such utilities and systems not shown on drawings or locations of which are unknown will be covered by adjustment to contract time and price in accordance of Section 00 72 00, GENERAL CONDITIONS.

#### **1.12 PHYSICAL DATA**

#### **1.13 PROFESSIONAL SURVEYING SERVICES**

#### **1.14 LAYOUT OF WORK**

#### **1.15 AS-BUILT DRAWINGS**

- A. The contractor shall maintain two full size sets of as-built drawings which will be kept current during construction of the project, to include all contract changes, modifications and clarifications.
- B. All variations shall be shown in the same general detail as used in the contract drawings. To insure compliance, as-built drawings shall be made available for the COTR'S review, as often as requested.
- C. Contractor shall deliver two approved completed sets of as-built drawings to the COTR within 15 calendar days after each completed phase and after the acceptance of the project by the COTR.
- D. Paragraphs A, B, & C shall also apply to all shop drawings.

#### **1.16 USE OF ROADWAYS**

- A. For hauling, use only established public roads and roads on Medical Center property and, when authorized by the COTR, such temporary roads which are necessary in the performance of contract work. Temporary roads shall be constructed by the Contractor at Contractor's expense. When necessary to cross curbing, sidewalks, or similar construction, they must be protected by well-constructed bridges.
- B. When new permanent roads are to be a part of this contract, Contractor may construct them immediately for use to facilitate building operations. These roads may be used by all who have business thereon within zone of building operations.

- C. When certain buildings (or parts of certain buildings) are required to be completed in advance of general date of completion, all roads leading thereto must be completed and available for use at time set for completion of such buildings or parts thereof.

#### **1.17 PRECONSTRUCTION RISK ASSESSMENT**

#### **1.18 TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT**

#### **1.19 TEMPORARY USE OF EXISTING ELEVATORS**

- A. Use of existing elevator for handling building materials and Contractor's personnel will be permitted subject to following provisions:
1. Contractor makes all arrangements with the Resident Engineer for use of elevators. The Resident Engineer will ascertain that elevators are in proper condition.
  2. Contractor covers and provides maximum protection of following elevator components:
    - a. Entrance jambs, heads soffits and threshold plates.
    - b. Entrance columns, canopy, return panels and inside surfaces of car enclosure walls.
    - c. Finish flooring.
  3. Government will accept hoisting ropes of elevator and rope of each speed governor if they are worn under normal operation. However, if these ropes are damaged by action of foreign matter such as sand, lime, grit, stones, etc., during temporary use, they shall be removed and replaced by new hoisting ropes.
  4. If brake lining of elevators are excessively worn or damaged during temporary use, they shall be removed and replaced by new brake lining.
  5. All parts of main controller, starter, relay panel, selector, etc., worn or damaged during temporary use shall be removed and replaced

with new parts, if recommended by elevator inspector after elevator is released by Contractor.

6. Place elevator in condition equal, less normal wear, to that existing at time it was placed in service of Contractor as approved by Contracting Officer.

#### **1.20 TEMPORARY USE OF NEW ELEVATORS**

#### **1.21 TEMPORARY TOILETS**

- A. Provide where directed, (for use of all Contractor's workmen) ample temporary sanitary toilet accommodations with suitable sewer and water connections; or, when approved by COTR, provide suitable dry closets where directed. Keep such places clean and free from flies, and all connections and appliances connected therewith are to be removed prior to completion of contract, and premises left perfectly clean.
- B. Contractor may have for use of Contractor's workmen, such toilet accommodations as may be assigned to by Medical Center or COTR. Contractor shall keep such places clean and be responsible for any damage done thereto by Contractor's workmen. Failure to maintain satisfactory condition in toilets will deprive Contractor of the privilege to use such toilets.

#### **1.22 AVAILABILITY AND USE OF UTILITY SERVICES**

- A. The Government shall make all reasonably required amounts of utilities available to the Contractor from existing outlets and supplies, as specified in the contract. The amount to be paid by the Contractor for chargeable electrical services shall be the prevailing rates charged to the Government. The Contractor shall carefully conserve any utilities furnished without charge.
- B. The Contractor, at Contractor's expense and in a workmanlike manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines, and all meters required to measure the amount of electricity used for the purpose of determining charges. Before final acceptance of the work by the Government, the Contractor shall remove all the temporary connections, distribution lines, meters, and associated paraphernalia.

- C. Contractor shall install meters at Contractor's expense and furnish the Medical Center a monthly record of the Contractor's usage of electricity as hereinafter specified.
- D. Heat: Furnish temporary heat necessary to prevent injury to work and materials through dampness and cold. Use of open salamanders or any temporary heating devices which may be fire hazards or may smoke and damage finished work, will not be permitted. Maintain minimum temperatures as specified for various materials:
1. Obtain heat by connecting to Medical Center heating distribution system.
    - a. Steam is available at no cost to Contractor.
- E. Electricity (for Construction and Testing): Furnish all temporary electric services.
1. Obtain electricity by connecting to the Medical Center electrical distribution system. The Contractor shall meter and pay for electricity required for electric cranes and hoisting devices, electrical welding devices and any electrical heating devices providing temporary heat. Electricity for all other uses is available at no cost to the Contractor.
- F. Water (for Construction and Testing): Furnish temporary water service.
1. Obtain water by connecting to the Medical Center water distribution system. Provide reduced pressure backflow preventer at each connection. Water is available at no cost to the Contractor.
  2. Maintain connections, pipe, fittings and fixtures and conserve water-use so none is wasted. Failure to stop leakage or other wastes will be cause for revocation (at COTR's discretion) of use of water from Medical Center's system.
- G. Steam: Furnish steam system for testing required in various sections of specifications.
1. Obtain steam for testing by connecting to the Medical Center steam distribution system. Steam is available at no cost to the Contractor.
  2. Maintain connections, pipe, fittings and fixtures and conserve steam-use so none is wasted. Failure to stop leakage or other waste

will be cause for revocation (at COTR's discretion), of use of steam from the Medical Center's system.

- H. Fuel: Natural and LP gas and burner fuel oil required for boiler cleaning, normal initial boiler-burner setup and adjusting, and for performing the specified boiler tests will be furnished by the Government. Fuel required for prolonged boiler-burner setup, adjustments, or modifications due to improper design or operation of boiler, burner, or control devices shall be furnished by the Contractor at Contractor's expense.

#### **1.23 NEW TELEPHONE EQUIPMENT**

The contractor shall coordinate with the work of installation of telephone equipment by others. This work shall be completed before the building is turned over to VA.

#### **1.24 TESTS**

- A. Pre-test mechanical and electrical equipment and systems and make corrections required for proper operation of such systems before requesting final tests. Final test will not be conducted unless pre-tested.
- B. Conduct final tests required in various sections of specifications in presence of an authorized representative of the Contracting Officer. Contractor shall furnish all labor, materials, equipment, instruments, and forms, to conduct and record such tests.
- C. Mechanical and electrical systems shall be balanced, controlled and coordinated. A system is defined as the entire complex which must be coordinated to work together during normal operation to produce results for which the system is designed. For example, air conditioning supply air is only one part of entire system which provides comfort conditions for a building. Other related components are return air, exhaust air, steam, chilled water, refrigerant, hot water, controls and electricity, etc. Another example of a complex which involves several components of different disciplines is a boiler installation. Efficient and acceptable boiler operation depends upon the coordination and proper operation of fuel, combustion air, controls, steam, feedwater, condensate and other related components.
- D. All related components as defined above shall be functioning when any system component is tested. Tests shall be completed within a reasonably

short period of time during which operating and environmental conditions remain reasonably constant.

- E. Individual test result of any component, where required, will only be accepted when submitted with the test results of related components and of the entire system.

#### **1.25 INSTRUCTIONS**

#### **1.26 GOVERNMENT-FURNISHED PROPERTY**

#### **1.27 RELOCATED EQUIPMENT OR ITEMS**

- A. Contractor shall disconnect, dismantle as necessary, remove and reinstall in new location, all existing equipment and items indicated by symbol "R" or otherwise shown to be relocated by the Contractor.
- B. Perform relocation of such equipment or items at such times and in such a manner as directed by the COTR.
- C. Suitably cap existing service lines, such as steam, condensate return, water, drain, gas, air, vacuum and/or electrical, whenever such lines are disconnected from equipment to be relocated. Remove abandoned lines in finished areas and cap as specified herein before under paragraph "Abandoned Lines".
- D. Provide all mechanical and electrical service connections, fittings, fastenings and any other materials necessary for assembly and installation of relocated equipment; and leave such equipment in proper operating condition.
- E. Contractor shall employ services of an installation engineer, who is an authorized representative of the manufacturer of this equipment to supervise assembly and installation of existing equipment, required to be relocated.
- F. All service lines such as noted above for relocated equipment shall be in place at point of relocation ready for use before any existing equipment is disconnected. Make relocated existing equipment ready for operation or use immediately after reinstallation.

**1.28 STORAGE SPACE FOR DEPARTMENT OF VETERANS AFFAIRS EQUIPMENT****1.31 CONSTRUCTION DIGITAL IMAGES****1.32 FINAL ELEVATION DIGITAL IMAGES****1.33 HISTORIC PRESERVATION**

Where the Contractor or any of the Contractor's employees, prior to, or during the construction work, are advised of or discover any possible archeological, historical and/or cultural resources, the Contractor shall immediately notify the Resident Engineer verbally, and then with a written follow up.

**1.34 PARKING**

There will be no parking space on site available to the contractor for staging, container, debris box, or any motor vehicle.

**1.35 I.D. BADGES**

All workers are required to obtain a time-limited I. D. badge from the VA Police Service located on the ground floor of Building 203. This badge must be worn at all times when workers are on site.

**1.36 RADIOLOGY AND BIO SAFETY****1.37 CONSTRUCTION SCHEDULE**

- A. The Contractor shall develop a Construction Schedule demonstrating fulfillment of contract requirements, shall keep the schedule up-to-date as required in this Article, and shall utilize the schedule for coordinating and monitoring work under the Contract (including activities of subcontractors, vendors, and suppliers). The schedule shall be prepared in the format of a Gantt or Bar Chart, utilizing Microsoft Project or similar computer application, subject to approval by the Resident Engineer.
- B. Within 10 calendar days after receipt of Notice to Proceed, the Contractor shall submit a complete Construction Schedule for review by the Contracting Officer under provisions of Section 01340, SAMPLES AND SHOP DRAWINGS. Submit three copies on sheets of paper 750 mm by 1050 mm

(30 by 42 inches). Within 10 calendar days of receipt of the Construction Schedule, the Contracting Officer or his representative will return the submittal with any comments or objections, and if appropriate, schedule a meeting with the Contractor for joint review, correction, or adjustment of the schedule. Within 14 calendar days after the later of the return of the submittal or the joint review meeting, the Contractor shall revise and submit three copies of the revised schedule for the Contracting Officer's approval.

- C. The Construction Schedule shall show construction activities in sufficient detail to monitor work progress, to support application and certificates for payment, and to coordinate submittal review, inspection, and other activities of the Resident Engineer and his consultants. As a minimum, it will contain the level of detail shown in the Sample Construction Schedule Drawing CS-1, which is a sample only, derived from a different project and not to be used as is for this project. Activities shall be identified by trade and nature of task, and shall show durations for the activity from allowable early-start and late-start to early-finish and late-finish, with graphic distinctions between these durations made by color or pattern.
- D. The Contractor shall update the Construction Schedule on a monthly basis, and shall submit an updated schedule with each payment request. Monthly job progress meetings shall be held on dates mutually agreed to by the Contracting Officer, or his representative, and the Contractor. An updated schedule shall be furnished by the Contractor to the VA at least three working days prior to the meeting. At the meeting, job progress will be reviewed to verify: actual start or finish dates for activities completed or in progress; remaining duration required to complete activities in progress or scheduled to start; and percentage complete for activities in progress. Any changes required to the schedule due to discrepancies between actual job progress and the schedule shall be reported by the Contractor, reviewed, and submitted for approval to the Contracting Officer. Any corrective actions in terms of increased manpower, shift hours, work days, or other measures necessary to maintain phasing or contract completion dates shall be reported by the Contractor, reviewed, and included in proposed schedule changes.
- E. Contractor shall install and post the construction signs at the entrance to the construction area. Sign shall include the Contractor name, telephone number.



**1.38 DAILY LOGS**

- A. Permit and Daily Construction check list
- B. Workers present and work taking place during day at project.
- C. Egress Routes for Construction Workers should be inspected daily.  
Report the findings and corrective actions weekly to the COTR.

**1.39 TB TESTING REQUIREMENTS**

- A. The contractor shall be responsible for providing written documentation that all of his employees and subcontractor employees that will be working within the identified areas of the Medical Center have a PPD tuberculin skin test (TST Testing) for the purpose of Tuberculosis screening within the last 12 months prior to starting work at the San Francisco VA Medical Center. The contractor shall insure that those individuals keep current annual test results throughout the duration of the project. The contractor is responsible to insure these documents are kept current and are readily available for review upon request. The Contractor shall provide this written document to the Contracting officer (CO) or Contracting Officer's Representative (COR) naming their employees or subcontractor employees, the date they were tested and the PPD Skin Test results. Documentation of where the test was performed is also required. If the employee has never had a PPD Skin Test then a two-step skin test or an FDA approved Quantiferon blood test is required.
- B. If the employee or the subcontractor employee test results are positive or their PPD Skin Test has been found to be positive in the past, the contractor is required to also state in writing if the employee was treated for latent Tuberculosis with INH. If the employee is a new PPD Skin Test Converter, a Chest X-Ray is required with proper documented results. The identified areas at the San Francisco VAMC that require these documented tests and results as part of the contract are:

**Buildings 1 (Ground Floor only), Buildings 8, 200, 203, and 208.**

#### 1.40 CONSTRUCTION AND DEMOLITION DEBRIS MANAGEMENT

This project requires compliance with the City of San Francisco's Ordinance # 27-06 for managing construction and demolition debris, where at least 65% can be reused/recycled and diverted away from the landfill. Compliance with this City Ordinance can be accomplished through using a registered transporter and registered facility for managing the construction/demolition debris. For more information, check out the following websites listed below:

Link to General website:

[http://www.sfenvironment.org/our\\_programs/interests.html?ssi=3&ti=5&ii=125](http://www.sfenvironment.org/our_programs/interests.html?ssi=3&ti=5&ii=125)

The link to the City Ordinance:

<http://www.sfenvironment.org/downloads/library/ondemolitionordinancefinal.pdf>

Link to "registered transporter":

[http://www.sfenvironment.org/downloads/library/cd\\_registered\\_transporters\\_102008.pdf](http://www.sfenvironment.org/downloads/library/cd_registered_transporters_102008.pdf)

Link to "registered facility":

<http://www.sfenvironment.org/downloads/library/registeredfacilities052108.pdf>

#### 1.41 SEASONAL INFLUENZA VACCINATION

Seasonal influenza vaccination is the single best way to prevent the spread of influenza in healthcare settings. It is the policy of this Medical Center that any contractor working in buildings 8, 203, 208, 200 (defined as patient care areas) must show evidence of receiving a flu shot during the flu season or wear an ordinary loop mask while working within 6 feet of the breathing zone of any patient. The contractor will be responsible for insuring its employees have had these vaccinations while performing work between in p[atient care define areas between the dates of November 1<sup>st</sup> to March 31<sup>st</sup>. Flu vaccination can be done at an outside provider or in the VASF Occupational Health at no charge. Proof of vaccination must be shown to the Project Engineer prior to start of

work using the self-certification form for each employee that will working in the defined patient care area at the SF VAMC during the defined timeline.

- - - E N D - - -