

PLANNING

ARCHITECTURE

ENGINEERING

INTERIORS



EST. 1915

ATLANTA
AUSTIN
BRYAN
DALLAS
DENVER
FORTH WORTH
HONG KONG
HONOLULU
HOUSTON
ISTANBUL
LAS VEGAS
LOS ANGELES8
MIAMI
MINNEAPOLIS
OMAHA
PHOENIX
SAN ANTONIO
SAN MARCOS
TIANJIN
WACO
WASHINGTON, DC

DATE: June 13, 2016

PROJECT NAME: VA CBOC Chula Vista

PROJECT NO.: Task Order # VA101F-15-J-0051
Project No. 046-10065-001

ADDENDUM NO.: H

The following changes, additions and / or deletions shall be made to the documents listed below. All other conditions shall remain unchanged.

H.1 See additional hardware sets:

HW 1L

1 Continuous Hinge	
1 Latchset	F04
1 Kick Plate	J102
1 Wall Stop	L02101 CONVEX
1 Threshold	J32300 x 57 MM WIDTH (2-1/4 INCHES)
1 Auto Door Bottom	R0Y346 – HEAVY DUTY
2 Sets Self-Adhesive Seals	R0Y154

HW 3B

Hinges	QUANTITY & TYPE AS REQUIRED
1 Office Lock	F04
1 Closer	C02011/C02021
1 Floor Stop	L02121 x 3 FASTENERS
1 Door Viewer	L03221 – 190° (VIEW INTO CORRIDOR)
1 Set Self-Adhesive Seals	R0Y154

OMIT VIEWER IF DOOR PROVIDED WITH VISION LITE.

PLANNING

ARCHITECTURE

ENGINEERING

INTERIORS



EST. 1915

ATLANTA

AUSTIN

DALLAS

FORT WORTH

HONG KONG

HONOLULU

HOUSTON

LAS VEGAS

LOS ANGELES

MIAMI

MINNEAPOLIS

OMAHA

PHOENIX

SAN ANTONIO

WACO

WASHINGTON, DC

HW 4L

1 Continuous Hinge

1 Classroom Lock

1 Kick Plate

1 Edge Guard (@ Wood Doors)

1 Floor Stop

1 Threshold

1 Auto Door Bottom

1 Set Sound/Light Seals

x INTEGRAL HINGE GUARD CHANNEL

X ADJUSTA-SCREWS

F08

J102

J208M / J211 (VERIFY), CUT:

HARDWARE

L02121 x 3 FASTENERS

J32300 x 57 MM WIDTH (2-1/4

INCHES)

R0Y346 – HEAVY DUTY

R0Y264/R0Y255

HW SH-2

1 Continuous Hinge

1 Door Pull w/ Plate

1 Lock

1 Strike/Keeper

1 Overhead Stop

1 Door Position Switch

J401 x J302

DETENTION TYPE LOCK

AS REQUIRED

C01541-ADJUSTABLE X SEC. TORX

HW SH-3B (RATED)

1 Continuous Hinge

1 Push-button Combination Lock

1 Closer

1 Kick Plate

1 Mop Plate (@ Inswing Doors)

1 Floor Stop

1 Set Self-Adhesive Seals

N3 – A156.13 F07 G1 E06

C02011/C02021

J102

J103

L02121 x 3 FASTENERS

R0Y154

HW SH-3C

1 Continuous Hinge

1 Push-button Combination Lock

1 Closer

1 Armor Plate

1 Edge Guard (@ Wood Doors)

1 Floor Stop

1 Set Self-Adhesive Seals

x INTEGRAL HINGE GUARD

CHANNEL X ADJUSTA-SCREWS

N3 – A156.13 F07 G1 E06

C02011/C02021

J101 x 1.275 MM (0.050 INCH)

THICKNESS

J208M / J211 (VERIFY), CUT:

HARDWARE

L02121 x 3 FASTENERS

R0Y154

--- End of Memo ---