

**SECTION 01 57 19**  
**TEMPORARY ENVIRONMENTAL CONTROLS**

**PART 1 GENERAL**

**1.1 DESCRIPTION**

- A. This section specifies the control of environmental pollution and damage that the Contractor must consider for air, water, and land resources. It includes management of visual aesthetics, noise, and solid waste, as well as other pollutants and resources encountered or generated by the Contractor. The Contractor is obligated to consider specified control measures with the costs included within the various contract items of work.
- B. Environmental pollution and damage is defined as the presence of chemical, physical, or biological elements or agents which:
  - 1. Adversely effect human health or welfare.
  - 2. Unfavorably alter ecological balances of importance to human life.
  - 3. Effect other species of importance to humankind.
  - 4. Degrade the utility of the environment for aesthetic, cultural, and historical purposes.

**1.2 DEFINITIONS OF POLLUTANTS**

- A. Chemical Waste: Petroleum products, bituminous materials, salts, acids, alkalis, herbicides, pesticides, organic chemicals, and inorganic wastes.
- B. Debris: Combustible and noncombustible wastes, such as leaves, tree trimmings, ashes, and waste materials resulting from construction or maintenance and repair work.
- C. Sediment: Soil and other debris that has been eroded and transported by runoff water.
- D. Solid Waste: Rubbish, debris, garbage, and other discarded solid materials resulting from project construction activities.
- E. Surface Discharge: The term "Surface Discharge" implies that the water is discharged with possible sheeting action and subsequent soil erosion may occur. Waters that are surface discharged may terminate in drainage ditches, storm sewers, creeks, and/or "waters of the United States" and require a permit to discharge water from the governing agency.
- F. Rubbish: Combustible and noncombustible wastes such as, but not limited to, paper, plastic, metal and plastic containers and cans, boxes, metal and lumber scrap, .
- G. Sanitary Wastes: Domestic Sanitary Sewage.

### 1.3 QUALITY CONTROL

- A. Contractor shall establish and maintain quality control for the environmental protection of all items set forth herein.
- B. Contractor shall record on daily reports any problems in complying with laws, regulations, ordinances and note any corrective action taken.

### 1.4 REFERENCES

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.
- B. U.S. National Archives and Records Administration (NARA):  
33 CFR 328.....Definitions, Waters of the United States.
- C. Federal Environmental Regulatory Requirements: Comply with applicable regulations. The following is for Contractor's information only:
  - 1. Storm water permits; refer to The Office of Wastewater Management, NPDES Storm Water Program: <http://www.epa.gov/npdes/stormwater>
  - 2. Dredge and fill (Section 404) permits; refer to U.S. EPA Office of Wetlands, Oceans, and Watersheds (OWOW): <http://www.epa.gov/owow/>
  - 3. RCRA hazardous and non-hazardous solid waste requirements; refer to EPA's Office of Solid Waste and Emergency Response:  
<http://www.epa.gov/epaoswer/osw/laws-reg.htm>
  - 4. Oil spill requirements for construction activities; refer to EPA Oil Program web site: <http://www.epa.gov/oilspill/>
  - 5. Hazardous substances (Superfund Liability) requirements for construction activities; refer to EPA's Superfund website:  
<http://www.epa.gov/superfund/index.htm>
  - 6. Polychlorinated Biphenyl (PCB) waste requirements; refer to EPA's Polychlorinated Biphenyl (PCB) Homepage: <http://www.epa.gov/pcb/>
  - 7. Air quality requirements for construction activities; refer to EPA'S Air Program Mobile Sources Page:  
<http://www.epa.gov/ebtpages/airmobilesources.html>
  - 8. Asbestos requirements for construction activities; refer to EPA's Asbestos Management and Regulatory Requirements Website:  
<http://www.epa.gov/fedsite/cd/asbestos.html>
  - 9. National Environmental Policy Act (NEPA) requirements for construction activities
  - 10. Endangered Species Act; refer to The US Fish and Wildlife Service Endangered Species Program: <http://endangered.fws.gov/>
  - 11. National Historic Preservation Act

C. State and Local Environmental Regulatory Requirements: Comply with applicable regulations. The following is for Contractor's information only:

1. State Office/Department of Environmental Quality.
2. Local Office/Department of Environmental Quality.
3. The Construction Industry Compliance Assistance Center:  
<http://www.cicacenter.org/index.cfm>
4. The National Environmental Compliance Assistance Clearinghouse:  
<http://cfpub.epa.gov/clearinghouse/>

#### **1.5 SUBMITTALS**

A. In accordance with Section, 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, the Contractor shall furnish the following:

1. Environmental Protection Plan: After the contract is awarded and prior to the commencement of the work, the Contractor shall meet with the Contracting Officer to discuss the proposed Environmental Protection Plan and to develop mutual understanding relative to details of environmental protection. Not more than 20 days after the meeting, the Contractor shall prepare and submit to the Contracting Officer for approval, a written and/or graphic Environmental Protection Plan including, but not limited to, the following:
  - a. Name(s) and qualifications of person(s) within the Contractor's organization who is (are) responsible for:
    - i. ensuring adherence to the Environmental Protection Plan.
    - ii. Manifesting hazardous waste to be removed from the site.
    - iii. Training the Contractor's environmental protection personnel.
    - iv. Performing site inspections and preparing site inspection reports as required by the Missouri Department of Natural Resources' general land disturbance permit.
  - b. Description of the Contractor's environmental protection personnel training program.
  - c. A list of Federal, State, and local laws, regulations, and permits concerning environmental protection, pollution control, noise control and abatement that are applicable to the Contractor's proposed operations and the requirements imposed by those laws, regulations, and permits.
  - d. Methods for protection of features to be preserved within authorized work areas including trees, shrubs, vines, grasses, ground cover, landscape features, air and water quality, fish and wildlife, soil, historical, and archeological and cultural resources.

#### **TEMPORARY ENVIRONMENTAL CONTROLS**

- e. Procedures to provide environmental protection that complies with the applicable laws and regulations. Describe the procedures to correct pollution of the environment due to accident, natural causes, or failure to follow the procedures as described in the Environmental Protection Plan.
  - f. Permits, licenses, and the location of the solid waste disposal area.
  - g. Drawings showing locations of any proposed temporary excavations or embankments for haul roads, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials. Include as part of an approved Erosion Control Plan.
  - h. A list of selected temporary and permanent best management practices (BMPs) called for in the Erosion Control Plan and SWPPP notes including:
    - i. A physical description of the BMP.
    - ii. Site and physical site conditions that must be met for effective use of the BMP.
    - iii. Installation/construction procedures for each BMP.
  - i. A list of specific instances of BMP's as called for in the Erosion Control Plan and SWPPP notes including:
    - i. Whether a specific BMP is temporary or permanent.
    - ii. Where in relation to other site features, the BMP is to be located.
    - iii. When the BMP will be installed in relation to each phase of the land disturbance procedures to complete the project.
    - iv. Site conditions that must be met before removal of the BMP if the BMP is not permanent.
  - j. A site map or maps defining the sloped areas for all phases of the project meeting the requirements of the Missouri Department of Natural Resources' General Land Disturbance Permit.
  - k. Environmental Monitoring Plans for the job site including land, water, air, and noise.
  - l. Work Area Plan showing the proposed activity in each portion of the area and identifying the areas of construction limits or protected areas. Plan should include measures for marking the limits of use areas. This plan may be incorporated within the Erosion Control Plan.
- B. Within 20 days after the date of its submittal, the Contracting Officer shall approve the Contractor's Comprehensive Environmental Protection Plan, or respond with an explanation for its rejection and resubmittal.

TEMPORARY ENVIRONMENTAL CONTROLS

- C. Approval of the Contractor's Environmental Protection Plan will not relieve the Contractor of responsibility for adequate and continued control of pollutants and other environmental protection measures.

#### **1.6.PROTECTION OF ENVIRONMENTAL RESOURCES**

- A. Protect environmental resources within the project boundaries and those affected outside the limits of permanent work during the duration of this contract. Confine construction activities to areas defined by construction limits, the specifications and drawings.
- B. Protection of Land Resources: Prior to construction, identify all land resources to be preserved within the work area. Do not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, top soil, land forms, wetlands or wetland buffers without prior approval from the Contracting Officer. Do not fasten or attach ropes, cables, or guys to trees for anchorage unless specifically authorized, or dictated by special emergency use.
1. Work Area Limits: Prior to any construction, mark/fence/protect the areas that require work to be performed under this contract. Mark/fence/protect monuments, works of art, and markers prior to construction. Convey to all personnel the purpose of marking and protecting all marked and protected objects.
  2. Protection of Specific Regulated Elements: Wetlands and wetland buffers and other landscape features shown on the drawings to be preserved by marking, fencing, or using any other approved protective techniques.
    - a. Protect trees and shrubs to remain on site to protect from damage per contract details.
    - b. All damage to existing trees and shrubs shall be immediately repaired by trimming, cleaning, and painting with antiseptic tree paint.
    - c. Do not store building materials or perform construction activities closer to existing trees or shrubs than the farthest extension of their limbs.
  3. Reduction of Exposure of Unprotected Erodible Soils: Plan and conduct earthwork to minimize the duration of exposure of unprotected soils. Clear areas only as needed to use to work the area to be developed. Form earthwork to final grade as shown as quickly as possible to minimize potential erosion damage. Immediately protect side slopes and back slopes upon completion of rough grading or clearing with appropriate material as defined in the Erosion Control Plan and SWPPP notes.

#### **TEMPORARY ENVIRONMENTAL CONTROLS**

4. Temporary Protection of Disturbed Areas: Construct diversion ditches, benches, check dams and berms to retard and divert runoff from the construction site to protected drainage areas as intended under paragraph 208 of the Clean Water Act.
    - a. Sediment Basins: Trap sediment from construction areas in temporary or permanent sediment basins that accommodate the runoff of a local (design year) storm. After each storm, pump the basins dry and remove the accumulated sediment. Control overflow/drainage with paved weirs or by vertical overflow pipes, draining from the surface.
    - b. Reuse or conserve the collected topsoil sediment as directed by the Contracting Officer. Topsoil use and requirements are specified in Section 31 20 00, EARTH MOVING.
    - c. Institute effluent quality monitoring programs as required by Federal, State, and local environmental agencies.
  5. Erosion and Sedimentation Control Devices: Construct or install all temporary and permanent erosion and sedimentation control features shown on the contract documents and called for in the Erosion Control Plan and SWPPP notes. Maintain temporary erosion and sediment control measures such as silt fence, sedimentation basins, grassing, and mulching, until permanent drainage and erosion control facilities are completed and operative.
  6. Manage and control borrow and spoil areas on Government property to minimize erosion and to prevent soil and/or sediment from leaving the project area.
  7. Protect adjacent areas from despoilment by temporary excavations and embankments.
  8. Handle and dispose of solid wastes in such a manner that will prevent contamination of the environment. Place solid wastes (excluding clearing debris) in containers that are emptied on a regular schedule. Transport all solid waste off Government property and dispose of waste in compliance with Federal, State, and local requirements.
  9. Store chemical waste away from the work areas in corrosion resistant containers and dispose of waste in accordance with Federal, State, and local regulations.
  10. Handle discarded materials other than those included in the solid waste category as directed by the Contracting Officer.
- C. Protection of Water Resources: Keep construction activities under surveillance, management, and control to avoid pollution of surface and

TEMPORARY ENVIRONMENTAL CONTROLS

ground waters and sewer systems. Implement management techniques to control water pollution by the listed construction activities that are included in this contract.

1. Washing and Curing Water: Do not allow wastewater directly derived from construction activities to enter water areas. Collect and place wastewater in sediment basins prior to entering retention/detention ponds, allowing the suspended material to settle, the pollutants to separate, or the water to evaporate.
- D. Protection of Fish and Wildlife Resources: Keep construction activities under surveillance, management, and control to minimize interference with, disturbance of, or damage to fish and wildlife. Prior to beginning construction operations, list protected species that require specific attention along with measures for their protection.
- E. Protection of Air Resources: Keep construction activities under surveillance, management, and control to minimize pollution of air resources. Burning is not permitted on the job site. Keep activities, equipment, processes, and work operated or performed, in strict accordance with State Regulations and Federal emission and performance laws and standards. Maintain ambient air quality standards set by the Environmental Protection Agency, for those construction operations and activities specified.
  1. Particulates: Control dust particles, aerosols, and gaseous by-products from all construction activities, processing, and preparation of materials at all times, including weekends, holidays, and hours when work is not in progress.
  2. Particulates Control: Maintain all excavations, stockpiles, haul roads, permanent and temporary access roads, spoil areas, borrow areas, and all other work areas within or outside the project boundaries free from particulates which would cause a hazard or a nuisance. Sprinklering, chemical treatment of an approved type, light bituminous treatment, or other methods are permitted to control particulates in the work area as approved in the Environmental Protection Plan.
  3. Hydrocarbons and Carbon Monoxide: Control monoxide emissions from equipment to Federal and State allowable limits.
  4. Odors: Control odors of construction activities and prevent obnoxious odors from occurring.
- F. Noise Control: Minimize noise using every action possible. Perform noise-producing work in less sensitive hours of the day or week as

TEMPORARY ENVIRONMENTAL CONTROLS

directed by the Contracting Officer. Maintain noise-produced work at or below the decibel levels and within the time periods specified.

1. Perform construction activities involving repetitive, high-level impact noise only between 8 a.m. and 6 p.m unless otherwise permitted by local ordinance or the Contracting Officer. Repetitive impact noise on the property shall not exceed the following dB limitations:

Time Duration of Impact Noise	Sound Level in dB
More than 12 minutes in any hour	70
Less than 30 seconds of any hour	85
Less than three minutes of any hour	80
Less than 12 minutes of any hour	75

2. Provide sound-deadening devices on equipment and take noise abatement measures that are necessary to comply with the requirements of this contract, consisting of, but not limited to, the following:
  - a. Maintain maximum permissible construction equipment noise levels at 15 m (50 feet) (dBA):

EARTHMOVING		MATERIALS HANDLING	
FRONT LOADERS	75	CONCRETE MIXERS	75
BACKHOES	75	CONCRETE PUMPS	75
DOZERS	75	CRANES	75
TRACTORS	75	DERRICKS IMPACT	75
SCAPERS	80	PILE DRIVERS	95
GRADERS	75	JACK HAMMERS	75
TRUCKS	75	ROCK DRILLS	80
PAVERS, STATIONARY	80	PNEUMATIC TOOLS	80
PUMPS	75	BLASTING	NOT ALLOWED
GENERATORS	75	SAWS	75
COMPRESSORS	75	VIBRATORS	75

- b. Provide soundproof housings or enclosures for noise-producing machinery to meet the requirements of this section.
  - c. Use efficient silencers on equipment air intakes.
  - d. Use efficient intake and exhaust mufflers on internal combustion engines that are maintained so equipment performs below noise levels specified.
  - e. Line hoppers and storage bins with sound deadening material.
  - f. Conduct truck loading, unloading, and hauling operations so that noise is kept to a minimum.

#### TEMPORARY ENVIRONMENTAL CONTROLS



3. Measure sound level for noise exposure due to the construction at least once every five successive working days while work is being performed above 75 dB(A) noise level. Measure noise exposure at the property line or 15 m (50 feet) from the noise source, whichever is greater. Measure the sound levels on the A weighted sound level of a General Purpose sound level meter at slow response. To minimize the effect of reflective sound waves at buildings, take measurements at 900 to 1800 mm (three to six feet) in front of any building face. Submit the recorded information to the Contracting Officer noting any problems and the alternatives for mitigating actions.
- G. Restoration of Damaged Property: If any direct or indirect damage is done to public or private property resulting from any act, omission, neglect, or misconduct, the Contractor shall restore the damaged property to a condition equal to that existing before the damage at no additional cost to the Government. Repair, rebuild, or restore property as directed or make good such damage in an acceptable manner.
- H. Final Clean-up: On completion of project and after removal of all debris, rubbish, and temporary construction, Contractor shall leave the construction area in a clean condition as approved by the Contracting Officer. Cleaning shall include off-cemetery disposal of all items and materials not required to be salvaged, as well as all debris and rubbish resulting from demolition and new work operations, clearing, logging and general construction in accordance with state and local regulations and the contract.

- - - E N D - - -