

SECTION 04 05 13
MASONRY MORTARING

PART 1 - GENERAL

1.1 DESCRIPTION:

Section specifies mortar materials and mixes. Exposed panels joints in Limestone are sealant. Coordinate mortar installation to allow installation of sealant.

1.2 RELATED WORK:

- A. Mortar used in Section:
 - 1. Section 04 43 00, NATURAL STONE VENEER.
 - 2. Section 04 72 00, CAST STONE MASONRY.
 - 3. Section 07 92 00, JOINT SEALANT.

1.3 TESTING LABORATORY-CONTRACTOR RETAINED

- A. Engage a commercial testing laboratory approved by CONTRACTING OFFICER to perform tests specified below.
- B. Submit information regarding testing laboratory's facilities and qualifications of technical personnel to CONTRACTING OFFICER.

1.4 TESTS

- A. Test materials proposed for use for compliance with specifications in accordance with test methods contained in referenced specifications and as follows:
- B. Mortar:
 - 1. Test for compressive strength and water retention; ASTM C270.
 - 2. Mortar compressive strengths 28 days as follows:
 - Type M: Minimum 17230 kPa (2500 psi) at 28 days.
 - Type S: Minimum 12400 kPa (1800 psi) at 28 days.
 - Type N: Minimum 5170 kPa (750 psi) at 28 days.
- C. Cement:
 - 1. Test for water soluble alkali (nonstaining) when nonstaining cement is specified.
 - 2. Nonstaining cement shall contain not more than 0.03 percent water soluble alkali.
- D. Sand: Test for deleterious substances, organic impurities, soundness and grading.

1.5 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Certificates:
 - 1. Testing laboratory's facilities and qualifications of its technical personnel.

2. Indicating that following items meet specifications:

- a. Portland cement.
- b. Masonry cement.
- c. Mortar cement.
- d. Hydrated lime.
- e. Fine aggregate (sand).
- f. Color admixture.

C. Laboratory Test Reports:

- 1. Mortar, each type.
- 2. Admixtures.

D. Manufacturer's Literature and Data:

- 1. Cement, each kind.
- 2. Hydrated lime.
- 3. Admixtures.
- 4. Liquid acrylic resin.

1.6 PRODUCT DELIVERY, STORAGE AND HANDLING

- A. Deliver masonry materials in original sealed containers marked with name of manufacturer and identification of contents.
- B. Store masonry materials under waterproof covers on planking clear of ground, and protect damage from handling, dirt, stain, water and wind.

1.7 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of specification to extent referenced. Publications are referenced in text by basic designation only.
- B. American Society for Testing and Materials (ASTM):
 - C40-04.....Organic Impurities in Fine Aggregates for
Concrete
 - C91-05.....Masonry Cement
 - C109-07.....Compressive Strength of Hydraulic Cement Mortars
(Using 2-in. or 50-MM Cube Specimens)
 - C144-04.....Aggregate for Masonry Mortar
 - C150-05.....Portland Cement
 - C207-06.....Hydrated Lime for Masonry Purposes
 - C270-07.....Mortar for Unit Masonry
 - C595-08.....Blended Hydraulic Cement
 - C780-07.....Preconstruction and Construction Evaluation of
Mortars for Plain and Reinforced Unit Masonry
 - C979-05.....Pigments for Integrally Colored Concrete
 - C1329-05.....Mortar Cement

PART 2 - PRODUCTS

2.1 HYDRATED LIME

ASTM C207, Type S.

2.2 AGGREGATE FOR MASONRY MORTAR

A. ASTM C144 and as follows:

1. Light colored sand for mortar for laying face brick.
2. White plastering sand meeting sieve analysis for mortar joints for pointing and laying of structural facing tile units except that 100 percent passes No. 8 sieve, and not more than 5 percent retained on No. 16 sieve.

B. Test sand for color value in accordance with ASTM C40. Sand producing color darker than specified standard is unacceptable.

2.3 BLENDED HYDRAULIC CEMENT

ASTM C595, Type IS, IP.

2.4 MASONRY CEMENT

A. ASTM C91. Type S.

2.5 MORTAR CEMENT

ASTM C1329, Type S.

2.6 PORTLAND CEMENT

A. ASTM C150, Type I.

2.7 LIQUID ACRYLIC RESIN

A formulation of acrylic polymers and modifiers in liquid form designed for use as an additive for mortar to improve physical properties.

2.8 WATER

Potable, free of substances that are detrimental to mortar, masonry, and metal.

2.9 POINTING MORTAR

A. For Cast Stone or Precast Concrete: Proportion by volume; One part white Portland cement, two parts white sand, and 1/5 part hydrated lime.

2.10 MASONRY MORTAR

A. Conform to ASTM C270.

B. Admixtures:

1. Do not use mortar admixtures, except color admixtures if approved by CONTRACTING OFFICER.
2. Submit laboratory test report showing effect of proposed admixture on strength, water retention, and water repellency of mortar.
3. Do not use antifreeze compounds.

C. Colored Mortar:

1. Maintain uniform mortar color for exposed work throughout.
2. Match mortar color in approved sample.

D. Color Admixtures:

1. Proportion as specified by manufacturer.

2.11 COLOR ADMIXTURE

- A. Pigments: ASTM C979.
- B. Use mineral pigments only. Organic pigments are not acceptable.
- C. Pigments inert, stable to atmospheric conditions, nonfading, alkali resistant and water insoluble.

PART 3 - EXECUTION

3.1 MIXING

- A. Mix in a mechanically operated mortar mixer.
 1. Mix mortar for at least three minutes but not more than five minutes.
- B. Measure ingredients by volume. Measure by the use of a container of known capacity.
- C. Mix water with dry ingredients in sufficient amount to provide a workable mixture which will adhere to vertical surfaces of masonry units.
- D. Mortar that has stiffened because of loss of water through evaporations:
 1. Re-tempered by adding water to restore to proper consistency and workability.
 2. Discard mortar that has reached its initial set or has not been used within two hours.

3.2 MORTAR USE LOCATION

- A. Use Type S mortar for setting cast and natural stone.

3.3 MORTAR JOINTS IN LIMESTONE PANELS

- A. All joints to receive sealant shall be as indicated on architectural drawings. Do not seal joints until they are in compliance with drawing, or meet with the approval of the architect.
 1. Joints to receive sealant and backing shall be a minimum of 3/8" wide
- B. Joints to receive sealant, backup material or preformed joint filler shall be cleaned out and raked to full width and depth as required by sealant contractor or others.

- - - E N D - - -