



1. REMOVE OR ABANDON MANHOLES AS SHOWN ON DRAWING. REMOVE SANITARY PIPE WITHIN 5' OF DEMOLISHED MANHOLE LOCATIONS. ABANDON REMAINING PIPE BY FILLING WITH FLOWABLE FILL AND BULKHEAD PIPE ENDS PER METROPOLITAN ST. LOUIS SEWER DISTRICT STANDARD SPECIFICATIONS.
2. TERMINATE PAVEMENT, SIDEWALK AND CURB REMOVAL AT JOINTS. WHERE POSSIBLE TO TERMINATE AT JOINT, FULL DEPTH SAWCUT MATERIAL TO PROVIDE A CLEAN, FINISHED EDGE TO MATCH INTO RECONSTRUCTION.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UTILITIES, ABOVE GROUND AND BELOW, SHOWN OR NOT SHOWN ON THESE DRAWINGS. CONTRACTOR SHALL ARRANGE FOR UTILITY LOCATES PRIOR TO DEMOLITION ACTIVITIES. NOTE THAT UTILITIES WITHIN THE CEMETERY MAY NOT BE MARKED BY "ONE-CALL" SERVICES. THE CONTRACTOR SHALL EMPLOY A PRIVATE LOCATE SERVICE TO MARK THESE PRIVATE UTILITIES INCLUDING THE UNDERGROUND ELECTRICAL SERVICE FEEDING THE FENCE COLUMN LIGHTING.
4. REMOVAL SHALL INCLUDE REMOVAL & DISPOSAL OFF-SITE OF ALL DEMOLISHED MATERIALS.
5. DEMOLITION TO OCCUR IN PHASES TO MINIMIZE DISRUPTION TO CEMETERY OPERATIONS. SEE PHASING PLANS FOR ADDITIONAL INFORMATION.

Know what's below,
Call before you dig.

I HEREBY CERTIFY THAT THIS PROFESSIONAL INVESTIGATION, OR REPORT WAS
PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION AND THAT I AM
A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE
STATE OF MISSOURI.
PRINT NAME: GARY R. JOHNSON, P.E.
SIGNATURE: [Signature]
DATE March 28, 2005 QUAL. ENGINEER P.E. 20120053

Anderson Engineering of Minnesota, LLC
13605 1st Avenue North
Suite 100
Plymouth, MN 55441
763-412-4000 (o) 763-412-4090 (f)
www.ae-mn.com

L-6

 Department of
Veterans Affairs