



1. GRADING CONTRACTOR SHALL VERIFY LOCATIONS AND ELEVATIONS OF ALL UNDERGROUND UTILITIES WITH THE RESPECTIVE UTILITY COMPANIES.

2. ALL EROSION CONTROL MEASURES CALLED FOR ON THESE PLANS AND SPECIFICATIONS, WHICH MAY INCLUDE SILT FENCE, SEDIMENTATION BASINS OR TEMPORARY SEDIMENT TRAPS, SHALL BE CONSTRUCTED AND SERVICABLE PRIOR TO CONSTRUCTION IN THE FOLLOWING ORDER:

- A. ROCK CONSTRUCTION ENTRANCES.
- B. SILT FENCE.
- C. BOD-ROLLS.
- D. TEMPORARY SEDIMENTATION BASINS AND OUTFALL FACILITIES.
- E. STORM WATER POND CONSTRUCTION.
- F. COMMON EXCAVATION AND EMBANKMENT (GRADING).
- G. SEED AND MULCH OR SOG.
- H. BO-ROLL BARRIERS IN FINISHED GRADED AREAS.
- I. INLET AND OUTFALL FACILITIES SUBSEQUENT TO STORM SEWER WORK.

3. GRADING CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE CITY AND NDES PHASE II PERMITTING REQUIREMENTS AS WELL AS ALL EROSION CONTROL MEASURES AS MAY BE SHOWN ON THESE PLANS OR SPECIFICATIONS. GRADING CONTRACTOR SHALL IMPLEMENT ANY ADDITIONAL EROSION CONTROL MEASURES AS MAY BE REQUIRED TO PROTECT ADJACENT PROPERTY.

4. ALL EROSION CONTROL FACILITY SHALL BE MAINTAINED BY THE GRADING CONTRACTOR. ANY EROSION OPERATIONS, ANY EROSION FACILITIES WHICH ARE TO BE REMOVED AS CALLED FOR ON THESE PLANS AND SPECIFICATIONS SHALL BE MAINTAINED BY THE GRADING CONTRACTOR UNTIL THE GRADING CONTRACTOR'S ENGINEER, THE GRADING CONTRACTOR SHALL THEN RESTORE THE SUBSEQUENTLY DISTURBED AREA IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS.

5. GRADING CONTRACTOR SHALL SCHEDULE THE SOGS ENGINEER SO THAT CERTIFICATION OF ALL CONTROLLED FILLS WILL BE FURNISHED TO THE OWNER DURING AND UPON COMPLETION OF THE PROJECT.

6. ALL GRADING AREAS, EXCEPT AREAS TO BE PAVED AND/OR SPECIFICALLY DESIGNED BY A LANDSCAPE ARCHITECT, SHALL BE COVERED WITH A MINIMUM 4" OF TOP SOIL. ALL DISTURBED AREAS SHALL BE SEEDED & MULCHED WITHIN 14 DAYS WITHIN 14 DAYS OF COMPLETION OF THE GRADING WORK.

7. ALL EXPOSED SOIL AREAS WITH A CONTINUOUS POSITIVE SLOPE WITHIN 200 LINEAL FEET OF ANY SURFACE WATER, MUST HAVE TEMPORARY EROSION PROTECTION OR PERMANENT COVER FOR THE EXPOSED SOILS EACH YEAR ROUND, WITHIN 7 DAYS OF COMPLETION OF THE GRADING WORK.

8. CONTRACTORS GRADING AND EROSION CONTROL OPERATIONS SHALL TAKE PLACE WITHIN THE CONSTRUCTION LIMITS.

9. IT IS REQUIRED THAT SOILS TRACKED FROM THE SITE BY MOTOR VEHICLES BE CLEANED DAY FROM PAVED ROADWAY SURFACES THROUGHOUT THE DURATION OF CONSTRUCTION.

10. PROVIDE TEMPORARY SEDIMENTATION BASINS AS DIRECTED BY THE ENGINEER.

11. ALL REQUIREMENTS OF THE LOCAL WATERSHED DISTRICT SHALL BE SATISFIED PER THE APPROVED PERMIT.

12. DETERMINING AND/OR BASIN DRAINING DISCHARGE SHALL BE DIRECTED TO SEDIMENTATION BASINS WHEREVER POSSIBLE. SEDIMENTATION PONTS SHALL BE ADEQUATELY PROTECTED FROM EROSION & SCOUR THROUGH USE OF APPROVED EROSION DISSIPATION DEVICES.

13. ALL SOLID WASTE/ CONSTRUCTION DEBRIS SHALL BE DISPOSED OF IN ACCORDANCE WITH LOCAL REQUIREMENTS. HAZARDOUS MATERIALS SHALL BE STORED/ DISPOSED OF IN COMPLIANCE WITH LOCAL REGULATIONS.

14. THE WORK TO MAINTAIN CONFORMANCE WITH THE CITY AND NPDES II PERMIT REQUIREMENTS, THIS WORK SHALL CONSIST OF OPERATIONS NECESSARY TO RAPIDLY STABILIZE SMALL CRITICAL AREAS, AND PREVENT EROSION OF SEDIMENTATION WITHIN THE WORK TRACK WITH TYPE 5 HYDRAULIC SOIL STABILIZER. THIS WORK SHALL BE COMPLETED WITHIN 7 DAYS OF THE OCCURRENCE OF THE DISTURBANCE. THIS WORK SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE MDD STANDARD SPECIFICATIONS, THE DETAILS SHOWN IN THE PLANS, AND THE FOLLOWING:

- METHOD ARE FIVE STABILIZATION METHODS APPLICABLE FOR THESE OPERATIONS. THESE METHODS MAY BE CONDUCTED INDEPENDENTLY OR IN COMBINATION.
- METHOD #1: APPLY TYPE 1 MULCH AND DISC ANCHOR
- METHOD #2: APPLY TYPE 1 MULCH AND TACK WITH TYPE 5 HYDRAULIC SOIL STABILIZER
- METHOD #3: HYDROSEED/SEED/FERTILIZER AND TYPE 6 HYDRAULIC SOIL STABILIZER
- METHOD #4: HAND SEEDING, FERTILIZER, AND TYPE 6 HYDRAULIC SOIL STABILIZER
- METHOD #5: PLACE GEOTEXTILE AND RIP RAP CLASS II IN VARIOUS CONFIGURATIONS

THESE EFFORTS WILL BE INCIDENTAL TO THE EROSION CONTROL BID ITEM.

15. CONTRACTOR SHALL PROVIDE A TEMPORARY SEDIMENTATION BASIN ON SITE FOR CONSTRUCTION WASH OUT USE. TEMPORARY BASIN SHALL BE LOCATED AS TO PROVIDE EASY ACCESS FOR CONSTRUCTION VEHICLES AND CONCRETE.

16. INLET SEDIMENTATION CONTROL IS TO BE PROVIDED TO ALL STORM SEWER CATCH BASINS THROUGHOUT CONSTRUCTION. MEASURES APPLIED SHALL COMPLY WITH LOCAL BEST MANAGEMENT PRACTICES AND NDES PHASE II PERMITTING REQUIREMENTS.

17. INSPECTION FREQUENCY - ACTIVE SITES: DAILY DURING STORM WATER OR SNOWMELT RUNOFF AND AT LEAST EVERY 7 DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES IN A 24-HOUR PERIOD. INSPECTIONS SHALL BE FOR EVIDENCE OF EROSION OR SEDIMENTATION. EROSION OR SEDIMENTATION SHALL NOT BE STABILIZED AND INSPECTED BEFORE LEAVING AN ACTIVE SITE.

NOTE: CONTRACTOR IS RESPONSIBLE FOR INSTALLATION, MAINTENANCE AND REMOVAL OF ALL APPLICABLE EROSION & SEDIMENT CONTROL ITEMS.

ARCHITECT/ENGINEERS:



EROSION CONTROL PLAN

Approved: Project Director

Project Title

SEWER RELOCATION

Location
ST. LOUIS, MO

Project Number
852CM3037

Drawing
Reference
Number

Drawing Number

L-7

P-0029720-00
BASE MAP 29H3

BID DOCUMENTS

Office of
Construction
and Facilities
Management



CONSULTANTS:

I HEREBY CERTIFY THAT THIS BLUE PRINT, SPECIFICATION, OR REPORT WAS
PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM
A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE
STATE OF MISSOURI.
PRINT NAME: GARY R. JOHNSON, P.E.

SIGNATURE: _____
DATE March 28, 2012 P.E. 2012005390

ENGINEERING • ARCHITECTURE • LAND SURVEYING
ENVIRONMENTAL SERVICES • LANDSCAPE ARCHITECTURE