



KEYED NOTES	
01	DUCTWORK SERVING AIR DUCT FROM INTERSTITIAL SPACE ABOVE. REFER TO M104 FOR CONTINUATION (TYPICAL FOR ALL AIR DEVICES).
02	PROVIDE "TSI--PRESSURA" PRESSURE MONITORING PANEL AND INCORPORATE TO ALARM BACKS IF THE ROOM BECOMES POSITIVELY PRESSURED. PROVIDE CONTROL VOLTAGE TRANSFORMER FOR MONITORING PANEL. COORDINATE EXACT LOCATIONS WITH ARCHITECT.
03	PROVIDE GREEN LIGHT AND RED LIGHT OUTSIDE OF ROOM AND INTERLOCK TO PRESSURE MONITORING PANEL TO VISUALLY ALARM STAFF IF THE PRESSURE OF THE ROOM BECOMES POSITIVE. COORDINATE LABELLING OF THE LIGHTS WITH OWNER. GREEN SHALL SIGNIFY NORMAL OPERATION AND RED SHALL ALARM. COORDINATE EXACT LOCATIONS WITH ARCHITECT.
04	REBALANCE EXISTING DIFFUSERS TO NEW CFM SHOWN.
05	REMOVED.

