

Statement of Work for Lead Based Paint Removal in Building 2

The contractor shall remove specified square footage of lead based paint and prime on the following floors of Building 2 and the Butler VA.

Basement 4830 SF Lead Based Paint

First Floor 120 SF Lead Based Paint, 594 LF Pucks

Second Floor 1358 SF Lead Based Paint, 746 LF Pucks

All work shall be completed IAW the attached specification No. 02 83 33.13. Lead based paint removed shall be disposed of in accordance with applicable Federal, State and Local Regulations. Surfaces shall be primed upon removal. The contractor shall supply all materials, ladders, scaffolding, etc. Air monitoring to be performed by others.

All work shall be performed during normal working hours, which is Monday – Friday, 8:00 AM – 4:00 PM, excluding federally observed holidays.

Attachments to the Statement of Work:

1. Specification No. 02 83 33.13
2. Building 2 Basement Drawing
3. Building 2 First Floor Drawing
4. Building 2 Second Floor Drawing