



AS BUILT-CHANGED ROOM NAMES

- NOTE:
1. R-13 UNFACED INSULATION IN ALL INT. WALLS
  2. ALL INTERIOR WALLS ARE DECK-TO-DECK.
  3. P.T. DISPENSER TO BE PLACED UP 44" A.F.F.
  4. SOAP DISPENSER TO BE PLACED UP 44" A.F.F.
  5. ADD 2x6 HORIZONTAL BLOCKING @ WALLS W/ HANDRAILS (UP 35" TO TOP).

SCHEDULE \ LEGEND

KEY	ITEM DESCRIPTION	SIZE	ROUGH OPENING
SC	36" X 80" STEELCRAFT W/ 12x12 PANE	36X80	40 1/2" X 82 1/2"
DSF	36" X 84" STOREFRONT BRONZE/TINTED	72X84	76" X 86"
M	36" X 80" MOHAWK - SOLID CORE	36X80	37 1/4" X 81"
M	48" X 80" MOHAWK - SOLID CORE	48X80	49 1/4" X 81"
M	32" X 80" MOHAWK - SOLID CORE	32X80	33 1/4" X 81"
M	42" X 80" MOHAWK - SOLID CORE	42X80	43 1/4" X 81"
B	20" X 44" RESTROOM - BRONZE/LOW E	20X44	24 1/2" X 52 1/2" UP 27 1/2"

THIS DRAWING IS PROPERTY OF AMTEX CORP. AND CANNOT BE DISTRIBUTED WITHOUT MANUFACTURERS CONSENT.

LTR	REVISION	BY	DATE

DATE:	12/2/10	SCALE:	1/16"=1'-0"	DWG. NO.	N112144-1	SHEET	A-2
DRAWN BY: M.L.S.		PROJECT: NORTON POLK		TITLE: FLOOR PLAN		MARK STEELE, P.E. 5139 N. TOM MURRAY AVE GLENDALE, AZ. 85301 P#: 602.385.2173	