



N.T.S.



- GENERAL NOTES:
1. A GROOVE JOINT 1/2" DEEP WITH 1/8" RADII SHALL BE REQUIRED IN THE CONCRETE SIDEWALK AT 6' INTERVALS. ONE 1/2" EXPANSION JOINT WILL BE REQUIRED AT EACH END.
  2. WIDTH OF SIDEWALKS TO BE 4' TO 8' OR TO MATCH EXISTING WIDTH.
  3. CONCRETE COMPRESSIVE STRENGTH SHALL BE 3000 PSI. IN 28 DAYS.



Department of  
Veterans Affairs