

**Addendum #3**  
**Project #516-336 Bay Pines VA Cancer Infusion Center**  
**04/26/2016**

This Addendum is made and hereby becomes a part of the Construction Documents for this project. It is to clarify some ambiguities found in the drawings and specs.

Clarifications to drawings and specifications:

1. Drawing PP1.2 note P115 states the 3" copper storm pipe is to extend through the floor and tie into the trench drain on the exterior of the connector. This is inaccurate; the 3" copper pipe shall be connected to the Civil Storm Lateral Piping.
2. Drawing PP.1.3 and on PP5.3 the medical gas outlets are shown being installed back-to-back in the Chemo Clinic. This is an accurate depiction of the design layout.
3. Drawing PP1.3 note P106 states that the med gas alarm panel is to have signal routed to Bldg. 100 Energy Center. Detail 2 on sheet E6.1 shows the alarm panel tie-in requirements.
4. On page 23-21-13-7, Division 23 Mechanical, PVC pre insulated pipe is specified. The pre-insulated PVC will be Schedule #80 as are the fittings. "Sticks & Kits" are acceptable for the fittings.
5. On specifications page 08 80 00-6, Part 2, section 2.1 C—"Exterior pane ASTM C1036, Type 1, Class 3, Quality q3, 6mm" should read for class as class 2, not class 3.

End of Addendum #3

