

three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
three eighths inch = one foot  
one half inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot

BUILDING SCHEDULE		BUILDING SCHEDULE	
NO	NAME	NO	NAME
2	DORMITORY	150	DIETETICS
3	DUPLEX QUARTERS	151	GAS METER HOUSE
4	DUPLEX QUARTERS	152	RESERVOIR "IRRIGATION"
5	DUPLEX QUARTERS	153	CHLORINATOR HOUSE
11	DUPLEX QUARTERS	154	HOSPITAL
12	DUPLEX QUARTERS	154A	OUT PATIENT ADDITION
13	DUPLEX QUARTERS	156	BULK OXYGEN STORAGE
14	SINGLE QUARTERS	155	GENERATOR HOUSE
15	POWDER MAGAZINE	157	HIGH VOLTAGE SWITCH GEAR
16	FIRE STATION	158	GENERATOR HOUSE
17	WAREHOUSE	159	GENERATOR HOUSE
20	ENGR. SHOPS	160	BOOSTER PUMP HOUSE
31	ENGR. WAREHOUSE	161	WELL VALVE HOUSE
35	MANAGERS QUARTERS	162	RESERVOIR "DOMESTIC WATER"
41	SINGLE QUARTERS	604	GARAGE
42	SINGLE QUARTERS	163	DOMESTIC WATER METER VAULT
43	SINGLE	164	IRRIGATION VALVE VAULT
47	SUPPLY STORAGE	165	PRV VAULT
52	FLAG POLE & MEMORIAL	166	HAZARDOUS WASTE
54	MISC. STORAGE	167	VBA REGIONAL OFFICE BLDG
141	ADMINISTRATION BUILDING	168	LIBERTY HOUSE
142	HEATING PLANT	169	INPATIENT MENTAL HEALTH UNIT
144	7-CAR GARAGE	170	AMM WAREHOUSE
145	SINGLE GARAGE	171	BOILER PLANT
146	7-CAR GARAGE		

Legend	
Green	New Road Construction
Orange	Overlay (1.5"-2"min) Mill Ends To Existing
Red	Crack Seal & Chip Seal
Magenta	Patch & Repair Pavement
Blue	Demo Existing Road, curb, and sidewalk
Dark Blue	Add ADA Sidewalk, Ramps and Parking Spaces

- 9
- New GSA Lot
- 5" pit run and 3" crushed base gravel
  - 2" asphalt compacted depth
  - 100' x 80'

- 1
- New four HC Spots with sidewalks, ramps, and curbs

- 1
- New Storm Drain Inlet (4-6)
  - Connect to new retention pond

10

New Bike Road

General Notes

- PRIORITIES LISTED 1 - 10
- RESEED ALL AREAS TO MATCHING EXISTING
- ALL ASPHALT COMPACTED TO DEPTH THICKNESS
- SWEEP AND CLEAN ALL CHIP SEALED SURFACES PRIOR TO RESTRIPIING ASPHALT.
- INSTALL NEW ROAD, ADA, AND PARKING SIGNS AND RELOCATE ALL INFORMATION SIGNS IN CONSTRUCTION AREAS.
- NEW ROAD RADIUS ARE 40' RADIUS MIN. AT THE INTERSECTION OF HONOR DRIVE AND HERO ROAD AND ROAD X, ROAD Y, AND PATRIOTS WAY
- CONTRACTOR RESPONSIBLE TO REMOVE ALL TREES AND VEGETATION AS REQUIRED.
- REPAIR ALL DAMAGE IRR LINES IN CONSTRUCTION ZONE
- NEW LED LIGHTING FOR PARKING LOT (I)
- RECONFIGURE VBA PARKING LOT AS REQUIRED

VA MONTANA HEALTHCARE SYSTEM FORT HARRISON, MONTANA

Drawing Title

ROADS BID SCHEDULE

Project Title

FORT HARRISON IMPROVE PATIENT ACCESS THROUGH UPGRADE TO ROADS

Project Number

436-16-101

Office of Construction and Facilities Management

Project Director

ROY STEINER, PROJECT ENGINEER  
VAMC FORT HARRISON

Location

FORT HARRISON, MONTANA

Drawing Number

RBS101

Department of Veterans Affairs

Date

02/17/2016

Checked

J.M.

Drawn

J.M.

Dwg. 1 of 1