

Amendment A00001 **SOW**. See underlined for changes:

1. CLIN 001e PCC Spindles

- a. Provide all materials and labor for the following item:
 - a. Remove and replace 22 spindles with new identical PCC spindle.
 - i. Spindle shall be installed in a similar manner as existing spindle.
- b. Basis of design – PCC Balustrade Design by Sandstone Inc. – BL-06
 - a. Any spindles removed that are in acceptable condition, shall be returned to the VA as government owned property to be used as spares in the future. Spindles damaged beyond reuse shall be disposed of by the contractor.
 - b. Replace any PCC Top Caps that are damaged during spindle removal process
 - i. Basis of design – PCC Top Rail by Sandstone Designs by Sandstone Inc. – WC-38
- c. Contractor shall submit product information for Government approval prior to work.

2. CLIN 001f Square Pilaster

- a. Provide all materials and labor for the following item:
 - a. Remove and replace 17 square pilasters with new identical PCC pilaster.
 - i. Pilaster shall be installed in a similar manner as existing pilaster.
 - b. Replace any PCC Top Caps that are damaged during spindle removal process
- b. Contractor shall submit product information for Government approval prior to work.