

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

REPLACE VALVE BOX. TYP. (SEE STANDARD VALVE BOX DETAIL)

LIGHT POLE (TYP)

REPLACE EXISTING CATCH BASIN AND CONNECT TO EXISTING STORM SEWER LINE WITH 4" SCH. 40 P.V.C. (SEE CATCH BASIN DETAIL)

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

PAINT ALL LINE STRIPPING, SPACE NUMBERS AND DIRECTIONAL ARROWS WHITE.

PAINT ALL HANDICAP LINE STRIPPING, SPACE NUMBERS AND SYMBOLS BLUE ACCORDING TO HANDICAP PARKING LINE STRIPPING DETAIL

REMOVE EXISTING AND INSTALL NEW POST AND HANDICAP PARKING SIGNS FOR SPACES 16 THROUGH 21. SPACE 21 WILL ALSO HAVE A VAN ACCESSIBLE SIGN.

REMOVE 12' X 12' CONCRETE PAD AND SURROUNDING FENCE AND INSTALL NEW 8' X 24' CONCRETE PAD PER CONCRETE DETAIL AND PAINT EIGHT (8) PARKING SPACES LABELED M1 - M8 FOR MOTORCYCLE PARKING. ALSO INSTALL FOUR (4) MOTORCYCLE PARKING SIGNS AND POST.

BUILDING 138 PARKING LOT:

Approved: Medical Center Director
Mark Murdock

Approved: Medical Center Assoc. Director
Jay Miller

Approved: Engineering Department
Daniel A. Martin

Drawing Title

BUILDING 138
PARKING LOT DETAIL

Approved: Project Director

Project Title

REPAIR ROADS, CATCH
BASINS AND OTHER
UNDERGROUND STRUCTURES

Location

MARION, IN

Date

11/25/2015

Checked

D. MARTIN

Drawn

Z. MCDANIEL

Project Number

610-11-114

Building Number

VARIOUS


Drawing Number

15-110M

Dwg. 4 of 12



= VALVE BOX REPLACEMENT LOCATION



= CATCH BASIN LOCATION