



REMOVE EXISTING AND INSTALL NEW POST AND GOVERNMENT VEHICLES ONLY SIGNS FOR SPACES 91 THROUGH 92.

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

INSTALL NEW POST AND "NO TRUCKS" SIGN AT NORTH END OF ROAD.

REMOVE EXISTING AND INSTALL NEW POST AND HANDICAP PARKING SIGN FOR SPACE 1. PARKING SPACE 1 SHALL ALSO HAVE A VAN ACCESSIBLE SIGN.

PAINT ALL LINE STRIPPING AND SPACE NUMBERS WHITE

REMOVE ISLAND AND REPLACE CURB AND INSTALL FULL DEPTH ASPHALT. ADJUST SPACE NUMBER SEQUENCE TO ACCOMMODATE

REMOVE EXISTING AND INSTALL NEW POST AND HANDICAP PARKING SIGNS FOR SPACES 21 THROUGH 26.

PAINT ALL HANDICAP LINE STRIPPING, SPACE NUMBERS AND SYMBOLS BLUE ACCORDING TO HANDICAP PARKING LINE STRIPPING DETAIL

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

REMOVE ISLAND AND REPLACE CURB AND INSTALL FULL DEPTH ASPHALT. ADJUST SPACE NUMBER SEQUENCE TO ACCOMMODATE

REMOVE ISLAND AND INSTALL FULL DEPTH ASPHALT. ADJUST SPACE NUMBER SEQUENCE TO ACCOMMODATE

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

INSTALL NEW POST AND "NO TRUCKS" SIGN.

BUILDING 172 PARKING LOT:

Approved: Medical Center Director  
Mark Murdock

Approved: Medical Center Assoc. Director  
Jay Miller

Approved: Engineering Department  
Daniel A. Martin

Drawing Title

BUILDING 172  
PARKING LOT DETAIL

Approved: Project Director

Project Title

REPAIR ROADS, CATCH  
BASINS AND OTHER  
UNDERGROUND STRUCTURES

Location

MARION, IN

Date

11/25/2015

Checked

D. MARTIN

Drawn

Z. MCDANIEL

Project Number

610-11-114

Building Number

VARIOUS

Drawing Number

15-110M

Dwg. 5 of 12

